



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
A	Part-1				
1	Demolition of brick work & stone masonry with any type of plaster, paint, skirting, dedo etc. including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (III) In cement mortar.	100.00	Cu.mt	0.00	0.00
2	Demolition of any type of R.C.C work with TMT bars, any type of plaster, paint, skirting, dedo etc. including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (I) R.C.C work.	2.00	Cu.mt	0.00	0.00
3	Dismantling all type of tiles flooring, or stone flooring laid in mortar, any type of flooring with mortar, waterproofing, including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	1645.00	Sqm	0.00	0.00
4	Dismantling all type of wall tiles, dedo and any type of (stone/ tiles) clading laid in mortar, any type of flooring with mortar, waterproofing, including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	368.00	Sqm	0.00	0.00
5	Dismantling any type of doors, windows, ventilators etc. (wood of steel) shutters with chowkhats, architraves, holdfasts, any type of frame and other attachments etc complete and stacking them within all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (i) Not exceeding 3 Sq.M in area	186.00	Each	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
6	Dismantling any type of doors, windows, ventilators etc. (wood of steel) shutters with chowkhats, architraves, holdfasts, any type of frame and other attachments etc. work complete and stacking them within all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (II) Exceeding 3 Sq.M in area	2.00	Each	0.00	0.00
7	Removing dry or oil bound distemper, all type of paint and texture paint by a washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete. work complete and stacking them within all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	5186.00	Sqm	0.00	0.00
8	Dismantling of any type of roofing sheet including ridges, Hips, Valleys, Gutters, fabrication, framing, fastener etc. stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (i) G.I. or all type of sheet roofing.	5.00	Sqm	0.00	0.00
9	Remove of existing Fabrication and steel structure including plates, rolled steel joists, channels, angles and all type of accessories etc. including stacking of the materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. work completed as per existing site conditions work complete as per the instruction of EIC.	1106.00	KG	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
10	Remove of existing sanitary fittings & vessals like basin counter, wash basin, w.c. pan, Indian and Europeon type flushing tank, all type of cock, accessories, all pipe, terrace's services pipeline etc. including stacking of the materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. work completed as per existing site conditions work complete as per the instruction of EIC.	19.00	Per Toilet	0.00	0.00
11	Earthwork in excavation by mechanical means (All type of soil) for foundation, footings, walls, retaining walls, rafts, trenches, drains, lift pits, underground sumps, tank, septic tanks, soak well, Box cutting etc. including dewatering the sub-soil water from any source and rain water to keep the excavation dry, removal of slush, dressing of sides and ramming of bottoms, planking, shoring & strutting, removal & disposal of surplus excavated material with all lead & lift. including compaction by using mechanical plate compactor / vibro roller, finished to desire levels all as per excavation plan and foundation drawings to get Modified Proctor Density test (MPD) of 95%., work including mechanical transport inclusive of royalty, statutory fees all permissions & any other incidental expenses etc. complete. i) Up to 1.5 Mtr Depth	31.00	Cu.mt	0.00	0.00
12	Filling available excavated earth in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering. Rate to include cost of compaction to achieve at least 95% Proctor Density of refilled excavated earth. Work shall complete as per the instruction of EIC. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	20.00	Cu.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
13	Earth Filling with murrum or approved quality earth in below flooring, sides of foundation, retaining wall, trenches, lift pits elsewhere directed in layers of not exceeding 150 mm thick including breaking clods, watering, compacting each layer with vibratory compactor and at inaccessible places with wooden/steel rammers to achieve 90-95% proctor density at optimum moisture content, all leads & lifts. Bailing/pumping out of water to keep site dry while back filling ,Cost shall include conveyance of all materials, labor, machinery etc. complete(only good yellow soil/ muurum to be used for filling) Work shall complete as per the instruction of EIC. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	31.00	Cu.mt	0.00	0.00
14	Filling in plinth with sand under floors including watering ramming, consolidating and dressing complete. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	16.00	Cu.mt	0.00	0.00
15	Providing and filling any thk. dry rubble stone packing under floor, foundation, steps, ramps, road & other similar locations, hand set vertically in regular lines, interstices filled in with smaller stone chips including watering & consolidating & finishing to the required levels & lines etc. with the use of 10 ton roller on with mechanical rammer & with manual tampering only at location where mechanical rammer cannot be moved complete as directed. with Binding layer shall be of metal and voids to be filled with sand/ quarry spalls. work shall complete as per the instruction of EIC.	4.00	Cu.mt	0.00	0.00
16	Filling, with good quality Cinder, as and where directed by the Architect & EIC, in sunk and other required area in layers of required thickness, including watering, ramming, consolidating well etc. complete, as directed. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	1.00	Cu.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
17	Providing and laying cement concrete 1:4:8 (1- Cement : 4- coarse sand : 8- hand broken stone aggregates 40 mm nominal size) and curing complete. including mixing laying, vibrating, consolidating, leveling and curing etc. complete with all labours and materials with formwork. The item includes finishing the top surface with trowel. Work complete including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (A) Foundation and Plinth	14.00	Cu.mt	0.00	0.00
18	Providing and laying in position Ready Mixed M-250 grade concrete for reinforced cement concrete work , using cement content as per approved Design Mix manufactured in fully automatic batching plant and transported to site of work in transit mixer for a lead up to 10 kms having continuous agitated mixer, manufactured as per mix design of specified grade for reinforced cement concrete work including pumping of R.M.C. from transit mixer to site of laying, excluding the cost of centering shuttering finishing and reinforcement including cost of admixtures in recommended proportions as per IS: 9103 to accelerate/ retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer - in - charge. Without Fly Ash (Min cement level as per latest IS 456 shall be maintained) (Cement level 450 kg)	4.00	Cu.mt	0.00	0.00
19	TMT Bars: Providing, straightening, cutting, bending, binding and laying in position of TMT FE 500/500D grade steel reinforcement conforming to IS 1786 : 1990 or latest code, to correct all shape and size as per detailed drawings, specifications for all RCC work etc, at all levels and all heights with necessary chairs and laps; with correct size PVC cover blocks or approved quality concrete cover blocks of same grade of concrete and binding wire of 18 gauge etc. complete with test certificate of the steel bars from manufactures as well as approved laboratory test certificates directed by Engineer in charge, etc. complete. Rate shall be inclusive of binding wire, cover, lap, chair etc. Work shall complete up to any levels, all floor & as per the instruction of EIC.	378.00	kg	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
20	Form work: Providing and erecting in position form work shuttering & boxing using steel / plywood / props / bracing / scaffolding / ledges and other shuttering materials of approved quality for concrete elements vertical, horizontal or inclined etc. in all shapes as per drawing including necessary scaffolding, bolts/nuts, fastener nails, wires for keeping in position till concrete is laid and concrete have acquired required strength, removal thereafter, applying shuttering oil, hacking etc. in line, level and plumb, all complete as per specification or as directed. At all levels below ground level and up to highest plinth level for all concrete elements of linear shape, size & direction etc., work shall complete up to any levels, all floor & as per the instruction of EIC.	28.00	Sq.mt	0.00	0.00
21	Providing & laying any thick Brick Masonry work using common burnt clay building bricks having crushing strength not less than 35 Kg/Sq. Cm. at all levels in cement mortar 1:6 (1 cement :6 fine sand) - including proper filling of all masonry joints, curing etc. complete. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC. (II) Conventional brick work	42.00	Cu.mt	0.00	0.00
22	Providing and laying Half brick masonry in common burnt clay building bricks having crushing strength not less than 35 Kg./Sq. Cm. in cement mortar 1:4 (1 cement : 4 coarse sand) in superstructure - at all floor levels including proper filling of all masonry joints, curing etc. complete. Work complete including all type of tools, tackles, scaffolding etc complete as per instruction of Architect/EIC. The rate includes providing and placing in position 2 Nos 6 mm dia bars at every third course of masonry work.	94.00	Sq.mt	0.00	0.00
23	Providing 10mm thick cement plaster in single coat on brick/concrete walls for interior plastering all level and finished even and smooth. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC. (ii) Cement mortar 1:4 (1-cement :4-sand)	541.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
24	20 mm thick Sand Faced Plaster: Providing and applying 20mm thick sand faced plaster (Using Wooden Gutka/Float) to all external surfaces at all levels and in any shape, in two coats, 12 mm thick average base coat in cement mortar 1:5 and 8mm thick finish coat in cement mortar 1:2 using fine sand for finish coat, including preparation of surface to uniform texture, staging, double scaffolding, curing, chicken mesh at the junction of masonry & RCC work using screw / dhoba nails, making moulded, grooves, drip moulds, tapak etc., complete as per specification and as directed by the EIC. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC.	10.00	Sq.mt	0.00	0.00
25	Gypsum Plaster for Saint Gobain Gyproc Elite MR (Moisture Resistant): Providing, preparing and applying 13 mm thick (average) premixed formulated one coat gypsum lightweight plaster Gyproc Elite MR having light weight aggregates of expanded Perlite and other special additives conforming to IS: 2547 both Part I & II - 1976 which is certified by Green Pro & GRIHA for green buildings and delivering a coverage of 21-22 sft/25kg bag @ avg thickness of 13 mm and having a setting time between 20 & 30 mins, having water absorption less than 10% as per DIN EN 520 applied directly on background such as brick/ block/ hacked RCC, on internal walls & ceiling at all floors and locations, finished in smooth line and level, free of undulations and cracks. also Provide of Gyproc Glass Fiber Mesh of 145 GSM, Mesh size of 5mm x 5mm with 0.15M (6 Inches) wide, for protection from formation of Cracks at joints of "Masonry (Brick or Blocks) & Concrete surfaces, Joint at sides of Doors & Windows, Plumbing Chasing, Electrical Conduits etc. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC.	348.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
26	Applying two coats of Birla (white cement based) or Asian (acrylic lapy- putty) or equivalent & two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC.	348.00	Sq.mt	0.00	0.00
27	Providing and applying crystalline mortar by mixing in the ratio of 4.5 : 1 (4.5 parts crystalline mortar : 1 part water) for the treatment of faulty construction joints, cracks, tie rod holes and spalled & honeycombed surface of RCC underground structures like basement, water tanks, bridge deck etc. to ensure water tightness. The crystallie mortar shall conform to the EN 1504-3 having compressive strength Class R4 ?45 MPa and adhesive bond strength Class R3 ?1.5 MPa. The work shall be carried out all complete as per specification and the direction of the engineer-in-charge. The product performance shall carry guarantee for 10 years against any leakage. For sealing cracks and faulty construction joints, routed out/making U-shape groove size 25x25mm and then primed the area with integral crystalline slurry @0.05kg/ running metre and while the surface is tacky filled the groove upto surface with crystalline mortar @1.50kg/ running metre. Once crystalline mortar is touch dry then finally applied two coats of integral crystalline slurry @0.05kg/running metre per coat. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC.	525.00	Rmt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
28	<p>Carring out plinth treatment to post construction / existing structure by spraying chemical solution for termite control treatment including labour and material consistment with I.S.I specification. Using Chlordene and Chiorpurfiles 20 EC. As Per 6131_paret-II Concentration Weight one percent is recommended i.e one litre 20 EC chemical emulsion with 19 liter give 1 % concentration inclusive of one litre chemical emulsion appication at the rate of 5 Litre chemical / Sqm of surface is recommended as per I.S.</p> <p>The whole work is to be executed through specialized agency with a guarantee of 5 (Five) years given on a prescribed proforma duly stamped. The termite control treatment work 10% will be retained from the billing amount for 5 years (without interest). The amount shall be refunded after Five years without interest. work complete including all type of tools , tackles, scaffolding, safety measures etc complete at any level and height. work complete as per the instuction of EIC/Architect. Including cost of all type of tools, tackles, all labour, materials, scaffolding, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.</p>	511.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
29	<p>Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement slurry mixed with water proofing cement compound consisting of applying :</p> <p>(a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/ sqm. This layer will be allowed to air cure for 4 hours.</p> <p>(b) Second layer of slurry of cement @ 0.242 kg/sqm mixed with water proofing cement compound @ 0.126 kg/sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours.</p> <p>The rate includes preparation of surface, water proofing compound of Dr. Fixit Pidiproof LW+ or Equevalant, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry. Including cost of all type of tools, tackles, all labour, materials, scaffolding, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.</p>	98.00	Sqm	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
30	<p>Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc consisting of following operations: (a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS. 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment. (b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineerin- charge over 20 mm thick layer of cement mortar of mix 1:5 (1 cement :5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineerin- charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs. (c) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/ sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge. (d) Finishing the surface with 20 mm thick jointless cement mortar of mix 1:4 (1 cement :4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge including laying glass fibre cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3 mm deep. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test."All above operations to be done in order and as directed and specified by the Engineer-in-Charge :</p> <p>22.7.1 With average thickness of 120 mm and minimum thickness at khurra as 65 mm.</p>	492.00	Sqm	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
31	Providing and fixing Heat Resistant Terrace Tiles (300 mm x 300 mm x 20 mm) with SRI (solar refractive index) > 78, solar reflection > 0.70 and initial emittance > 0.75 on waterproof and sloped surface of terrace, laid on 20 mm thick cement sand mortar in the ratio of 1:4 (1 cement : 4 coarse sand) and grouting the joints with mix of white cement & marble powder in ratio of 1:1, including rubbing and polishing of the surface upto 3 cuts complete, including providing skirting upto 150 mm height along the parapet walls in the same manner. Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	492.00	Sqm	0.00	0.00
32	Providing and laying polished Kota stone slab flooring over 20mm (Average) thick base of cement mortar 1:6 (1-cement : 6- coarse sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of slab including rubbing and polishing etc. complete. Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. (A) 25mm thick	56.00	Sqm	0.00	0.00
33	Providing and laying polished kota stone slab 25mm thick in risers of steps,skirting Dedo and pillars laid on 10mm thick cement mortar 1:3 (1-Cement : 3 coarse sand) and jointed with gray cement slury mixed with pigment to match the shade of slab including rubbing and polishing etc. complete. Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	5.00	Sqm	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
34	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing, edge finish, moulding, cutting etc. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges , anti skid grooving. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of Granite 150/ Sq.ft	9.00	Sq.mt	0.00	0.00
35	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias, risers of steps, dedo and pillars and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish, grooving etc. complete at all levels. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of Granite 150/ Sq.ft	3.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
36	Providing and fixing 24" x 24" vitrified 8 to 10 mm thick tile flooring over 20 mm (average) base of cement mortar 1:6 (1 cement: 6 coarse sand) on new surface or fixing flooring by adhesive material and jointed with color cement slurry including finished with flush pointing & cleaning the surface etc. complete for antiskit. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of Granite 35/ Sq.ft	43.00	Sq.mt	0.00	0.00
37	Providing and laying Vitrified tiles 8 to 10 mm thick , in skirting risers of steps and dedo on 10mm thick cement plaster 1:3 (1-cement : 3-coarse sand) and jointed with white cement slurry. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of Granite 40/ Sq.ft	14.00	Sq.mt	0.00	0.00
38	Vitrified Tiles Flooring (Toilet) : Providing and laying Matt finish Vitrified tiles flooring using minimum 10 mm thick tiles of as per approved make list by architect/client, including preparing base for leveling with 20mm thick cement mortar 1:6 (1 cement : 6 coarse sand) and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction and approval by architect. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift, work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. (A) Tile size: 600 mmX 600 mm or as per approved by architect/EIC, Basic rate of tile is Rs. 35/Sqft	72.00	Sq.mt	0.00	0.00
39	Toilet Flooring : "-----Do-----" as per above specification for complete work. (A) Tile size:				



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
40	Vitrified Tiles Wall Dado (Toilet and other wall surfaces): Providing and laying Matt finish Vitrified tiles in dado using minimum 10 mm thick tiles as per approved make list by architect /client. fixed in dado on 10 mm th. Cement plaster 1:3 (1 cement: 3 coarse sand) All surfaces must be dimensionally stable according to level, cured, undamaged, compact,rigid,resistant, dry and free from any debonding agents tiles fixed by approved tile adhesive and all application shall be done under instruction of manufacturer guideline and specification , and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction all complete as per approved sample by Architect, drawings and instruction of EIC. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning , at all floor, all level, all depth, all Height, all lead and lift , work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. (B) Tile size: 600 mmX 1200 mm, Basic rate of tile is Rs. 40/Sqft	270.00	Sq.mt	0.00	0.00
41	Toilet Dado: "-----Do-----" as per above specification for complete work. (B) Tile size: 600 mmX 1200 mm, Basic rate of tile is Rs. 45/Sqft	97.00	Sq.mt	0.00	0.00
42	Vitrified Tile Flooring : Vitrified Tile Flooring : Providing and laying Vitrified tiles flooring using minimum 10 mm thick tiles of as per approved make list by architect/client, including preparing base for leveling with 20mm thick cement mortar 1:6 (1 cement : 6 coarse sand) and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction and approval by architect. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift , work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. (A) Tile size: 1200 x 600 mm Basic rate of tile is Rs. 50/Sqft.	423.00	Sq.mt	0.00	0.00
43	Vitrified Tile Flooring : " ----- Do -----" as per above specification for complete work . (A) Tile size: 800 x	165.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
44	Vitrified Tile Skirting : Providing and laying Vitrified tiles in skirting using minimum 10 mm thick tiles as per approved make list by architect /client fixed in dado on 10 mm th. Cement plaster 1:3 (1 cement: 3 coarse sand) All surfaces must be dimensionally stable according to level, cured, undamaged, compact, rigid, resistant, dry and free from any debonding agents tiles fixed by approved tile adhesive and all application shall be done under instruction of manufacturer guideline and specification and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction all complete as per approved sample by Architect, drawings and instruction of EIC. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning , at all floor, all level, all depth, all Height, all lead and lift, work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. (A) Tile size: 1200 x 600 mm Basic rate of tile is Rs. 50/Sqft	51.00	Sq.mt	0.00	0.00
45	Vitrified Tile Skirting : " ----- Do -----as per above specification for complte work . (A) Tile size: 800 x 800 mm Basic rate of tile is Rs. 40/Sqft	18.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
46	Artificial Stone Flooring : Providing & laying approved quality 15mm thick Artificial stone flooring of approved shade, in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid with adhesive and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, placing at all floors and for all leads, at all floors, all levels, all heights and all shapes, all accessories, Scaffolding, protection sheet etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of Full Body Artificial stone is Rs. 150/ Sqft.	53.00	Sq.mt	0.00	0.00
47	Artificial Stone Cladding : " -----Do-----" as per above specification for complete work. Using 10 mm th. Cement plaster 1:3 (1 cement: 3 coarse sand) instead of 1:6 cement mortar with adhesive. Basic rate of Full Body Artificial stone is Rs. 150/ Sqft.	7.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
48	<p>Artificial Stone door frame: Providing & laying approved quality 15 mm thick Artificial stone work of approved shade (selected and sorted for its uniform colour and thickness)., in door jambs lining, frame etc. in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. including 4 mm deep groove, work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of Full Body Artificial stone is Rs. 150/ Sqft.</p>	236.00	Rmt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
49	<p>Artificial Stone window sill : Providing & laying approved quality 15 mm thick Artificial stone work of approved shade (selected and sorted for its uniform colour and thickness)., in window sill etc. in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. including 4 mm deep groove, at all floors, all levels, all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and polishing of edges. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of Full Body Artificial stone is Rs. 150/ Sqft.</p>	176.00	Rmt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
50	Artificial stone top Platform (for Service counter : 450mm width): Providing & fixing two layers of Pantry Platform, first layer using 25mm thick Kotastone of approved shade and second layer using approved shade and sample of 15 mm thick Artificial stone, joined together with 1:4 Cement mortar bedding / approved tile adhesive , to true plane & level or to slopes,or close jointed with cement slurry with pigment of matching shade and colour and finishing with the same, including dedo 6", cutting stone as per required shape & size to fit sink & 3" to 9" fascia with moulding, nosing, chamfered front edges, fixing, disposal of debris etc. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. . Basic rate of Full Body Artificial stone is Rs.150/ Sqft.	4.00	Rmt	0.00	0.00
Total Amount					0.00
B	Part-2				
51	Artificial Stone Basin Counter for Toilet : Providing & fixing two layers of wash basin counter, first layer using 25mm thick Kotastone of approved shade and second layer using approved shade and sample of Artificial stone, joined together with 1:4 Cement mortar bedding / approved tile adhesive , to true plane & level or to slopes, or close jointed with cement slurry with pigment of matching shade and colour and finishing with the same, including dedo 6", cutting kota & tile as per required shape & size to fit Wash basin & 4" fascia with moulding, nosing, chamfered front edges, fixing, disposal of debris etc. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of Full Body Artificial stone - Rs. 150/Sq.ft	35.00	Rmt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
52	Granite platform for Kitchen : Providing & fixing two layers of platform , first layer using 25mm thick Kotastone of approved shade and second layer using approved shade and sample of Mirror finish Granite, joined together with 1:4 Cement mortar bedding / approved tile adhesive , to true plane & level or to slopes, or close jointed with cement slurry with pigment of matching shade and colour and finishing with the same, including dedo 6", cutting kotah & tile as per required shape & size to fit Wash basin & 4" facia with moulding, nosing, chamfered front edges, fixing, disposal of debris etc. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of granite is 120/ Sq.ft	7.00	Rmt	0.00	0.00
53	Single Leaf Flush Door finish with laminate : Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make and finished with both side 1 mm thick laminate as approved sample. including Hardware system of SS 304 Grade like Hinges, Mortise lock with knob, door closer, door stopper etc. as per approved make & Sample. work complete including all type of hardware, fittings, fixtures as per instruction of Client/ Architect etc. complete as per detailed drawings and specifications. sample mock shall be approved from Architect/Client. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Equivalent to VNR Series Laminate. (Note: Door opening area shall be measured for payment. No extra payment shall be paid) Basic rate of VNR Laminate is 45 Sq.ft	56.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
54	Single Leaf Flush Door finish with laminate for toilet : Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make and finished with both side 1 mm thick laminate as approved sample. including Hardware system of SS 304 Grade like Hinges, Mortise lock with knob, door closer, door stopper etc. as per approved make & Sample. work complete including all type of hardware, fittings, fixtures as per instruction of Client/ Architect etc. complete as per detailed drawings and specifications. sample mock shall be approved from Architect/Client. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Equivalent to VNR Series Laminate. (Note: Door opening area shall be measured for payment. No extra payment shall be paid) Basic rate of VNR Laminate is 45 Sq.ft	30.00	Sq.mt	0.00	0.00
55	WPC shutter with laminate finish (Duct area): Providing and fixing in position 12 mm thick WPC shutter of approved make with laminate finish as approved, shutter fixed with floor and above pivot of approved make, pivot cover plate, safety measures, lock & handle etc fixtures of approved make list with all necessary fittings etc. aluminium frame 25x30 Complete as per detailed drawings and specifications.	19.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
56	<p>Sliding window with mosquito shutter: Domal section : 27x65 mm series Supply & Fixing of Aluminium sliding window with powder coated as per by approved make & sample by architect/EIC. Frame section: 40 x 89 x 1.5 mm, Shutter section : 27x 65 x 1.5 mm, Mosquito shutter : 27 x 65 x 1.5 mm, 18x24 fly proof stainless steel grade 304 wire gauge jali or as per approved by architect/EIC. Glass : 5 mm thick clear reflective toughened glass Work including Trolley Wheel (Bearing), EPDM Gasket, Woolen In Shutter, Concealed Lock, Anti Rattling Guide, Lock Guide, handle Antilifting, Shutter Corner Clit, Shutter wing Connector, Interlock EPDM Gasket, Interlock Guide, Anti Capillary Pad, Bush Bottom silicon all side & All Necessary Hardware etc. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.</p>	31.00	Sqm	0.00	0.00
57	<p>Fixed Glass Aluminium Window: Domal section : R40 mm series Supply & Fixing Fixed glass window Comprising from Domal section series R40 mm series with powder coated as per approved make & sample by Architect/EIC. Frame section: 40 x 39.4 x 1.25 mm Glass : 5 mm thick clear reflective toughened glass of saint gobain or approved make list including EPDM Gasket and All Necessary Hardware etc. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.</p>	40.00	Sqm	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
58	Toilet Ventilation : Providing and fixing standard extruded of alluminium section of size 63 mm x 38.10 mm x 1.2 mm (jindal section : 2434 @ wt. 0.643 kg per mt with powder coated alluminium frame for ventilation with 5 mm thick frosted glass as details & provision of exhaust fan. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	7.00	Sq.mt	0.00	0.00
59	Providing and fixing fly proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete. With 12 mm mild steel U beading. Work complete including all type of material, fittings , fixtures, Finish, loading , unloading , transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights , necessary frame work, Scaffolding etc complete as per detailed drawings , specifications & instruction of Client/EIC. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	7.00	Sqm	0.00	0.00
60	EWC -1: Providing and fixing wash down water closet (European type W.C. pan) as per approved make of selection & shade with seat cover, P OR S Trap M.S. or G.I bracket , CP brass hinges and rubber buffers and Jointing the trap with soil pipe in cement mortar : 1:1 (1 cement : 1 fine sand) including cutting and making good the walls and floors where required with all labour and materials. All works to be carried out as per instructions and direction of Engineer-in-charge. Model Equivalent to Kohler 27902IN-SS-0	5.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
61	EWC-2 : Providing and fixing wash down water closet (European type W.C. pan) as per approved make of selection & shade with seat cover, P OR S Trap M.S. or G.I bracket , CP brass hinges and rubber buffers and Jointing the trap with soil pipe in cement mortar : 1:1 (1 cement : 1 fine sand) including cutting and making good the walls and floors where required with all labour and materials. All works to be carried out as per instructions and direction of Engineer-in-charge. Model Equivalent to Kohler 26998IN-0	14.00	Nos	0.00	0.00
62	Flushing Tank: Providing and fixing Preumatic Flushing tank of as per approved make list . Work complete including all type of finishing. Model Equivalent to Kohler 26352IN-M-NA : INSTAFIT® NXT GEN - MECH IN WALL TANK	19.00	Nos	0.00	0.00
63	Flush Plate: Providing and fixing BEVEL FACE PLATE POLISHED CHROME of as per approved make list . Work complete including all type of finishing. Model Equivalent to Kohler 5413IN-M-CP	19.00	Nos	0.00	0.00
64	Health faucet: Providing and fixing 12mm dia. Health faucet with 8 mm dia of as per approved make list with flexible pipe of 1.mt. length and holding stands complete. Work complete including all type of finishing. Model Equivalent to kohler 12927IN-CP, HEALTH FAUCET W/SDSPRAY, METAL HOSE	19.00	Nos	0.00	0.00
65	Toilet Papers Holder: Providing and fixing Toilet papers holder of as per approved make list . Work complete including all type of finishing. Model Equivalent to Kohler 5632IN-CP	19.00	Nos	0.00	0.00
66	COMPLEMENTARY ANGLE VALVE: Providing and fixing 15mm dia COMPLEMENTARY ANGLE VALVE of as per approved make list. Work complete including all type of finishing. Model Equivalent to kohler 11568IN-7B-CP - COMPLEMENTARY ANGLE VALVE	19.00	Nos	0.00	0.00
67	Wash Basin-1: Providing and fixing Wash Basin including fittings and waste pipe and fixing on wash basin counter by tile adhesive of approved make. Work complete including all type of finishing. Model Equivalent to kohler 5373IN-0 FOREFRONT RECT W/O FAUCET DECK+ 20746IN-CP COMPLEMENTARY GRID DRAIN, LONG	5.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
68	Wash Basin - 2 : Providing and fixing Wash Basin including fittings and waste pipe and fixing on wash basin counter by tile adhesive of approved make. Work complete including all type of finishing. Model Equivalent to kohler 28784IN-0 KOHLER VIVE GEO VESSEL + 1460429-CP HIDDEN DRAIN ASSEMBLY	14.00	Nos	0.00	0.00
69	Basin spout - 1: Providing and fixing 15mm dia wall Mounted Basin spout of as per approved make list and work complete including all type of accessories. Model equivalent to kohler 5684IN-4ND-CP; ALEO+ WM LAV FAUCET TRIM and 5679IN-CP; SC WM VALVE ASSY	5.00	Nos	0.00	0.00
70	Basin spout - 2 : Providing and fixing 15mm dia wall Mounted Basin spout of as per approved make list and work complete including all type of accessories. Model equivalent to kohler 5683IN-4ND-CP ALEO WM LAV FAUCET TRIM +5679IN-CP SC WM VALVE ASSY	14.00	Nos	0.00	0.00
71	Providing and fixing 15mm dia. Angular Cock as per approved make list and work complete including all type of accessories . Model equivalent to Kohler 11568IN-7-CP	19.00	Nos	0.00	0.00
72	Providing and fixing in position Soap Dispensor as per approved make list and work complete including all type of accessories. Model equivalent to JAQUAR - CAT- CAN-1135N	19.00	Nos	0.00	0.00
73	Providing and fixing Towel ring of as per approved make of selection or as directed by EIC. Jaquar : ACN-1121N	19.00	Nos	0.00	0.00
74	Handrayer : Providing and fixing in position of Handdrayer of as per approved make list. Work completed as per the instruction of EIC. Model Equivalent to kohler 5486T-0P (Bardon Touch Less Hand Dryer In White)	19.00	Nos	0.00	0.00
75	Bib Tap (Utility area): Providing and fixing 15mm dia Bib Tap of as per approved make list. Work complete including all type of finishing. Model Equivalent to kohler	3.00	Nos	0.00	0.00
76	Kitchen sink: Providing and fixing Kitchen sink as per approved make including all fitting material including Fixing of with necessary plumbing work as per detail drawing and plumbing work .Material approved by architect/EIC. Model Equivalent to NIRALI GRACE JUMBO 685X535X254	2.00	Nos	0.00	0.00
77	Sink Cock: Providing and fixing 15mm dia. Sink Cock of as per approved make of selection. Model	2.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
78	RAINDUET SQUARE 203MM RAINHEAD : Supply, Installation, Testing and Commissioning of Rainduet Square Rainhead of Kohler or equivalent approved make with all necessary fittings material work complete as per the detailed drawing. Rate shall be inclusive of all materials, loading, unloading, all taxes, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC. Model Equivalent to Kohler code No 73038IN-CL-CP RAINDUET EDGE SQUARE 203MM RAINHEAD	5.00	Nos	0.00	0.00
79	RAINDUET SQUARE 203MM RAINHEAD : Supply, Installation, Testing and Commissioning of Rainduet Square Rainhead of Kohler or equivalent approved make with all necessary fittings material work complete as per the detailed drawing. Rate shall be inclusive of all materials, loading, unloading, all taxes, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC. Model Equivalent to Kohler code No 73199IN-CP RAINDUET SQUARE 203MM RAINHEAD	14.00	Nos	0.00	0.00
80	WALL MOUNT SQUARE SHOWERARM : Supply, Installation, Testing and Commissioning of WALL MOUNT SQUARE SHOWERARM of Kohler or equivalent approved make with all necessary fittings material work complete as per the detailed drawing. Rate shall be inclusive of all materials, loading, unloading, all taxes, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC. Model Equivalent to Kohler code No 20138IN-CP; COMPLEMENTRY SQUARE SHOWERARM WALL MOUNT	19.00	Nos	0.00	0.00
81	SPATULA HANDSHOWER LARGE WITH HOSE : Supply, Installation, Testing and Commissioning of SPATULA HANDSHOWER LARGE WITH HOSE of Kohler or equivalent approved make with all necessary fittings material work complete as per the detailed drawing. Rate shall be inclusive of all materials, loading, unloading, all taxes, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC. Model Equivalent to Kohler code No 98445IN-CP	5.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
82	ALEO BATH SPOUT W/ DIVERTER : Supply, Installation, Testing and Commissioning of ALEO BATH SPOUT W/ DIVERTER of Kohler or equivalent approved make with all necessary fittings material work complete as per the detailed drawing. Rate shall be inclusive of all materials, loading, unloading, all taxes, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC. Model Equivalent to Kohler code No 20077IN-CP	19.00	Nos	0.00	0.00
83	RAINJOY SLIDE BAR : Supply, Installation, Testing and Commissioning of RAINJOY SLIDE BAR of Kohler or equivalent approved make with all necessary fittings material work complete as per the detailed drawing. Rate shall be inclusive of all materials, loading, unloading, all taxes, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC. Model Equivalent to Kohler code No 72740IN-CP; RAINJOY SLIDE BAR	19.00	Nos	0.00	0.00
84	ALEO+RECE B&S TRIM, 40mm with VALVE : Supply, Installation, Testing and Commissioning of ALEO+RECE B&S TRIM, 40mm of Kohler or equivalent approved make with all necessary fittings material work complete as per the detailed drawing. Rate shall be inclusive of all materials, loading, unloading, all taxes, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC. Model Equivalent to Kohler code No 72328IN-4FP-CP; ALEO+ RECE B&S TRIM, 40mm + 882IN-CP; AQUA TURBO 235 MANUAL VALVE	19.00	Nos	0.00	0.00
85	Bottle Trap: Providing and fixing chromium plated Bottle Trap of as per approved make list , with necessary coupling of approved make for wash basin & sink. Work complete including all type of finishing. Model Equivalent to kohler 75823IN-CP - BOTTLE TRAP 350MM	21.00	Nos	0.00	0.00
86	Mirror -1: Providing and fixing 6 mm thick mirror of Kohler or as per approved make shall be fixed with SS studs. Provision shall be made for conceal led light work as per detailed drawing / instruction of architect complete. Rate shall be inclusive of frosting work as per detail drawing. Model Equivalent to kohler 26052-BLL; KOHLER ESSENTIAL RECTANGLE MIRROR (560mm L x 864mm H)	5.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
87	Mirror - 3 : Providing and fixing 6 mm thick mirror of Saint Gobain/ Modiguard / Asahi as per approved make shall be fixed with SS studs. Provision shall be made for conceal led light work as per detailed drawing / instruction of architect complete. Rate shall be inclusive of frosting work as per detail drawing. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	14.00	Sq.mt	0.00	0.00
88	Collapsible steel shutter: Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	6.00	Sqm	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
89	MS Fabricated Door: Providing Fabrication & erection 3 mm thick M.S. sheet/plate door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using M.S. angels 40x40x6 mm for diagonal braces. including CNC cutting/Engraving as per reference image given by Architect. The work includig necessary fabrication work, fittings, fixtures, accessories, pivot, door, handle, lock etc complete. finish with Anti corrosive paint with primer as per approved shade by Architect. The scope includes loading, transportation, unloading and delivery and erection site of all fabricated structures, alignment and welding of all structures true to line, level, plumb and dimension. sample mock shall be approved from Architect/EIC. Shop drawing shall be provided by Contractor. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protectiion sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. (Preparation Area)	3.00	Sq.mt	0.00	0.00
90	Fabricated work: Providing Fabrication & erection of steel structure as per drawings including materials, consisting of plates, rolled steel joists, channels, angles, chequered plates etc and also rectangular / square hollow steel sections, insert plates in RCC/Brickwork, anchor bolts for steel structure, sleeve pipes, anchor nuts, washers etc, straightening of raw steel if required, fabrication of steel structures with primer and minimum two coats of anti corrosive matt finish paint including preparation of supplementary sketches and detailed bill of materials supply of bolts, nuts, washers, shims, packs, putty, gas, welding electrodes and all other consumables, as required and carrying out surface preparation all complete. The scope includes loading, transportation ,unloading and delivery and erection site of all fabricated structures,, alignment and welding of all structures true to line, level, plumb and dimension, including rectification if any, splicing, site assembly all as per technical specifications and drawings, ,all complete.Contactror shall provide stability certificate for the fabrication structure. Rate inclusive of shop drawing.	1723.00	KG	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
91	<p>S.S. & Glass Railing: Staircase Material: SS 304 Grade MAT finish, Top handrail: Ø 50mm X 1.5mm thick AISI 304 Grade S.S. Modular Handrail Verticle Balustrade : 40mm X 40mm X1.5mm thick AISI 304 Grade S.S Top Mounted Square Baluster with Double Glass holding Accessories,100 x 100 x 8mm Thick 304 Grade base Plate With 2 No. Hilti frame Anchor HRD-C M10 X 100 mm : balusters to be placed at approximate 1200.00mm C/C Glass: 12mm thick Straight Toughened Glass as per approved make & sample work complete including all type of modular fittings, fixing, fixtures, accessories, tools, tackles, scaffolding, anchoring, silicon seal, epoxy grouting , insets plates, mock up sample etc complete as per the detailed drawing & Instruction of EIC. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.</p>	17.00	Rmt	0.00	0.00
92	<p>Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.</p>	245.00	Sqm	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
93	<p>Polycarbonate roofing : Fabrication, Erection and Paint on M.S. Structure as per design finalized. Supply & Installation of Standing Seam. Polycarbonate Roofing Sheet as per final approved drawing on M.S. Structure as per design submitted. Polycarbonate Roofing Sheet Specification: Type of Roofing Sheet: Standing Seam Multiwall Modular Panel Sheet Make: Coxwell Domes, Lexan, Sebic Thickness: 10mm , UV Coating: Both Side Paint Specification: 1 Coat Primer and 2 Coat Enamel Paint of Make Asian / Burger M.S. Pipe Make: Apollo / Asian Including cost of all type of tools, tackles, scaffolding, all labour, materials, transportation, Finishing, all type of fabrication & steel work with paint, accessories , silicon sealent ,. Work complete for at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the Detailed specification, shop drawing , approved sample, instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Plan area shall be measured for payment. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved</p>	34.00	Sq.mt	0.00	0.00
94	<p>Providing laying and jointing in true line and level 15mm dia. U.P.V.C. Pipe (SCH- 40) for cold water including fittings make PRINCE / SUPREME / ASTRAL / FINOLEX or equivalent as approved by Engineer In Charge. Pipe shall be fixed on the wall with the help of clamp at every two metre C/C or shall be cancelled as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.</p>	200.00	Rmt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
95	Providing laying and jointing in true line and level 25mm dia. U.P.V.C. Pipe (SCH- 40) for cold water including fittings make PRINCE / SUPREME / ASTRAL / FINOLEX or equivalent as approved by Engineer In Charge. Pipe shall be fixed on the wall with the help of clamp at every two metre C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.	120.00	Rmt	0.00	0.00
96	Providing laying and jointing in true line and level 32mm dia. U.P.V.C. Pipe (SCH- 40) for cold water including fittings make PRINCE / SUPREME / ASTRAL / FINOLEX or equivalent as approved by Engineer In Charge. Pipe shall be fixed on the wall with the help of clamp at every two metre C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.	60.00	Rmt	0.00	0.00
97	Providing laying and jointing in true line and level 40mm dia. U.P.V.C. Pipe (SCH- 40) for cold water including fittings make PRINCE / SUPREME / ASTRAL / FINOLEX or equivalent as approved by Engineer In Charge. Pipe shall be fixed on the wall with the help of clamp at every two metre C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.	60.00	Rmt	0.00	0.00
98	Providing laying and jointing in true line and level 50mm dia. U.P.V.C. Pipe (SCH- 40) for cold water including fittings make PRINCE / SUPREME / ASTRAL / FINOLEX or equivalent as approved by Engineer In Charge. Pipe shall be fixed on the wall with the help of clamp at every two metre C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.	150.00	Rmt	0.00	0.00
99	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and	120.00	Rmt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
100	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [B] 20 mm.	60.00	Rmt	0.00	0.00
Total Amount					0.00
C	Part-3				
101	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [C] 25 mm.	60.00	Rmt	0.00	0.00
102	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [D] 32mm.	60.00	Rmt	0.00	0.00
103	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [E] 40mm.	100.00	Rmt	0.00	0.00
104	Supplying & erecting resin bonded flap rock wool / glass wool with conductivity valve 1.67 sq.mm per watt & to with stand the temp. to 100 degree centigrade C thickness 50mm with G I pipe of following size dia "B" class as per IS:1239. The plastic sheet to be used as covering of glass wool. Al. cladding besides other materials like chicken mesh, 26 G Al. Sheet shall be used for cladding the insulation pipe.; (A) for 20 mm dia pipe	60.00	Mtr	0.00	0.00
105	(B) For 25 mm dia pipe	60.00	Mtr	0.00	0.00
106	(C) for 32 mm dia pipe	60.00	Mtr	0.00	0.00
107	(D) for 40 mm dia pipe	100.00	Mtr	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
108	Supply, Installation, Testing & Commissioning of SPLIT HEAT PUMP Power Supply : 220V/440V/1Ph/3Ph/50Hz , Tank, Compressor, Heating Element, Sound Level : <50 dB Refrigerant Type : R410a, Outer Body Material : Prepainted Steel, Inner Tank Material : Glass Lined MS Tank, Max Water Pressure : 0.8 Mpa, Defrosting : Auto, Water Proof Grade : IPX4, Insulation Thickness : PUF - 50mm, Emerson Expansion valve. Hot Water Circulation pump. with Multi-function digital control panel. Max. Temp. 60 C. Operating ambient condition -5 c to 45 c. 50 db a low noise level. complete with all required accessories to complete the job with Valves & Piping.: 1) Capacity of 300 LPD	1.00	Ea.	0.00	0.00
109	2) Capacity of 500 LPD	1.00	Ea.	0.00	0.00
110	Providing and fixing Gun metal check or non-return fullway wheel valve.(C) 25mm dia.	12.00	Each	0.00	0.00
111	Providing and fixing Gun metal check or non-return fullway wheel valve.(D) 32mm dia.	4.00	Each	0.00	0.00
112	Providing and fixing Gun metal check or non-return fullway wheel valve.(E) 40mm dia.	4.00	Each	0.00	0.00
113	Providing and fixing Gun metal check or non-return fullway wheel valve.(E) 50mm dia.	4.00	Each	0.00	0.00
114	Supply, installation, testing and commissioning of gunmetal, male or female threaded isolation control valve (Butterfly Valve), confirming to latest IS , PN 10.0, with necessary specials, union, nipples etc., to complete the job. (Audco/Lehry/ R.B./zoloto). 65mm dia.	2.00	Each	0.00	0.00
115	Supplying, fitting and fixing Non return valve (Spring type Dual plate type) as per API 594/598 , tested to 10 kg/sq.cm etc. complete. (// Audco/Lehry/ R.B./ Spirex). 40mm dia.	1.00	Each	0.00	0.00
116	Supplying, fitting and fixing Non return valve (Spring type Dual plate type) as per API 594/598 , tested to 10 kg/sq.cm etc. complete. (// Audco/Lehry/ R.B./ Spirex). 50mm dia.	1.00	Each	0.00	0.00
117	Supply, Installation, Testing and Commissioning of 25 mm dia. air release valve. (// Audco/Lehry/ R.B./ Spirex)	1.00	Each	0.00	0.00
118	Providing and fixing mosquito proof stainless steel overflow grating for tanks.(// Audco/Lehry/ R.B./ Spirex) 100mm dia.	1.00	Each	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
119	Valve Chambers: Construction of valve chamber brick masonry 230 mm thick wall , inside with 75 second class designation brick work in cement mortar 1:5 (1 cement :5 fine sand) for valve, FRP surface heavy duty chamber cover(600MM X 600MM) with Frame, RCC top slab for valve with chained lid and Rcc top slab 1:2:4 mix (1 cement:2 coarse sand : 4 graded stone aggregate 20mm nominal size) necessary excavation foundation concrete 1:5:10 (1 cement :5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement :3 coarse sand) 12mm thick finished with a floating coat of neat cement complete as per standard design: (Valve Chamber). Size of 0.75 m x 0.75 m and upto 1.0 m deep for Isolation Valve	1.00	Each	0.00	0.00
120	Supply, installation, Testing and Commissioning of 15mm Nominal diameter Garden Hydrant with gun metal Ball Valve, GI pipe for Flexible hose Connection Provision and all required accessories etc.	5.00	Each	0.00	0.00
121	Providing erecting and fixing double coated Syntex PVC. (ISI) water tank of required capacity each with all necessary fittings and connection etc. complete on terrace.	10000.00	litre	0.00	0.00
122	Providing & erecting water cooler having storage capacity 150 Ltr. & cooling capacity 150 Ltr.per hour @ an ambient temp of 450 C. The outlet temp. of the water should drop by 150C within a hour, The water cooler should be comprising of hermetically sealed compressor, fan motor, condensing unit, water tank surrounded by evaporating, coil, thermostats, relay etc.complete with necessary inlet & outlet connection. The body of water cooler will be made from Stainless Steel.	2.00	Each	0.00	0.00
123	Supplying & erecting 5 stage single reverse osmosis water purification system with M.S. powder coated frame, prefilter housing with 'O' ring presediment filter GAC filter, carbon filter suitable buster DC pump capacity 80 psi, mention with 40 Osg inline type post carbon filter auto low & high pressure switches with following size of storage tank & LPH capacity & erected as directed with one year comprehensive maintenance guarantee. [C] 50 Ltr / Hr with 250 psi 2 nos booster pump	2.00	Each	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
124	Providing and fixing to wall ceiling and floor 10.0 Kg. F/Cm2 working pressure poluthene pipes of the following outside Dia. Low densidy, complete with special falnge compression type fittings, wall clipsetc. including making good the wall ceiling and floor.(C) 32mm	10.00	Rmt	0.00	0.00
125	Providing and fixing to wall ceiling and floor 10.0 Kg. F/Cm2 working pressure poluthene pipes of the following outside Dia. Low densidy, complete with special falnge compression type fittings, wall clipsetc. including making good the wall ceiling and floor.(D) 40mm	150.00	Rmt	0.00	0.00
126	Providing and fixing to wall ceiling and floor 10.0 Kg. F/Cm2 working pressure poluthene pipes of the following outside Dia. Low densidy, complete with special falnge compression type fittings, wall clipsetc. including making good the wall ceiling and floor.(E) 50mm	30.00	Rmt	0.00	0.00
127	Providing and fixing to wall ceiling and floor 10.0 Kg. F/Cm2 working pressure poluthene pipes of the following outside Dia. Low densidy, complete with special falnge compression type fittings, wall clipsetc. including making good the wall ceiling and floor.(G)110 mm	200.00	Rmt	0.00	0.00
128	Providing and fixing to wall ceiling and floor 10.0 Kg. F/Cm2 working pressure polythene pipes of the following outside Dia. Low densidy, complete with special falnge compression type fittings, wall clipsetc. including making good the wall ceiling and floor.(F) 75mm	300.00	Rmt	0.00	0.00
129	Providing and fixing PVC SWR Nahni trap IS 14735 for drain - 100 mm diameter with jali of the following nominal diameter of self cleansing design with C.I sread down or hinged grating including the cost of cutting and making good the walls.	1.00	each	0.00	0.00
130	Providing and fixing PVC SWR Nahni trap IS 14735 for drain - 75 mm diameter with jali of the following nominal diameter of self cleansing design with C.I sread down or hinged grating including the cost of cutting and making good the walls.	42.00	each	0.00	0.00
131	Providing and fixing S.W. gully trap with C.I. grating brick masonry chamber and water tight C.I. cover with frame of 300mm x 300mm size (inside) with standard weight.(i) Square mouth traps. (A) 100mm x 100mm size P type. (upto 10 ton)	6.00	Each	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
132	Providing, laying and jointing in true line and level 110 diameter U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 110 mm diameter x 149 mm length x 145 mm height at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	10.00	Rmt	0.00	0.00
133	Providing, laying and jointing in true line and level 160 diameter U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 160 mm diameter x 210 mm length x 196 mm height at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	100.00	Rmt	0.00	0.00
134	Constructing Manhole with R.C.C. top slab in 1:2:4 mix (1-cement :2-coarse sand : 4-graded stone aggregate 20mm nominal size) foundation concrete 1:3:6 mix (1-cement : 3- coarse sand :6-Brick bats 40 + 50mm size) inside plastering 15mm thick with Cement Mortar 1:5 (1-Cement : 5-coarse sand) finished with a floating coat of neat cement and making channels in cement concrete 1:2:4 mix (1-Cement :2-Coarse sand :4-stone aggregate 20mm nominal size) finished smooth complete including curing and festing (i) Inside size 900mm x 1200mm and 1.5M. deep including C.I. cover with frame size 560mm diameter total weight of cover and frame to be not less than 128 kgs. (Wt. of cover 64 Kg. and Wt. of frame 64 Kg.)(A) With 230mm thick walls of brick masonry using brick having crushing strength not less than 35Kg. / Sq.cm. in Cement Mortar 1:5 (1- Cement: 5-Coarse sand) (1) A type depth 0.90 Metre for 150mm diameter sewer.	6.00	Each	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
135	Providing and laying Cement concrete 1:5:10 (1-Cement : 5-Fine sand :10-Graded stone aggregate 40mm nominal size) bedding for stoneware pipes of following internal diameters with necessary formwork and curing complete.(B) 150mm dia. (166mm Ave. bed thickness)	110.00	Rmt	0.00	0.00
136	Constructing brick masonry chamber for underground C.I. Inspection chamber and bends with bricks having crushing strength not less than 35Kg. Cm ² in C.M. 1:5 C.I. cover with frame (Light duty) 455mm x 610mm intenal dimensions total weight of cover with frame to be not less than 38Kg. (Wt. of cover 23 Kg.) and Wt. of frame 15Kg.) (R.C.C. top slabe with 1:2:4 mix (1-cement :2- coarse sand :4-graded stone aggregate 20mm size) foundation concrete 1:5:10 inside plaster 15mm thick with cement mortar 1:3 finished smooth with a floating coat of neat cement on walls and bed concrete etc. complete.(i) Inside dimensions 455mmx 610mm and 450mm deep for single pipe line. (upto 10 ton)	6.00	Each	0.00	0.00
137	Construction of septic Tank in all types of soil with 40 Cm .thick masonry in CM 1:6, 15 Cm thick C.C bed of 1:5:10, M-15 grade C.C flooring & over stone slab covering ,80 mm thick slab ,jointing of slab in CM 1:3. Ralthal, Kharanja, 50 mm thick stone partition walls, 20 mm thick plaster in CM 1:6 finished with neat floating cement, 4 Nos C.I foot rests of approved design ,two No. 450 mm dia each Ferro cement cover with frame, earth work etc. complete as per approved drawing including disposal of surplus earth within a lead of 50 mtr:- Required size of 3mtr x 2.0 mtr x 3 mtr deep for 500 visitors or As per Architectural Drawings.	1.00	Job	0.00	0.00
138	Construction of Soakage well in all types of soil of approved drawing, top 90 Cm .Portion in 450mm thick masonry with CM 1:6, 80 mm thick stone slab covering, jointing of slab in CM 1:3 ,Ralthal, kharanja 40mm thick M-15 grade C.C flooring, earth work etc . complete including disposal of surplus earth within a lead of 50 mtr . Inner Dia : 3 mtr & 6 mtr deep. or As per Architectural Drawings.	1.00	Job	0.00	0.00
139	Providing and fixing G.I. Rain water spout of 50mm dia. and 30cm. length.	6.00	Each	0.00	0.00
140	Constructing Brick masonry road gully chamber 500mm x 450mm x 600mm including 500mm x 450mm C.I. horizontal grating wih frame complete.	6.00	No.	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
141	Providing, laying and jointing in true line and level 160 diameter U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 160 mm diameter x 210 mm length x 196 mm height at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	50.00	Rmt	0.00	0.00
142	Providing and laying Cement concrete 1:5:10 (1-Cement : 5-Fine sand :10-Graded stone aggregate 40mm nominal size) bedding for stoneware pipes of following internal diameters with necessary formwork and curing complete.(B) 150mm dia. (166mm Ave. bed thickness)	50.00	Rmt	0.00	0.00
143	ELECTRICAL PART: Point wiring for Light / Bell with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in/ on surface on wall/ceiling complete with 6A Modular type switch / bell push & accessories and earth continuity of following type, erected on PVC / Metallic box, single mounting base frame covered with textured/metallic front plate modules erected on / in wall / ceiling as per pipe erected, with necessary Lamp holder/ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories CAT III	200.00	Pt	0.00	0.00
144	Point wiring for secondary light point with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling, complete with earth continuity and necessary connection with primary light with accessories erected on Metal / PVC box covered with 3 mm thick PC(Polycarbonet) / Acrylic sheet for open / concealed wiring. with necessary Lamp holder / ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories	89.00	Pt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
145	Point wiring for Two Way Controlled Light Point with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (green) both are of .ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling ,complete with 6A Modular type switches and following type of accessories erected on PVC / Metallic box, single mounting base frame covered with textured / metallic front plate modules erected on / in wall / ceiling as per pipe erected. with necessary batten/angle holder or ceiling rose or H.D.Connector as directed CATIII	20.00	Pt	0.00	0.00
146	Point wiring for FAN with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (Green) both are of .ISI marked 1.1 KV Grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling complete with 6A Modular type switch and hum free EME four or more step type electronic fan regulator with separately mounted and accessories with earth continuity of following type erected on PVC / Metallic box, single mounting base frame covered with textured/metallic front plate modules erected on / in wall / ceiling as per pipe erected. with necessary ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories.CAT III	24.00	Nos	0.00	0.00
147	Point wiring for Looped Plug with 6A Modular type switch & 5 pin socket erected on PVC / Metallic box, single mounting base frame covered with textured / metallic front plate modules erected on / in wall / ceiling with following type accessories. CAT III	84.00	Nos	0.00	0.00
148	Providing following type of Modular Type Accessories mounted with PVC / metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate , modules erected with necessary connections as per site situation directed by Engineer In charge. (23)USB Charger with output of 5 V DC,2.1 A with inbuilt surge protection. Cat-III	59.00	Ea	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
149	Point wiring for Individual Plug with & earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of to be erected concealed in / on surface of wall / ceiling complete with Modular type switch & 5 pin Plug erected on PVC / Metallic box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories. For 6A Plug with 2-1.5 sq.mm Cu. Wire with medium class Rigid PVC pipe and accessories CAT III	40.00	Pt	0.00	0.00
150	Point wiring for Individual Plug with & earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of to be erected concealed in / on surface of wall / ceiling complete with Modular type switch & 5 pin Plug erected on PVC / Metallic box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories.[III] For 16A Plug with 2-2.5 sq.mm Cu. Wire (a) with medium class Rigid PVC pipe and accessories.CAT-III	24.00	Pt	0.00	0.00
Total Amount					0.00
D	Part-4				
151	Point wiring for Individual Plug with & earthwire of 2.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of to be erected concealed in / on surface of wall / ceiling complete with Modular type switch & 5 pin Plug erected on PVC / Metallic box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories.[III] For 16A Plug with 2-4 sq.mm Cu. Wire (a) with medium class Rigid PVC pipe and accessories.CAT-III	20.00	Pt	0.00	0.00
152	Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling, with 1.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size (a) with medium class Rigid PVC pipe and accessories	200.00	Mtr	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
153	Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling, with 1.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size (a) with medium class Rigid PVC pipe and accessories (B) 2 wire 2.5 sq. mm	1000.00	Mtr	0.00	0.00
154	Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected in / on wall / ceiling with 2.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size. (a) with medium class Rigid PVC pipe and accessories (b) 2 wire 6 sq. mm	1500.00	Mtr	0.00	0.00
155	Providing and erecting ISI mark Medium class RIGID PVC PIPES of following size complete to be erected on/in wall or ceiling erected with necessary PVC fittings & Junction boxes fixed with adhesive solution & Clamps with following dia of pipes, in approved manner as directed (b) 25 mm	2000.00	Mtr.	0.00	0.00
156	Providing & erecting Approved make Ceiling Fan with double ball bearing ISI mark with Condenser 230 volt A.C.50 Hz 1200 mm sweep complete having 3 blades aluminium body and blade sets having ornamental design shanks , canopy & 30 cms. down rod erected with 24/0.2, 3 core flexible wire with earthing. [Make shall be approved by Engineer in Charge]	24.00	Nos	0.00	0.00
157	Providing 2.5mm.thick laminated acrylic sheet to cover the fan hook or Fan box.	24.00	Nos	0.00	0.00
158	Supplying and erecting 19 / 20 mm. nominal bore Medium Class M.S. Pipe down rod erected duly painted for fan complete with necessary 24/ O.20, 3 core flexible wire with earthing.	24.00	Mtr	0.00	0.00
159	Supplying & erecting fan hook box of 10 mm M.S. round bar bounded to the RCC bars up to 50mm length each side and pierced through a 16 Gauge M.S. box / Heavy Duty PVC box complete erected concealed in Ceiling with necessary finishing.	24.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
160	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs.(The DBs should be used of same company of MCB to be used) (F) Single phase 6 way SS Double door	22.00	Each	0.00	0.00
161	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, Confirms to IS 8623-1 & 3, IEC 61439-1 & 3 without MCB to house appropriate nos. of MCBs.(The DBs should be used of same company of MCB to be used) suitable for. (A) single phase incoming and horizontal single phase outgoing. (iv)Single phase 12 way SS Double door	2.00	Each	0.00	0.00
162	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs N) Three phase 8 way SS Double door for horizontal single phase outgoing	2.00	Ea	0.00	0.00
163	providing and erecting Miniature circuit breaker single pole 6A to 25A suitable to operate on 240 V A.C. system and having breaking capacity 10 KA to be erected in existing box. confirming to IS 8828/1996 with ISI Mark Cat.III	144.00	EA	0.00	0.00
164	Providing & erecting 240 V MCB double pole switch for lighting Load (B Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (B) 40 Amp. Cat.III	26.00	Ea	0.00	0.00
165	Providing & erecting 415V MCB Four Pole Switch for Lighting Load (B curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity (b)40 Amp. Cat.III	6.00	Ea	0.00	0.00
166	Providing & erecting 415 V MCB Four Pole for Motor & Inductive Load (C Curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity C) 63 Amp. CAT-III	2.00	Ea	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
167	Approved make ELCBs / RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed (i) 25 Amps.DP Cat. III	2.00	Ea	0.00	0.00
168	Approved make ELCBs / RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed (i) 40 Amps.DP Cat. III	36.00	Ea	0.00	0.00
169	Approved make ELCBs / RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed (i) 63 Amps.DP Cat. III	1.00	Ea	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
170	Providing & erecting weather proof, dust & vermin proof, floor mounted front operated indoor type cubical panel board having IP-64 protection made from 14 SWG thick CRC M.S. sheet for outer body & doors, 16 SWG thick CRC M.S. sheet for internal partitions with necessary supporting angles, flats including cutting, bending, drilling, welding, riveting with internal partitions & cable alley as per requirements & instruction of engineer-in-charge with erection of supplied switch gears, BUSBARS, with suitable size of inter connecting PVC copper wire / copper-aluminium strips, rubber grommets, rib, bakelite control fuses for measuring instruments, earth bus & earth bolts, foundation flange - bolts-base Plates, sufficient nos. of hinged doors, handles with locking arrangement and rubber gasket complete. The Panel shall be painted with epoxy powder coating. (The rates excludes the cost of switchgears, bus bars, inter connecting mains & Copper Aluminium strips, meters, Fuses etc. The dimension shall be measured excluding base beams) The panel shall be supplied with following approved manufacturers with following size. (A) The standard companies switch gear shall be used and only manufacturers at CPRI approved factory and shall be certified by that company whose switch gears are used after fabrication for beneficial use and having Logo on the Panel (ii) with 550 mm. Depth	3.00	SQMT	0.00	0.00
171	Supplying and erecting triple pole & neutral 440V/ 500V panel mounting Aluminium Busbars with four equal Nos. of bus having current density not more than 0.8 Amp. / sq.mm (Rated current / cross section area) duly wrapped with colour insulating tape for phase sequence of following current carrying capacity, erected with necessary bus bar supports /insulators, main cable socket to each busbar,erected in existing cubical panel with necessary connections(B) Suitable for 200 Amp. Capacity	2.00	Ru Mtr	0.00	0.00
172	Supplying and erecting approved make panel mounting type Digital Voltmeter having 3 digits LED display, 0 to 750 AC Volts range erected on existing panel board with all connection, wiring etc .with manufacturers calibration certificate.	1.00	Each	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
173	Supplying and erecting approved make panel mounting type Digital Ammeter having 3 digits LED display, external CT operated, calibrated for 0 to 1000 Amps suitable to operate on 500 Volt AC , erected on existing panel board with all connection, wiring etc .with manufacturers calibration certificate.	1.00	Each	0.00	0.00
174	Supplying and erecting Ammeter / Voltmeter selector switch for 3 phase AC Supply 500 V on existing panel board with necessary connections.	2.00	Each	0.00	0.00
175	Providing & erecting L.T. Current Transformer with bar primary 50/5 to 1000/5 ratio 15 VA burden erected in existing CRCA box duly secured with insulating materials connected to the meter	3.00	Each	0.00	0.00
176	Supplying and erecting approved make set of indicator lamps of LED type lamp, lens cover, Bakelite holder complete erected with necessary connections.	6.00	Each	0.00	0.00
177	Providing , erecting , fabricating the M.S. structure as per requirement on site incorporating proper size of M.S. angles, flats, bars, channels, sections complete with cutting, welding, grinding & finishing duly painted with one coat of red oxide with erection on site as per direction of engineer in charge with necessary grouting, cementing, plastering & finishing complete.	60.00	Kg.	0.00	0.00
178	Supplying & erecting approved make Four Pole 415V change over switch interior for panel mounting with operating mechanism A.C.23 duty conforming to IS for (D)200A Cat-III	1.00	Each	0.00	0.00
179	providing and erecting Approved make Four pole moulded case circuit breaker having breaking capacity ICU of 35 KA. at 415 V. having normal current rating 125A. with Fixed thermal & magnetic release suitable to work on A.C.supply 50 c/s. with all internal connections & complete erected in existing 16 G.M.S. housing. ICS=100% of ICU only Cat III	1.00	Each	0.00	0.00
180	providing and erecting Approved make Four pole moulded case circuit breaker having breaking capacity ICU of 35 KA. at 415 V. having Normal current rating 200A.with variable Thermal & magnetic release	1.00	Each	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
181	Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables (H) 3 1/2 core 185 Sq. mm (95 Sq. mm 1/2 core)	100.00	Mtr	0.00	0.00
182	Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables. A)4 core 16 Sq. mm	200.00	Mtr	0.00	0.00
183	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Copper conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe at road crossing or floor of following size of cable. (C) 3 core 6 Sq. mm	900.00	MTR	0.00	0.00
184	Providing and, fixing heavy duty flange type brass double compression type cable gland with rubber ring for PVC insulated a rmoured cable complete with out going tails, insulating tape etc for following size of cables.(G) 3 & 1/2 core 185 Sq. mm	2.00	EA	0.00	0.00
185	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. D) 2 to 4 core 16 Sq. mm	4.00	Ea	0.00	0.00
186	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. B) 2 to 4 core 6 Sq. mm	44.00	Ea	0.00	0.00
187	Solder less crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (I) 185 Sq.mm.	8.00	Ea	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
188	Solderless crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. C)16 Sq. mm	8.00	Ea	0.00	0.00
189	Solder less crimping type Copper lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (A) 1.5/2.5 to 6 Sq.mm	176.00	Ea	0.00	0.00
190	Supplying & erecting in earthpit of minimum bore dia. 225mm size ASH or approved make Safe Earthing Electrode consisting Pipe-in-Pipe Technology as per IS 3043-1987 made of corrosion free G.I.Pipes having Outer pipe dia of 80 mm having 80-200 Micron galvanising, Inner pipe dia of 40 mm having 200-250 Micron galvanising, connection terminal dia of 14 mm with constant ohmic value surrounded by highly conductive compound with high charge dissipation suitable for following type of applications. [B] For electrical installation up to 440 V Length of Pipe - 2 Mtr Back filling compound - 1 Nos. of Bag of 15 Kgs.	2.00	Nos	0.00	0.00
191	Providing and erecting required size HOT deep Galvanised iron strip for earthing of H.T. , OCB/ ACB/ Transformer LT panel board, Motors etc. using proper clamp.	60.00	KG	0.00	0.00
192	Providing and erecting Annealed bare Copper wire 8 to 16 SWG.	40.00	KG	0.00	0.00
193	Providing and erecting HOT deep Galvanised iron strip wire 8 to 16 SWG.	40.00	KG	0.00	0.00
194	Providing and fixing approved make Perforated C type cable tray. Made from pre- galvanized CR sheet steel. The cable tray should be bended as per IS 2062/1079 . with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..150 X 50 X 1.5 mm Thick	100.00	RMT	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
195	Providing and fixing approved make Perforated C type cable tray. Made from pre- galvanized CR sheet steel. The cable tray should be bended as per IS 2062/1079 . with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge.300 X 50 X 1.5 mm Thick	100.00	RMT	0.00	0.00
196	Providing and fixing approved make Perforated C type cable tray. Made from pre- galvanized CR sheet steel. The cable tray should be bended as per IS 2062/1079 . with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge. (7) 600 X 50 X 1.5 mm Thick	10.00	RMT	0.00	0.00
197	Providing and fixing approved make '90° Elbow' for Perforated C type cable tray. Made from pre galvanized CR sheet steel. The Junction should be bended as per IS 2062/1079. with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..(b)90° Elbow (3) 150 X 50 X 1.6 mm Thick 90° Elbow	4.00	EA	0.00	0.00
198	Providing and fixing approved make '90° Elbow' for Perforated C type cable tray. Made from pre galvanized CR sheet steel. The Junction should be bended as per IS 2062/1079. with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..(b)90° Elbow (5)300 X 50 X 2.0 mm Thick 90° Elbow	4.00	EA	0.00	0.00
199	Providing and fixing approved make '90° Elbow' for Perforated C type cable tray. Made from pre galvanized CR sheet steel. The Junction should be bended as per IS 2062/1079. with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..(b)90° Elbow (7) 600 X 50 X 2.0 mm Thick 90° Elbow	2.00	EA	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
200	"Supply Installation Testing Commissioning of Indoor deep Recessed Round downlight 12-15W Recess Mounted Round backlit downlighter with below features 1. Pressure die cast Aluminum alloy housing for better thermal conductivity. 2. PS diffuser for optimum light transmission. Round Version. 3. Efficacy of Fixture more then or equal to 85 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80 High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 5. LED life of more then 35000 Hrs @ L70. TISVA LIGHTING (USHA INTERNATIONAL LTD) recess mounted die cast downlight VITO 13w DLP13W4K11 Equalant in LIGHTING TECHNOLOGIES/ENDO/LIGMAN"	177.00	EACH	0.00	0.00
Total Amount					0.00
E	Part-5				
201	Supply Installation Testing Commissioning of decorative indirect wall light longer then 600mm 24-30w with below features Colour : steel, black, white / plastic, satined Dimmensions: L 620, H 80, A 90 Wattage: 26-30w Output < 2500Lms Fixture should be more the IP44 rated EGLO make 99691 SANIA 5 or equilant in Lighting technologies/ENDO/LIGMAN	3.00	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
202	<p>Supply Installation Testing Commissioning of Indoor Surface mounted COB type cylinder Light 12W-15w Surface Mounted COB Spotlight downlighter with below features Pressure die cast Aluminum alloy housing for better thermal conductivity. Powder coated using Nano technology for longer durability. PS diffuser for optimum light transmission. Efficacy of Fixture above 95 Lumens /watt Available with 5700K, 4000K & 3000K CCT. CRI>80 High efficiency driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD. Tilttable. LED life of 50000 Hrs @ L70. IP20 Protection Luminaire performance & Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, Surge : IEC 61000-4-5, EMC : EN 55015. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) PF >=0.95 and THD <=5 % (Certificate need to be submitted from NABL Accredited lab) The manufacturer should be ISO 9001 -2008 and ISO 14001 -2004 Company The manufacturer should have their own driver Manufacturing Facility. The manufacturer should have their own NABL accredited lab Equivalent to Lighting Technologies Intenso Min 15w.or Equalant in ENDO/LIGMAN"</p>	6.00	EACH	0.00	0.00
203	<p>Supply Installation Testing Commissioning of decorative recess wall mounted step/foot light 3-9w with below features Colour : steel, nickel, white,black Dimmensions: 150X300 Wattage: 3-9w Output : 200-500Lms</p>	46.00	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
204	<p>Indoor BATTEN Lighting 28W-33w 1200MM Surface mounted TUBE LIGHT/batten with below features Extuded Aluminum alloy housing for better thermal conductivity. Powder coated using Nano technology for longer durability. PS diffuser for optimum light transmission or option of Lens Based profile for better task lighting. Option to be selected by Architect / Consultant Efficacy of Fixture 95 Lumens /watt Available with 5700K, 4000K & 3000K CCT. CRI>80 High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD LED life of 50000 Hrs @ L70. IP20 Protection Luminaire performance & Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, Surge : IEC 61000-4-5, EMC : EN 55015. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) PF >=0.95 and THD <=5 % (Certificate need to be submitted from NABL Accredited lab) The manufacturer should be ISO 9001 -2008 and ISO 14001 -2004 Company The manufacturer should have their own driver Manufacturing Facility. The fitting should be customizable and shapes like X,Y,+ i.e. corss/plus shape can be made using the profiles. FITTING SHOULD HAVE UP & DOWN EFFECT i.e. 30-40% of wattage should be upwards The manufacturer should have their own NABL accredited lab Equivalent to Lighting Technologies INDO BATTEN 28W 4ft OR Equivalent in Endo / Ligman.</p>	19.00	EACH	0.00	0.00
205	<p>Providing following type of Modular Type Accessories mounted with pvc / metallic box, single mounting base frame covered with textured / metallic front plate , modules erected with necessary connection. As</p>	20.00	EA	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
206	Supplying & erecting approved make Telephone Cable electrolytic copper conductor PE insulation twisted in two pairs, & wrapped with FRLS PVC tape & sheathed with FRLS PVC or HFFR outer Jacket suitable for telephone wiring & confirming to C-DOT erected in existing pipe. of following size of conductors & nos.of pairs. With necessary connections. [A] Conductor Size 0.5 mm. 2) Two Pairs	600.00	Mtr	0.00	0.00
207	Supplying & erecting Delton or approved make Telephone Cable electrolytic copper conductor PE insulation twisted in two pairs, & wrapped with FRLS PVC tape & sheathed with FRLS PVC or HFFR outer Jacket suitable for telephone wiring & confirming to C-DOT erected in existing pipe. of following size of conductors & nos.of pairs. With necessary connections.[B] Armoured(Jelly Filled) (2) Twenty Pairs	50.00	Mtr	0.00	0.00
208	Supplying & erecting Delton or approved make Telephone Cable electrolytic copper conductor PE insulation twisted in two pairs, & wrapped with FRLS PVC tape & sheathed with FRLS PVC or HFFR outer Jacket suitable for telephone wiring & confirming to C-DOT erected in existing pipe. of following size of conductors & nos.of pairs. With necessary connections.[B] Armoured(Jelly Filled) 3) Fifty Pairs	50.00	Mtr	0.00	0.00
209	Providing & erecting main Distribution (MDF) indoor type, back mounted frame. (c) Suitable for 50 pair	1.00	Ea	0.00	0.00
210	Supplying & erecting push button type telephone instrument having speaker phone Caller ID & hands free dialling system & 30 memories with display system (a) Single line BPL / SONY/ BEETEL or equivalent make.Cat : III & As per approved Make List.	20.00	EA	0.00	0.00
211	DOME CAMERA-Full HD 1080p 25/30 fps image with a 1/2.7" or 1/2.8" 2 MP sensor, 2.7-12 mm, F1.4, zoom lens, True WDR up to 140 dB ensures glare-free images, H.264 and MJPEG codec, triple stream support, IR LEDs provide up to 50 m (150') of illumination in dimly lit or nighttime scenes, Waterproof (IP67) and IK10 vandal resistant camera housing ,ONVIF Profile S and G compliant	10.00	Ea	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
212	Supplying & erecting approved make LAN cable of following size in existing pipe as per direction [D] CAT - 6e (For LAN, Telephone & Camera).	600.00	Mtr	0.00	0.00
213	Network Video Recorder: Supply, Installation, Testing and Commissioning of IP surveillance solution central management 1080P with minimum 16 Channel NVR 8 SATA HDD with 5 Client License, with required slots numbers of Hard Disk and slots to carry out 30Days backup. Recording speed at 25/30FPS.	1.00	Ea	0.00	0.00
214	Supply, Installation, Testing and commissioning of 1 TB Surveillance series Hard disk	2.00	Ea	0.00	0.00
215	SITC of Jack Panel, fully loaded with 24 nos. UTP ports for PCB based IO Jacks (RJ45, TIA-568C Category-6, Installation and Termination of all 24 nos. Category-6 UTP , unloaded with individually replaceable 24 nos. Category-6 I/O Jacks complying with TIA-568.C.2, as per given jack specification Shall be suitable for loading unshielded & shielded jacks for different category systems (CAT 6 & CAT 6A)	1.00	Ea	0.00	0.00
216	SITC of company fabricated patch cords shall conform to Cat- 6 & conductor shall be stranded for better flexibility Shall support network line speeds up to 1 Gbps Shall have RJ-45 jacks. (A) 1 Mtr	24.00	Ea	0.00	0.00
217	SITC of 24 x 10/100/1000BASE-T PoE ports 4 x Gigabit RJ45/SFP Combo ports Advanced L2 switching and security features L2+ Static Routing Optional "standard mode" or "surveillance mode" management user interface 193 W PoE budget	1.00	Ea	0.00	0.00
218	Providing & Erecting Network rack with following capacity with Necessary cooling fan,Cable manager,6A PDU,equipment rack with necessary mounting accessories. (A) 9 U	1.00	Ea	0.00	0.00
219	Providing & Erecting approved make following size of TV Co-axial flexible cable comprising inner conductor of solid bare copper insulated with Foam PE & Secondary conductor made of poly - Aluminium film bonded Al. Braids @ suitable coverage overall sheathed with black PVC insulation. b).RG-6	1000.00	Mtr	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
220	Providing following type of Modular Type Accessories mounted with pvc / metallic box, single mounting base frame covered with textured / metallic front plate , modules erected with necessary connection. As desired by Engineer In charge (4) TV Co-axial Socket outlet Cat.II	19.00	Ea	0.00	0.00
221	HVAC PART: Providing and erecting Inverter based approved make split air-conditioning unit consisting of condensing unit with variable speed fan motor, inverter type hermetically sealed rotary compressor with accessories etc. duly connected separately erected evaporating unit and blower motor with its accessories by means of extra supplied proper insulated copper tubing, drain PVC pipes suitable for (cost includes Eco Friendly green gas charging and 15A plug top & Remote Control & MS Stand) with necessary core cutting. (2)For 4/5 Star Rating of current year (C) for 1.7 to 2 ton capacity-Premium Cat.	21.00	Ea.	0.00	0.00
222	Rigid UPVC drain pipe of 10 Kg/cm ² . rating with 9 mm thick.nitrile rubber insulation.: (E) 19 mm dia.	100.00	Rmt.	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
223	<p>Gypsum MR grade Ceiling : M/F Suspended MR Ceiling includes Gypserra Perimeter Channel {Material-GI(IS513),YS-260Mpa,Finish- Galvanised 150GSM(IS27)} is fixed along the perimeter of existing wall/ partition with the help of HILTI HPS - 1 (6x40) impact anchor, at 600mm centres. Gypserra Ceiling Angle {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} is suspended by fixing it to the Gyproc soffit cleat {GI(IS513)YS-260Mpa,Finish-Galvanised 150GSM(IS277) }. Soffit Cleat and Gyproc Rawl Plug- Ø8x45mm {Material-IS 513 CR2 grade, Zinc coating (7 to 8 microns) pull out load- 6.8kN for M30 concrete grade} creating 1220mm x 1220mm grid. Gypserra™ Intermediate channel {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277) } is fixed to the Gypserra™ Ceiling Angle with M6 x 12mm Hex Bolt & Hex Nut arrangement {Material-As per EN 10083 Finish – Zinc Plating} or with 2 Nos of Ø4.2x13 Gyproc® metal to metal screw {Material-Carbon steel EN-ISO 7049/50 Finish- Zinc Coating Thickness- 4.14micron.} The Gypserra™ Ceiling Section {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} is then fixed to the Gypserra™ Intermediate Channel {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} with the help of Gyproc® Connecting Clip {Material-High carbon spring steel wire(BS970Gr.En42)-46-48HRC,Finish-Zinc plating 4-6 micron} and in direction perpendicular to the Intermediate channel at 457mm c/c. Single layer of 12.5mm tapered edge Gyproc® MR (conforming to IS 2095 Part 1:2011/ EN 520:2004, Type-A & H1/ASTM C1396) is then screw fixed to ceiling section with 25mm drywall screws {Material-Carbon steel EN-ISO 7049/50,Finish-Case hardened Grey Phosphating} at 230mm centres on ceiling section & 150mm at periphery of ceiling. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Gyproc® Pro-Fill Jointing compound (Conforms to ASTM C475), Gyproc® Joint Paper tape. Serrated section has effective thickness of 2T (2xdepth), better load carrying capacity, enhanced screw retention, Improved acoustic performance & fire resistance as compared to plain steel section. All Gypserra™ metal components are patent applied for.(Application No. 201741018271)</p> <p>The item includes providing and fixing trap door of size 600 X 1200 mm as per approved sample of Ceiling panels comprise of a powder-coated beaded steel frame with gypsum / plywood board door. Each panel features a push- latch closing mechanism with door retaining safety cable & hook.Suspenders from ceiling to support the frame and trap door firmly along with necessary hilti fastner, cleats, screws, angles, packing, , safety measures etc. complete work. Necessary cutting / providing openings in the ceiling for AC fixtures, grills, electrical fittings, or other utility services, hatch openings etc. shall be provided by the Contractor and cost of making such modifications shall be included in the price.</p>	689.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
224	Wooden ceiling finish with VNR Laminate : " -----Do-----" as per above specification for complete work. Only finish with VNR laminate instead of veneer.	5.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
225	<p>Metal Ceiling: Supplying and Installing metal ceiling - Linear 184-C Galvanized Steel 0.50mm TCT Plain Wooden Powder Coated on visible surface of Panel and backside framing in regular black color Metal False ceiling System.</p> <p>Panel (Galvanized Steel): Metalium make 184C Panels are roll formed using state of the art roll forming lines to 84mm wide, 12.5 mm deep & 0.5 mm TCT Galvanized Steel as per IS-513 with recessed flange of 24 mm. Panel length is up to approximate 5 mtr. Panel shall be Wooden Powder coated on external surface only. When two panels are to be joined, they shall be joined together by means of panel coupler suitable for 184C Panel.</p> <p>Paint Detail: Wooden Powder Coated panel shall be chromatized for maximum bond between metal and paint, enamelled twice under high temperature, one side with full primer and finish coat, the other side (Inner side) with a primer coating and skin coat on continuous paint line or Powder coated panel shall be 50 microns thick on exposed surface.</p> <p>Installation detail: The carrier shall be suspended from slab/truss by 4mm dia galvanized rod & height adjustment powder coated spring steel clips at maximum 1.2 to 1.5 meter centre to centre. The 4mm dia galvanized rod shall be fixed to slab by forming one end "J" shape with roll inserts.</p> <p>Carrier 184-C: Carrier shall be 20mm wide at bottom and 39 mm deep with cutouts to hold the panel in a module of 200 mm, carrier shall be roll formed out of 0.45 mm GI coil and cut to a standard length of 2.5 mtr. When two or more carriers are to be joined, they shall be joined together by means of carrier coupler which will clip on to the holes in the sides of the cut carrier and hold them firmly in place while maintaining the module of 200mm centre to centre. Edge Profile: Edge profile shall be L- shaped, roll formed out of 0.5mm Galvanized steel strips with coil coating or powder Coating in standard colors. Work complete including all type of material, fittings , fixtures, Finish, safety measures , loading , unloading , transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights etc complete as per detailed drawings ,specifications & instruction of Client/EIC.</p>	15.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
226	Frosted sparkling glass film (Colour film) : Providing and fixing frosted glass film of approved make Translucent, cast PVC, self-adhesive vinyl, special CRYSTAL-effect film to reproduce Sand-blasting effect on glass with customised designs. MCS warranty of 3 (if exposed to direct sunlight) to 10yrs (indoors) must be endorsed by manufacturer. Rate shall be inclusive plotter cutting design as per Architect/Client suggestion. Contractor shall provide shop drawing for approval of Architect/Client.work complete including all type of tools, tackles, scaffolding etc complete as per suggestion of Architect/Client. If in case any application finishing will not as per satisfaction contractor shall remove all film at their cost. Contractor shall do a sample mock of 5 Sqm minimum of glass film), shall be approved from Architect/Client.	5.00	Sq.mt	0.00	0.00
227	Alluminium Skirting : Providing and Fixing ofAluminium Skirting as per approved make having width of 75 MM X thickness of 2mm made out of 6063 Grade Aluminium alloy duly powder coated as desired in the Ral Colour code decided by the architect having neat screw fixed arrangement with Rubber seal over it as per Manufacturers Specification. work complete as per the instruction of Architect. Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, placing at all floors and for all leads,all accessories as described in item description.	50.00	Rmt	0.00	0.00
228	Laminate Panelling : " -----Do -----" as per above item specification for complete work . using 1 mm thick laminate instead of veneer for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs. Equivalent to VNR Series Laminate.	9.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
229	Gypsum panelling: Gypsum panelling :The M/F wall lining includes 12.5mm Gyproc® Quattro Gypsum Board, screw fixed with drywall screws of 25mm at 300mm centers to one side of 45X18X0.5mm Gypliner ceiling channel (0.5mm thick having 18mm flange each made of GI Steel) placed at 600mm center to center in 195X29.5X0.9mm fixing bracket at 900mm c/c with 25X25X0.5mm Gypliner angle at bottom and top of the channel such a manner that joints staggered to avoid leakage through joints. Fixing strip of 75X0.5mm should be installed at horizontal joint of boarding. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Jointing compound and Joint Paper tape. 50mm Glasswool of density 20kg/m3 should be placed in metal frame.Necessary fabrication with anticorrosive paint work , scaffolding, anchor fasting , bolting HILTI or equivalent make with testing certified in scope of contractor)Rate shall include cost of making of all cut-outs for light fixtures, switchboards gadgets, gizmo, pelmets, grooves, beads cut out as per EIC instruction at siteThe rate shall be in sq.mt for all floors and at all heights including all costs. The shop drawing (or a sample mock of 5 Sqm minimum of the frame work and partition) shall be approved from EIC and Architect.Panelling item including openable shutter wherever required area and finish with the same material. Only the clear elevation area shall be measured and paid.	120.00	Sq.mt	0.00	0.00
230	Extra labor rate for providing various sizes as per the detailed drawing CNC cutting / Engraving work for any type of material approved by EIC / Architect. The rate shall be for all floors, at all heights, all shapes including all costs.	30.00	Sq.mt	0.00	0.00
231	Soft Board : Providing and fixing on wall 12mm thick approved quality soft board with cotton cloth/fabric of approved make and shade on 12mm thick IS 710 ply 50 mm th approved Glass wool sheet with PVC grip , as approved sample and as directed by EIC. The work shall be measured & paid in Sqm. for all floors, all level and at all heights including all costs .Only the clear elevation area of the cloth/fabric shall be measured and paid. All the work complete as per the detailed drawing , mockup sample and instruction of Architect/EIC. Basic rate of cotton cloth /fabric for 54" wide shall be Rs 200/Rmt	2.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
232	Ply palmet : Providing and fixing wooden pelmets of upto 200 mm x 300 mm L shape made of 19mm thick ply as per IS 710 and beading of 4mm thick and 25mm wide Ghana Teak wood for projection screen. Rate to be inclusive of lipping, cutting, wastages, necessary fixtures, nails, adhesives, necessary scaffolding, fixing at all heights and for all floors as per drawing and approved sample etc should also take load of all the all roller blinds.	27.00	Rmt	0.00	0.00
233	Eyelet Curtain : For Suite room Supply and installation of Eyelet curtains (3 Plit curtain) of approved make as per architect selection . Double rod with front sheer curtain and back main curtain as per selection of architect. Work complete incldung all type of stiching , fixing , accessories ,nclusive of installation, material cost, labor, wastage, operating system all tools tackles, scaffoldings, hardware at all floors, all levels and heights, necessary edge binding with approved fabric and thread of colour similar to the colour of the blinds. Same rate shall be applicable for all heights and for all floors. height will be measured from top of the palmet to sill bottom lvl.height will be measured from top of the palmet to sill bottom lvl. MAIN FABRICS + SHEER FABRICS+ BLACKOUT : rate of Fabric is 950 / Rmt .	9.00	Sq.mt	0.00	0.00
234	Eyelet Curtain : For all other area : "-----Do-----" as per above specification for complete work . Supply and installation of Eyelet curtains(3 Plit curtain) of approved make as per architect selection. MAIN FABRICS + BLACKOUT : rate of Fabric is 650 / Rmt.	23.00	Sq.mt	0.00	0.00
235	Dining area table : 2800 x 1000 mm: Providing & placing of Dining table as per drawing and ref Image. Table Top: 18 mm thick Granite stone as per approved sample by Architect. Frame Structure: MS Hollow Box section with Powder coating as per drawing. item including of Including cost of all type of tools, tackles, scaffolding, all labour, materials, wastages, transportation, finishing, all type of fabrication & steel work, accessories, for all floors, all heights, all levels and all places within campus. Basic rate of Granite stone 150/-Sq.ft	1.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
236	Dining area table : 2400 x 750 mm : "-----Do-----" as per above specification for complete work. Basic rate of Granite is 150/ Sq.ft	1.00	Nos	0.00	0.00
237	Dining area table : 1200 x 750 mm : "-----Do-----" as per above specification for complete work. Basic rate of Granite is 150/ Sq.ft	2.00	Nos	0.00	0.00
238	Dining area chair : Supplying and placing Fix Chair with Seat. as per approved and selection by Architect/ Client. Make: Amardeep or equivalent make as per approved make list. tapperd Legs at the base duly polished. Work complete including all necessary Solid wood , polish , hardware and fittings , mock up sample, loading,unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic rate of fabric 1000/ Rmt	8.00	Nos	0.00	0.00
239	Dining area chair : Supplying and placing Fix Chair with Seat. as per approved and selection by Architect/ Client. Make: Novella 09 of Nilkamal or equivalent make as per approved make list .tapperd Legs at the base duly polished. Work complete including all necessary hardware and fittings , mock up sample, loading,unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	12.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
240	<p>Double Bed with Back panel : Size 2050x1800 mm: Bed : KING SIZE BED WITH HEADBOARD (SOLIDWOOD FINISH) as per detail drawings. Providing bed without under storage unit with necessary SOLID WOOD (Mango wood / Seesam) structure with polish as per approved make by Architect/Client. Solid wood shall be approved by Architect. Work complete including all type of material, Solid wood fittings , fixtures,Finish, loading , unloading ,transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights, etc complete as per drawings ,specifications & instruction of Client/EIC.</p>	14.00	Nos	0.00	0.00
241	<p>Side Unit : Rooms 1 to 4 : Size : 450 mm x 450 mm Providing and fixing side table with 2 drawers unit with necessary SOLID WOOD (Mango wood / Seesam) structure with polish as per approved make by Architect/Client. Solid wood shall be approved by Architect. Work complete including all type of material, Solid wood fittings , fixtures,Finish, loading , unloading ,transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per drawings ,specifications & instruction of Client/EIC.</p>	28.00	Nos	0.00	0.00
242	<p>Double Bed with Back panel : Size 2050x1800 mm: Bed : KING SIZE BED WITH HEADBOARD (SOLIDWOOD FINISH) as per detail drawings. Providing bed without under storage unit with necessary SOLID WOOD (Mango wood / Seesam) structure with polish & Fabric finish as per approved make by Architect/Client. Solid wood shall be approved by Architect. Work complete including all type of material, Solid wood fittings , fixtures,Finish, loading , unloading ,transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per drawings ,specifications & instruction of Client/EIC. Farbic rate - 1000/ Rmt</p>	5.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
243	Side Unit : Main building Suite room : Size : 450 mm x 450 mm Providing and fixing side table with 2 drawers unit with necessary SOLID WOOD (Mango wood / Seesam) structure with polish as per approved make by Architect/Client. Solid wood shall be approved by Architect. Work complete including all type of material, Solid wood fittings , fixtures,Finish, loading , unloading , transportation, all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per drawings ,specifications & instruction of Client/EIC.	10.00	Nos	0.00	0.00
244	Writing desk : @ 450-500 mm width : Suite room Providing and fixing 35 mm thick Writing desk with drawer unit comprising from MR grade ply with 1 mm thick VNR laminate finish as per approved sample. Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transportation, all leads ,accessories, PVC edge beading , sample mockup, all floor , all levels, all heights , etc complete as per drawings ,specifications & instruction of Client/EIC. Basic rate of VNR Laminate is 50/ Sq.ft	7.00	Rmt	0.00	0.00
245	Writing desk : @ 450-500 mm width : Rooms 1 to 4 "-----Do-----" as per above specification for complete work Basic rate of VNR Laminate is 45 Sq.ft	19.00	Rmt	0.00	0.00
246	Writing desk & Living room chair : Suite room Supplying and placing Fix Chair with Seat. as per approved and selection by Architect/ Client. Make: Delta of Amardeep or equivalent make as per approved make list Work complete including all necessary Solid wood , polish , hardware and fittings , mock up sample, loading,unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic rate of fabric 1000/ Rmt	5.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
247	<p>Writing desk & room chair : Rooms 1 to 4 Supplying and placing Fix Chair with Seat. as per approved and selection by Architect/ Client. Make: Delta of Amardeep or equivalent make as per approved make list. Work complete including all necessary Solid wood , polish , hardware and fittings , mock up sample, loading,unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic rate of fabric 800/ Rmt</p>	14.00	Nos	0.00	0.00
248	<p>Double Bed Mattress : Size : King size bed mattress : 5.5'X6'X8" : For Suite room Mattress of Kurlon, Sleepwell, springfit,Peps Industries Pvt. Ltd, Spring Air. or as per approved make and sample by Architect . Model equivalent to SPRING AIR BASIC - DOUBLE POSTURE : BONNELL P.U. FOAM BOTH SIDE : 5.5'X6'X8" Mattress comprising from Bonded foam with softy sandwich layer of 100mm thick with 50mm thick softy foam which is from standard make, Both foam are fix with standard glue with both side kwilted cotton fabric cover, Bed all edges are stitch with piping finish with standard finishing, Cotton kwilt of Dark colour decorative shade require & mockup sample approved by the Architect/ EIC. Work complete including all type of material, fittings , fixtures,Finish, loading , unloading ,transporation, , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per drawings ,specifications & instruction of Client/EIC.</p>	5.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
249	<p>Double Bed Mattress : Size : King bed size mattress : 5.5'X6'X 6" : Other room Mattress of Kurlon, Sleepwell, springfit,Peps Industries Pvt. Ltd, Spring Air. or as per approved make and sample by Architect . Model equivalent to SPRING AIR BASIC - DOUBLE POSTURE : BONNELL P.U. FOAM BOTH SIDE : 5.5'X6'X8" Mattress comprising from Bonded foam with softy sandwich layer of 100mm thick with 50mm thick softy foam which is from standard make, Both foam are fix with standard glue with both side kwilted cotton fabric cover, Bed all edges are stitch with piping finish with standard finishing, Cotton kwilt of Dark colour decorative shade require & mockup sample approved by the Architect/ EIC. Work complete including all type of material, fittings , fixtures,Finish, loading , unloading ,transporation, , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per drawings ,specifications & instruction of Client/EIC.</p>	14.00	Nos	0.00	0.00
250	<p>Pillow : 17" x 27" Providing and supplying standard make full size recron pillow . Pillow cover stitched properly with standard stitching. Pillow of standard quality with stadard make. Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per Shop drawings ,specifications & instruction of Client/EIC.</p>	38.00	Nos	0.00	0.00
Total Amount					0.00
F	Part-6				
251	<p>CUSHION : 16 " x 16" Providing and supplying Cushion (Recron) as per approved make & Sample Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all</p>	38.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
252	Cushion cover : Providing and supplying as per approved make & Sample of cushion cover (Polyster / Cotton). Work complete including all type of material, fittings, fixtures, Finish, loading, unloading ,transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per Shop drawings ,specifications & instruction of Client/EIC.	16.00	Rmt	0.00	0.00
253	Bedcover for double bed of suite room Providing and supplying double bed bed cover (cotton) as per approved make & Sample . Work complete including all type of material, fittings , fixtures,Finish, loading , unloading transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per Shop drawings ,specifications & instruction of Client/EIC.	5.00	Nos	0.00	0.00
254	BEDSHEETS WITH PILLOW COVER : (White 250 TC) : For Double bed Providing and supplying bedsheet with pillow cover as per approved make & Sample . Work complete including all type of material, fittings , fixtures,Finish, loading , unloading transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per Shop drawings ,specifications & instruction of Client/EIC.	19.00	Nos	0.00	0.00
255	BED RUNNER WITH STITCHING: Providing and supplying as per approved make & Sample of Bed runner cover (Polyster / Cotton). Work complete including all type of material, fittings , fixtures,Finish, loading , unloading ,transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per Shop drawings ,specifications & instruction of Client/EIC.	10.00	Rmt	0.00	0.00
256	TV Ledge : Providing and fixing 35 mm thick Writing desk comprising from MR grade ply with 1 mm thick VNR laminate finish as per approved sample. Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per drawings ,specifications & instruction of Client/EIC. Basic rate of VNR Laminate is 50/ Sq.ft	33.00	Rmt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
257	<p>Wardrobe : VNR Laminate finish Providing, making and fixing wardrobe units in position as per drawings. Front solid shutter : 25 mm thick IS 303 BWR ply with both side laminate finish. Back side : 12 mm thick IS 303 BWR ply with one side laminate finish Bottom & Side : 19 mm thick IS 303 BWR ply with both side laminate finish Shelves/Divider : 19 mm thick IS 303 BWR ply with both side laminate finish as per approved sample by Architect/Client. Drawer Unit : 2 Nos of Drawer unit as per drawing. Hardware : All necessary brass satin finish nickel plated/ S.S 304 grade (hardware from Hettich like Auto Hinges, handle, Multipurpose lock, Telescopic channel, S.S. pipe oval Hettich (047 615) , tower bolts, ball catches/Magnet, hydraulic hinges etc as per approved sample. Skirting : 75 mm ht skirting with laminate finish. Edge Finish : All the exposed edges are with 2mm PVC edge Imported banding & sealed edges are with 0.8mm thick PVC Imported edge banding. Work complete including all type of material, fittings , fixtures,Finish, loading , unloading ,transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights ,necessary grooves etc complete as per detailed drawings ,specifications & instruction of Client/EIC.Basic rate of VNR Laminate is 50/ Sq.ft</p>	58.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
258	<p>Below counter Storage with Veneer finish : Providing, making and fixing wardrobe units in position as per drawings.</p> <p>Front solid shutter : 25 mm thick IS 303 BWR ply with both side Veneer finish with polish</p> <p>Back side : 12 mm thick IS 303 BWR ply with one side Veneer finish with polish</p> <p>Bottom & Side , shelves/Divider : 303 BWR ply with Veneer finish with polish</p> <p>Hardware : All necessary brass satin finish nickel plated/ S.S 304 grade (hardware from Hettich like Auto Hinges, handle, Multipurpose lock, Telescopic channel, S.S. pipe oval Hettich (047 615) , tower bolts, ball catches/Magnet, hydraulic hinges etc as per approved sample.</p> <p>Skirting : 75 mm ht skirting with Veneer finish with polish.</p> <p>Edge Finish : All the exposed edges are with 2mm PVC edge Imported banding & sealed edges are with 0.8mm thick PVC Imported edge banding.</p> <p>Work complete including all type of material,Haffele/ Hettich fittings , fixtures,Finish, loading , unloading ,transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights ,necessary grooves etc complete as per detailed drawings ,specifications & instruction of Client/EIC. Basic Rate for material only teak veneer - 120/Sqft.</p>	5.00	Sq.mt	0.00	0.00
259	<p>Below counter Storage with VNR laminate finish :</p> <p>" -----Do----- as per above specification for complete work . Using 1 mm thick VNR laminate instead of Veneer . Basic Rate of VNR laminate is 50/ Sq.ft</p>	12.00	Sq.mt	0.00	0.00
260	<p>Luggage rack: Size : 900 x 450-500 mm</p> <p>Providing and fixing on site in required position 35 mm thick top with wooden framing and finish with 1 mm thick laminate as per suggested by Architect complete. The work including 4 mm thick ss strip , all necessary frame work and fittings accessories,and lighting arrangment work complete as per the detailed drawing.</p> <p>Work complete including all type of material, fittings , fixtures,Finish, loading , unloading ,transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per Shop drawings ,specifications & instruction of Client/EIC.</p>	19.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
261	<p>Pantry below storage : Providing, making, fixing as per detail drawing made from 19 mm IS 710 BWP ply structure and both side 1 mm th laminate finish shall be of approved make & shade and as per the detail drawing. All the edges of ply shall be covered with Laminate finish Rate shall also inclusive of all necessary brass satin finish nickel plated/S.S 304 grade hardware like Hinges, locks, 6" handle , 75 mm tower bolts, ball catches/Magnet, The rate shall be inclusive of shelf both side laminated finish and as per detail drawer unit with SS 304 grade kitchen basket as per selction by architect The rate shall be in sqm of elevation area for all floors and at all heights including all costs complete as per the Architectural drawings & instructions. Only the elevation area of the storage unit will be measured and paid for. Item for laminate fixing and polishing is included in this item. Approval of all loose material (sample of materials to be used) & raw manufacturing to be got approved in advance from EIC & Architect prior to the final production of the work. Manufacturing shall in parts or as whole as per the requirements & or assembled at site as per the requirement and directed by EIC & Architect. All material to be used shall be as per the drawings & confirm to the relevant detailed material specifications of this document. The work shall be measured & paid in sqm The rates shall be inclusive of all wastages, material, labor, transportation, loading, unloading, fixing in position, etc. complete to the satisfaction of the Architect and EIC. The mock-up of 1 unit shall be approved from EIC and Architect prior to the final production . Basic rate of laminate is 45 /Sqft.</p>	6.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
262	<p>Pantry above storage -350DX600 H: Providing, making, fixing as per detail drawing made from 19 mm IS 710 BWP ply structure and both side 1 mm th laminate finish shall be of approved make & shade and as per the detail drawing. All the edges of ply shall be covered with Laminate finish Rate shall also inclusive of all necessary brass satin finish nickel plated/S.S 304 grade hardware like Hinges, locks, 6" handle, 75 mm tower bolts, ball catches/Magnet, The rate shall be in sqm of elevation area for all floors and at all heights including all costs complete as per the Architectural drawings & instructions. Only the elevation area of the storage unit will be measured and paid for. Item for laminate fixing and polishing is included in this item.</p> <p>Approval of all loose material (sample of materials to be used) & raw manufacturing to be got approved in advance from EIC & Architect prior to the final production of the work. Manufacturing shall in parts or as whole as per the requirements & or assembled at site as per the requirement and directed by EIC & Architect. All material to be used shall be as per the drawings & confirm to the relevant detailed material specifications of this document. The work shall be measured & paid in sqm. The rates shall be inclusive of all wastages, material, labor, transportation, loading, unloading, fixing in position, etc. complete to the satisfaction of the Architect and EIC. The mock-up of 1 unit shall be approved from EIC and Architect prior to the final production. Basic rate of laminate is 45 /Sqft.</p>	6.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
263	Console : Providing & fixing Console complete as per drawing/Ref Image. Approx size : 1500 x 400 x 600 mm made from up of 19 mm thick BWR grade ply & finished of Veneer with PU polish as per approved make and shade and solid wooden leg with matt finish monocoat polish as per drawing. Rate shall be inclusive of providing, fixing all necessary brass satin finish nickel plated/ S.S 304 grade (hardware from Hettich like Auto Hinges, handle, Rod locks, Multipurpose lock, Rate shall be inclusive of internal shelves of 19mm thick IS 303 BWR ply and laminate , PVC edge beading . All external & internal exposed woodwork to be finished in PU semi gloss paint finish polish as per specified item's manufacturer's specifications.Rate shall inclusive of providing mock up sample for approval of architect. Basic Rate for material only veneer - 120/Sqft.	4.00	Nos	0.00	0.00
264	Planter box: Providing making, fixing as per detail drawing and required length and depth shall be made from 19mm IS 710 BWP ply with both side laminate finish and providing lighting arrangement cutout and fixing as per detail drawing and instruction. Rate shall inclusive all necessary hardware and fitting, ms framing, paint. The work shall be done as per the specifications, sample approved and as directed by the Architect/ Client. Rate shall inclusive of providing mockup sample for approval of Architect/ Client. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessorie, sample mockup etc as described in item description.work complete as per the instruction of Client/EIC.	7.00	Sq.mt	0.00	0.00
265	Planter box finished with Coloured HDF : " -----Do-----" as per above specification for complete work . Only 8 MM thick Coloured HDF with PU polish instead of Laminate finish.	2.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
266	Texture paint :Wall painting two coats with Stucco of Asian or equivalent approved brand in any shades and colour as directed on wall surface to give an even shade including applying of a one coat of Penetrating primer or equivalent and two coats of paint, scaffolding to at any height with all labour and material thoroughly brushing the surface free from mortar droppings and other foreign matter and sand prepared smooth etc. complete. The substrate must be sound, clean, dry, free from dust, oil, grease and laitance etc. All traces of release agents must be removed. On chalky and dusty surfaces, all loose material must be removed by stiff bristle brushing. The primer / paint application is to be done with the rollers. rate shall be including, safety measures , crack filling and levelling as per manufacturers specification. Top coat should have. 1) Low VOC content. 2) Crack Bridging ability upto 2.6 mm. 3) 100% pure acrylic emulsion 4) Anti-Carbonation concrete protection 5) Very Low Flame spread 6) Superior Washability	228.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
267	<p>Art work: Providing and fixing in position commissioned art works inside the building on the wall or ceiling and extension of the same till floor/ceiling. The composition of the commissioned art work shall be from any type of wood, metal like copper, brass, SS, MS, fabric, acrylics, rubber, plastic, tough boards, cement fibre board, HDF board, artificial stone, natural stone, gypsum, POP etc. all. The form of material may also vary based on material properties like sheets, wires, blocks, inclusion of cut-outs, bending of the materials, profile cutting and shaping of the materials, manufacturing at site as well as at site, covering the prepared material by means of the bubble sheets, jute bags or in wooden packing materials. The commissioned art work may require any shade, finish and texture of duco painting, specialty painting, PU painting, general painting to paintable surfaces, galvanizing, powder coating, anodizing etc.. The base surface where the commissioned art work is to be installed also needs some modification to enhance the effect of art works. The use of material like fibre glass wool/ boards, filler fabric, mounting material may also be essential based on the design of the art work by artist. The rate shall be inclusive of any type of lighting features to be added into it includes LED lights, neon lights including its supporting and suitable wiring for the same within the art works. Only one electrical control point connection will be given as close to art works. The rate shall be inclusive of making necessary provisions within the commissioned art works of fixing of the same. The provisions of the fixing of the art work may be in parts but it shall be inclusive of the all arrangements like LN key, studs, anchors, nuts and bolts etc. all.. The concept of the art work will be generated by architect and interior designer and based on that offers from the artists to be invited for design and execution of the artwork. The selection of the artist is to be done by architect and interior designer only. Main contractor is bound to follow the methodology suggested by architect and interior designer to be followed for development of commissioned art work. Contractor shall submit 3d model/sketch as per given concept by Architect for further approval of design. Appointed artist shall provide basic mock-up sample as per architect requirement for approval. The overall outline area covered by art work is to be considered for the measurement instead of actual area of art work. The quotations of the artist shall be got approved in advance including area of the proposed art works. Total payment of the artwork will be done as per basic rate and difference between actual cost per sqm and basic rate per sqm will be added or deducted without any consideration of the, overhead and profit over the difference. It is the responsibility of the main contractor to provide scaffolding, power, water, facilitating the areas required for developments and storage of the art work etc. The protection and cleaning of the pre and post installation of the art work is the responsibility of the main contractor.</p>	1.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
268	Signages : Providing and fixing signages comprising form SS 304 grade plate with Vinyl film letter , HDF finish as per instruction of Archiect/EIC. Contractor shall submit mock up sample.	3.00	Sq.mt	0.00	0.00
269	Logo Work : Providing and fixing standard Logo using virgin acrylic or other material like Colored HDF/cementsheet /SS plate with CNC work complete as per architect selection , letters as per detailed drawings and fixed with approved adhesive with necessary fittings and provision shall be made for conceal LED light as per detail drawing. (logo size will be aprox. Size - 600 mm dia)	1.00	Nos	0.00	0.00
270	Signages: 3D letters with LED : Wall Mounted Material : 3 mm thick exterior grade premium quality ACP sheet (0 .25 mm foil thickness) & and 3D Embossed virgin acrylic/aluminum letters as per approved make and sample by Architect/ Client. Led Light : Rishang(Korea) and SMPS as per approved make and sample by Architect/ Client. The rate shall be for complete item of Designing , providing , fixing & erection , inclusive of all material, labor, wastages, necessary tools & tackles, adhesives, required hardware/accessories , any type of framing work , engraving , required civil work with finishing , LED light . Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transporation, , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per drawings ,specifications & instruction of Client/EIC.	15.00	Sq.mt	0.00	0.00
271	Magazine rack : Providing & Fixing of MAGAZINE RACK as per detail drawings. Make : Metal Finish .Structure : Metal Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	1.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
272	Dressing Mirror : 900 x 2100 Providing & Fixing of DRESSING MIRROR as per detail drawings. Make : MR Grade Plywood Structure : Plywood + Mirror Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	19.00	Nos	0.00	0.00
273	Puffy : Providing & Fixing of Puffy as per approved sample by Architect. Make : Solidwood , Structure : Solidwood , Finish : Fabric Finish (Basic Rate of Fabric is Rs 800 Per Meter) Leg : Wooden Leg Finish : Approved Shade Polish on Wooden Leg Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	19.00	Nos	0.00	0.00
274	Metal wall cloak (350mm dia) : Providing, and fixing Metal wall clock as per sample approved by architect . Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	23.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
275	<p>Customised wall painting Canvas painting with frame work :Providing making painting/polishing and Fixing in position of wooden frames having profile as per drawing and sizes as specified for paintings with card board mounting /canvas frames including backing of required thickness of hardboard / ply board(IS 303 BWR) backing. Frame shall be hanged on the wall using key hole chaplas fixed at the back part of the frame at all heights, all floors and all levels. The rates shall be inclusive of all material, labour, wastage, antitermite treatment, polishing all tools tackles etc complete. Sample of the frame shall be got approved by Architect prior to manufacturing on large scale. D) Wooden Frames for Canvas Work as per drawings: Frame Size - 75mm x20mm Wood Work - Burma Teak Wood Frame shall be finished with PU polish work. The art work shall be hanged on the wall using heavy duty approved key-hole chaplas</p>	2.00	Sq.mt	0.00	0.00
276	<p>Painting : Providing Wall painting as per Architects selection . Basic rate of painting is 3000/- Nos Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	25.00	Nos	0.00	0.00
277	<p>Artifacts : Providing and supplying Artifacts as per selection . Glass/Metal/Fiber/Ceramic Basic rate of Artifacts is - 2500 Nos Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	15.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
278	Door mat : 400 mm X600 mm Providing and supplying Antiskid Door mat (BATHMAT - OBSSSION (DIANA)) as per selection . Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	22.00	Nos	0.00	0.00
279	Door mat : 450 mm X750 mm Providing and supplying DOORMAT- SUPERLIVING (MATH WITH RUBBER BACKIN) POLYSTER/JUTE as per selection . Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	19.00	Nos	0.00	0.00
280	Dustbin : Providing and placing in position SS brush finish (5 LTS PEDAL BIN/ STEP BIN -) of Karma Square Pedal bin 10x15 Stainless Steel Dustbin or Equivalent as per images and as selected by the Architect.	24.00	Nos	0.00	0.00
281	Dustbin : Providing and placing in position SS brush finish (12 LTS PEDAL BIN/ STEP BIN -) of Karma Square Pedal bin 10x15 Stainless Steel Dustbin or Equivalent as per images and as selected by the Architect.	2.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
282	<p>Sitting Ledge</p> <p>Providing and fixing ledge seating made from 40 density PU foam with fabric finish , necessary fabrication with paint , ply , fittings , fixtures , etc complete as per selection of architect & Reference Image.</p> <p>The work shall be done as per drawing specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, approved make for all floors, all heights, all levels and all places within campus.</p> <p>Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. The unit shall be manufactured in parts and these parts shall be assembled at site.</p>	33.00	Rmt	0.00	0.00
283	<p>Providing and fixing 12 mm thick Marine plywood conforming to IS: 710 / WPC board.</p> <p>Work complete including all necessary hardware and fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	70.00	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
284	<p>Head Table with One Drawer unit : 1800 x 750 x 750 mm Table Top : 25mm thick Exterior grade Prelaminated Partical board with matching PVC edge banding and aluminum flip up with anodized finish. Under structure : 25mm thick pre laminated Gable Ends with Ms Powder coated Beams. Modesty : 18 mm thick pre laminated partical board modesty Wire management : Powder coated wire tray with switch plate & PVC wire guard for wire management One Drawer Unit : Comprising from Exterior grade Prelaminated Partical board with matching PVC edge banding , handle & lock & key. All the exposed edges are with 2mm PVC edge Imported banding & sealed edges are with 0.8mm thick PVC Imported edge banding. PVC edge banding are imported from Rehau or Dolken of Germany. Work complete including all necessary hardware and fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	1.00	Nos	0.00	0.00
285	<p>Chair Type-6A (Other area Chair) -Model equivalent make - Model equivalent to Vento 02 : Mid Back Revolving Chair as per approved make list. Chair With frame in MS, PU foam in back & Moulded PU Seat, Chrome Arms with PU cladding & Synchro Mechanism, Chrome base, & Gas Lift. Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	1.00	Nos	0.00	0.00
Total Amount					0.00
G	Part-7 (Rate Only Item)				



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
286	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead. work complete Including cost of all labour, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	R/o	Sqm	0.00	0.00
287	Dismantling aluminium/ Gypsum partitions, ACP clading, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge. Work complete including all type of tools, tackles, scaffolding etc complete as per instruction of Architect/EIC.	R/o	Sqm	0.00	0.00
288	Earthwork in excavation by mechanical means (All type of soil) for foundation, footings, walls, retaining walls, rafts, trenches, drains, lift pits, underground sumps, tank, septic tanks, soak well, Box cutting etc. including dewatering the sub-soil water from any source and rain water to keep the excavation dry, removal of slush, dressing of sides and ramming of bottoms, planking, shoring & strutting, removal & disposal of surplus excavated material with all lead & lift. including compaction by using mechanical plate compactor / vibro roller, finished to desire levels all as per excavation plan and foundation drawings to get Modified Proctor Density test (MPD) of 95%., work including mechanical transport inclusive of royalty, statutory fees all permissions & any other incidental expenses etc. complete. ii) 1.5 to 3.0 Mtr Depth	R/o	Cu.mt	0.00	0.00
289	Providing and laying cement concrete 1:3:6 (1- Cement : 3- coarse sand : 6- hand broken stone aggregates 40 mmm nominal size) and curing complete including mixing laying, vibrating, consolidating, leveling and curing etc. complete with all labours and materials with formwork. The item includes finishing the top surface with trowel. Work complete including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (A) Foundation and Plinth	R/o	Cu.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
290	Providing and laying controlled cement concrete M.250 and curing complete. including mixing laying, vibrating, consolidating, leveling and curing etc. complete with all labours and materials with formwork. The item includes finishing the top surface with trowel, necessary admixtures etc. Work complete including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC. (excluding the cost of reinforcement) (A) Foundations, footings, Base of columns and Mass concrete.	R/o	Cu.mt	0.00	0.00
291	Providing and laying controlled cement concrete M.250 and curing complete. including mixing laying, vibrating, consolidating, leveling and curing etc. complete with all labours and materials with formwork. The item includes finishing the top surface with trowel, necessary admixtures etc. Work complete including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC. (excluding the cost of reinforcement) (C) Slabs, landing, shelves, Balconies, Lintels, Beams, Girders and Cantilever upto floor two level.	R/o	Cu.mt	0.00	0.00
292	Providing and laying controlled cement concrete M.250 and curing complete. including mixing laying, vibrating, consolidating, leveling and curing etc. complete with all labours and materials with formwork. The item includes finishing the top surface with trowel, necessary admixtures etc. Work complete including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC. (excluding the cost of reinforcement) (D) Columns, Pillars posts and struts, upto floor two level.	R/o	Cu.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
293	Providing and laying Autoclaved Aerated concrete (AAC) blocks masonry with 150mm/230mm/300 mm thick with Grade-I AAC blocks of density 551 to 650 kg/ cum conforming to IS: 2185 (Part 3) in super structure above plinth level up to floor all level with RCC band at sill level and lintel level with approved block laying polymer modified adhesive mortar all complete as per direction of Engineer-in-Charge. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC. The rate includes providing and placing in position 2 Nos 6 mm dia bars at every third course of masonry work.	R/o	Cu.mt	0.00	0.00
294	Exterior Texture Paint (Apex Ultima Allura Torino of Asian Paint code - PRODUCT CODE 5417): Providing and applying Stone finish Exterior Texture Paint in 2 coats paint + 1 coat primer with approved brand & manufacture to give an even and smooth shade of color of approved shade after thoroughly cleaning the walls by water and brushing to remove all dirt and remains of loose materials, up to all level above plinth complete ,scaffolding to any height ,curing etc complete. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning , at all floor, all level, all depth, all Height, all lead and lift, performance warranty certificate etc. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	R/o	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
295	Vitrified Tiles Flooring : Providing and laying Rustic / wood finish Matt type Vitrified tiles flooring using minimum 10 mm thick tiles of as per approved make list by architect/client, including preparing base for leveling with 20mm thick cement mortar 1:6 (1 cement : 6 coarse sand) and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction and approval by architect. The rate shall be inclusive of protection sheet. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning , at all floor, all level, all depth, all Height, all lead and lift , work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of tile is Rs. 35/Sqft	R/o	Sq.mt	0.00	0.00
296	Vitrified Tiles Skirting : Providing and laying in skirting using minimum 10 mm thick tiles as per approved make list by architect /client fixed in dado on 10 mm th. Cement plaster 1:3 (1 cement: 3 coarse sand) All surfaces must be dimensionally stable according to level, cured, undamaged, compact, rigid, resistant, dry and free from any debonding agents tiles fixed by approved tile adhesive and all application shall be done under instruction of manufacturer guideline and specification , and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction all complete as per approved sample by Architect, drawings and instruction of EIC. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning , at all floor, all level, all depth, all Height, all lead and lift, work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of tile is Rs. 35/Sqft	R/o	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
297	Granite Basin Counter for Toilet : Providing & fixing two layers of wash basin counter, first layer using 25mm thick Kotastone of approved shade and second layer using approved shade and sample of Mirror finish Granite, joined together with 1:4 Cement mortar bedding / approved tile adhesive , to true plane & level or to slopes, or close jointed with cement slurry with pigment of matching shade and colour and finishing with the same, including dedo 6", cutting kotah & tile as per required shape & size to fit Wash basin & 4" fascia with moulding, nosing, chamfered front edges, fixing, disposal of debris etc. finished as per design in detail drawing and instruction of Architect/EIC.sample mock shall be approved from Architect/EIC. Basic rate of granite is 120/ Sq.ft	R/o	Rmt	0.00	0.00
298	Single Leaf Flush Door finish with laminate with frame : Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make and finished with both side 1 mm thick laminate as approved sample. including Ply framing with both side Laminate as per drawing. including Hardware system of SS 304 Grade like Hinges, Mortise lock with knob, door closer, door stopper etc. as per approved make & Sample. work complete including all type of hardware, fittings, fixtures as per instruction of Client/ Architect etc. complete as per detailed drawings and specifications. sample mock shall be approved from Architect/Client. Equivalent to VNR Series Laminate. (Note: Door opening area shall be measured for payment. No extra payment shall be paid) Basic rate of VNR Laminate is 45 Sq.ft	R/o	Sq.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
299	<p>Aluminium Fins/Louvers (Elevation): Supplying and Installing of METALIUMTM make U- Shaped Baffle 50*50*50mm (50mm gap) Galvanized Steel 0.50mm TCT plain wooden powder coating on visible surface of Panel and supporting structure in black color Exterior Louver System.</p> <p>Panel (Galvanized Steel): Metalium make square edge P-50 series panels, 50 * 50 * 50 mm& 0.50 mm TCT Galvanized Steel. Panel length is up to approx. 3 mtr. Panels shall be wooden powder coated on visible surface with special Exterior Grade powder to enhance property of Fadedness Resistivity.</p> <p>P-50 Carrier (U Shaped): Black enameled Galvanized Steel Carrier of 20mm wide at bottom x 39mm deep x 0.6 mm thick in a standard length of 8' with cutouts to hold the panel in a module of 100 mm centre to centre at a distance of 1 mtr. Carrier and suitable structure shall be powder / coil coated on exterior face to enhance properties of Fadedness and corrosion resistivity.</p> <p>Installation Details: GS Clit shall be fixed on vertical columns with dash fasteners at distance not more than 1 mtr. Centre to centre on which Tubular Stud sections will be laid with corrosion proof screws and on this rigid structure carrier shall be fixed vertically / horizontally at distance of 1 mtr. Centre to centre. Panel shall be clipped to carriers. Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, placing at all floors and for all leads, all accessorie , Scaffolding etc as described in item description. Work complete as per the detailed drawing , mockup sample and instruction of Architect/Client.</p>	R/o	Sqm	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
300	ACP Cladding: Designing, fabricating, testing, installing and fixing in position Curtain Wall with Aluminium Composite Panel Cladding, with open grooves for linear as well as curvilinear portions of the building , for all heights and all levels etc. including: (a) Structural analysis & design and preparation of shop drawings for pressure equalisation or rain screen principle as required, proper drainage of water to make it watertight including checking of all the structural and functional design. (b) Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. (c) The fastening brackets of Aluminium alloy 6005 T5 / MS with Hot Dip Galvanised with serrations and serrated washers to arrest the wind load movement, fasteners, SS 316 Pins and anchor bolts of approved make in SS 316, Nylon separators to prevent bi-metallic contacts all complete required to perform as per specification and drawing The item includes cost of all material & labour component, the cost of all mock ups at site, cost of all samples of the individual components for testing in an approved laboratory, field tests on the assembled working curtain wall with aluminium composite panel cladding, cleaning and protection of the curtain wall with aluminium composite panel cladding till the handing over of the building for occupation. Base frame work for ACP cladding is payable under the relevant aluminium item.s The Contractor shall provide curtain wall with aluminium composite panel cladding, having all the performance characteristics all complete , as per the Architectural drawings, as per item description, as specified, as per the approved shop drawings and as directed by the Engineer-in-Charge. However, for the purpose of payment, only the actual area on the external face of the curtain wall with Aluminum Composite Panel Cladding (including width of groove) shall be measured in sqm. up to two decimal places.	R/o	Sqm	0.00	0.00
301	Providing laying and jointing in true line and level 65mm dia. U.P.V.C. Pipe (SCH- 40) for cold water including fittings make PRINCE / SUPREME / ASTRAL / FINOLEX or equivalent as approved by Engineer In Charge. Pipe shall be fixed on the wall with the help of clamp at every two metre C/C or shall be cancelled as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.	R/o	Rmt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
302	Providing laying and jointing in true line and level 80mm dia. U.P.V.C. Pipe (SCH- 40) for cold water including fittings make PRINCE / SUPREME / ASTRAL / FINOLEX or equivalent as approved by Engineer In Charge. Pipe shall be fixed on the wall with the help of clamp at every two metre C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.	R/o	Rmt	0.00	0.00
303	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [F] 50mm.	R/o	Rmt	0.00	0.00
304	Providing, laying and jointing in true line and level 110 diameter U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 110 mm diameter x 149 mm length x 145 mm heigh at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	R/o	Rmt	0.00	0.00
305	Providing, laying and jointing in true line and level 200 diameter U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 160 mm diameter x 210 mm length x 196 mm heigh at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	R/o	Rmt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
306	Providing, laying and jointing in true line and level 250 diameter U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 160 mm diameter x 210 mm length x 196 mm height at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	R/o	Rmt	0.00	0.00
307	Construction of Percolation Well with all required connections as per detailed design 3mtr dia X 4 mtr liquid depth+ invert Level) for catch basin with FRP Heavy duty manhole cover and overflow connection to the nearest drain.	R/o	Each	0.00	0.00
308	Constructing Grit/ Silt chamber in brick masonry with cement mortar 1:4, waterproof cement plastering 12mm thick for inside and outside using waterproofing compound, CC 1:4:8 bedding with 1:2 smooth finishing inside with chamfering, RCC M-20 slab in M 20 using black trap, san and cement with 150mm thick RCC slab and providing and fixing medium type FRP manhole cover and farm etc. comp.Scope shall also including required gravel, sand etc. complete the job as per details drawing. (Size 2000 x 2000 x 1200mm (liquid depth) +IL.	R/o	Each	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
309	<p>Supply Installation Testing Commissioning of Indoor Recessed round downlight 15-18W Recess Mounted round backlit downlighter with below features Pressure die cast Aluminum alloy housing for better thermal conductivity.</p> <ol style="list-style-type: none"> 1. Powder coated using Nano technology for longer durability. 2. PS diffuser for optimum light transmission. Round Version. 3. Efficacy of Fixture 95 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80 High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 5. Certifice life of fixture LED life of 50000 Hrs @ L70 . 6. IP20 Protection Luminaire performance & Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, 7. Surge : IEC 61000-4-5, EMC : EN 55015 The manufacturer should be ISO 9001 -2008 and ISO 14001 -2004 Company 8. Have their own driver Manufacturing Facility. 9. Have their own NABL accredited lab 10. Fixture color options Ebony Black , silver ,Terracota .Light Colors 5700 deg K, 4000 deg K, 3000 deg K <p>Lighting technologies DLCR 18w D/L Equalant in ENDO/TISVA</p>	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
310	<p>Supply Installation Testing Commissioning of Indoor Recessed round downlight 10-12W Recess Mounted round backlit downlighter with below features Pressure die cast Aluminum alloy housing for better thermal conductivity.</p> <ol style="list-style-type: none"> 1. Powder coated using Nano technology for longer durability. 2. PS diffuser for optimum light transmission. Round Version. 3. Efficacy of Fixture 95 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80 High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 5. Certifice life of fixture LED life of 50000 Hrs @ L70 . 6. IP20 Protection Luminaire performance & Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, 7. Surge : IEC 61000-4-5, EMC : EN 55015 The manufacturer should be ISO 9001 -2008 and ISO 14001 -2004 Company 8. Have their own driver Manufacturing Facility. 9. Have their own NABL accredited lab 10. Fixture color options Ebony Black , silver ,Terracota .Light Colors 5700 deg K, 4000 deg K, 3000 deg K <p>Lighting technologies DLCR 12w D/L Equalant in ENDO/TISVA</p>	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
311	<p>Supply Installation Testing Commissioning of Indoor Office Lighting 9-10 Recess Mounted Spotlight downlighter with below features Pressure die cast Aluminum alloy housing for better thermal conductivity. Powder coated using Nano technology for longer durability. PS diffuser for optimum light transmission. Efficacy of Fixture above 95 Lumens /watt Available with 5700K, 4000K & 3000K CCT. CRI>80 High efficiency driver with inbuilt surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD. Tilttable. LED life of 50000 Hrs @ L70. IP20 Protection Luminaire performance & Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, Surge : IEC 61000-4-5, EMC : EN 55015. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) PF >=0.95 and THD <=5 % (Certificate need to be submitted from NABL Accredited lab) The manufacturer should be ISO 9001 -2008 and ISO 14001 -2004 Company The manufacturer should have their own driver Manufacturing Facility. The manufacturer should have their own NABL accredited lab Lighting Technologies Intenso Min 9w. or Equalant in ENDO/LIGMAN</p>	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
312	<p>Supply Installation Testing Commissioning of Indoor cove mounted customized 18X18mm corner 45degree customized Extruded Aluminium alloy Housing and polycarbonate diffuser profile for continuous decorative illumination</p> <p>Anodised aluminium end caps firmly fixed on the aluminium extrusion</p> <p>Silver anodised finish for elegant look . Efficacy of Fixture ≥ 100 Lumens/Watt suitable for self adhesive Strips with driver.</p> <p>Wattage should be 12=15w/m. Should have a dotless continuous effect. Should be operated using remote driver of 24V Dc kept at suitable locations for future maintainance.</p> <p>Quantity in metres</p> <p>Lighting technologies maze 15w/m led strip set or Equalant in ENDO/LIGMAN</p>	R/o	EACH	0.00	0.00
313	<p>"Supply Installation Testing Commissioning of Indoor deep Recessed Round downlight 3w Recess Mounted Round backlit downlighter with below features</p> <ol style="list-style-type: none"> 1. Pressure die cast Aluminum alloy housing for better thermal conductivity. 2. COB Lens. 3. Efficacy of Fixture more then or equal to 85 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80 High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <10% THD 5. LED life of more then 35000 Hrs @ L70. <p>TISVA LIGHTING (USHA INTERNATIONAL LTD) recess mounted die cast Cob Spot ORRIN 3w</p> <p>Equalant in LIGHTING TECHNOLOGIES/ENDO/LIGMAN"</p>	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
314	<p>Supply Installation Testing Commissioning of IP 65 40w Linear Batten with dissused lens for better distrubution with CCT of 4000k to be mounted in niche provided. Fixture should not be more than 70mm thick.IP-65 Protection with high quality silicon gaskets. Hinging with clear glass / polycarbonate cover with housing provided for easy maintenance. (FOR EXTERNAL LIGHT)</p> <p>1.Housing made of pressure die cast aluminium with well designed heat sink for rapid heat dissipation 2. PC Injection Moulded Diffuser for high light transmitivity .Fixture Lumen Output should be greater than 100 lumen per watt. 3. Min IP 65 Ingress Protection & IK08 rating for Fixture and IP67 for Driver . 5 . The driver should be easily maintainable from the rear side 6. Fixture should be warrantied for 5yrs for 50,000 hrs @ L70 (LM79 from NABL accredited Lab to be submitted along with Letter from Manufacturer for the Life class claim of L70 @ 50,000 hrs.) 7. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) 8 . PF >=0.9 and THD <=10 % (Certificate need to be submitted from NABL Accredited lab) 9. The manufacturer should be ISO 9001 -2008 and ISO 14001 -2004 Company 10. . The Fixture should be provided with a suitable cradle for sturdy mounting. 11. Have their own driver Manufacturing Facility. 12. Have their own NABL accredited lab. Lighting Technologies make : Amiot : A04557ID00 or Equalant in ENDO/LIGMAN</p>	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
315	<p>Supply Installation Testing Commissioning of Indoor recess mounted profile light 2400mm 45W-50w 2400MM lighting fixture with below features Fixture output efficacy 4000-4500Lumens. Cut out required 60mm. Extruded Aluminium alloy Housing and polycarbonate diffuser profile for continous decorative illumination Anodised aluminium end caps firmly fixed on the aluminium extrusion Silver anodised finish for elegant look . Efficacy of Fixture >=100 Lumens/Watt suitable for self adhesive HARD PCD LED Strips with driver for Installation/ PCB Mounted solution Available only in PCB option. Should be 4 feet length High end Metallic driver for better life and performance. LED life of 50000 Hrs @ L70. IP20 Protection Luminaire performance & Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, Surge : IEC 61000-4-5, EMC : EN 55015. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) PF >=0.95 and THD <=5 % (Certificate need to be submitted from NABL Accredited lab) The manufacturer should be ISO 9001 -2008 and ISO 14001 -2004 Company The manufacturer should have their own driver Manufacturing Facility. The manufacturer should have their own NABL accredited lab Equivalent to Lighting Technologies Recess Profile or Equalant in ENDO/LIGMAN</p>	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
316	<p>Supplying, Installation, testing & erecting of High end 20W UP / Down outdoor Light with Following specifications .(3000 deg warm white) Min IP 54 to ensure fixture is water and dust tight . External separate Silicon encapsulated isolated driver for ensuring better reliability and safety. 10KV/5KVA external surge arrestor. TISVA LIGHTING (USHA INTERNATIONAL LTD) Wall mounted outdoor up & down wall light Equalant in LIGHTING TECHNOLOGIES/ENDO/LIGMAN"</p>	R/o	EACH	0.00	0.00
317	<p>Supply, Installation, Testing & Commissioning of Max. 38 W Suspended luminaire with Housing: Extruded aluminium housing fitted with metal end cap suitable for Up/Down light application. Diffuser: Easy fit opal acrylic diffuser provides smooth light distribution, LEDs: Mounted on MCPCB and connected in series parallel combination.100lm/w , PF >=0.95 and THD <=10 % , Surge protection:- 2KV, IP20. Luminaire is available with different colour temperature: White (WH) : 4000K Driver: 1 no., Constant current output driver, operating range 150–275V AC supply voltages. Mounting type: Luminaire is suspended with the help of 2 nos., of suspension system. (1.5 mtr.Length) which comes along with luminaire. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) The manufacturer should be ISO 9001 -2008 and ISO 14001 -2004 Company ,Have their own driver Manufacturing Facility, Have their own NABL accredited lab The manufacturer/ authorised Channel partner of the manufacturer has to submit for 5yr free replcement unconditionalGuarantee for complete Fixture Lighting Technologies Make:- ILEAN V3 56W UP/DOWN 50W or Equalant in ENDO/LIGMAN</p>	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
318	<p>"Supplying, Installation, testing & erecting of High end 20W Spike Light with Following specifications .</p> <ol style="list-style-type: none"> 1. Housing made of pressure die cast aluminium alloy with corrosion resistance powder coating .Should have both the option of spike as well as fixed base stand for surface mounted option. 2. Specially formulated UV Stabilised Injection molded PC diffuser for high Caliber light transmission, Minimal Glare and Maximum Output. 3. Min IP I66 to ensure fixture is water and dust tight . 4. External separate Silicon encapsulated mettalic isolated driver for ensuring better reliability and safety. 10KV/5KVA external surge arrestor. 6. Fixture should be warrantied for 5 yrs for 50,000 hrs @ L70 7. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) 8. PF >=0.95 and THD <=15 % (Certificate need to be submitted from NABL Accredited lab) 9. The manufacturer should be ISO 9001 -2008 and ISO 14001 -2004 Company 10. Have their own driver Manufacturing Facility. 11. Have their own NABL accredited lab 12. Fixture should be offered in ebony black color . Light Colors 5700 deg K, 4000 deg K, 3000 deg K , light beam angles , 10 deg , 30 deg and 40 deg. <p>Lighting Technologies CLIMBER 20W Mono Color Equivalent in Endo / Ligan</p>	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
319	<p>Supplying, Installation, testing & erecting of High end 8-10w EXTERNAL Recess/surface mounted Wall step Light with Following specifications .(3000 deg warm white)</p> <ol style="list-style-type: none"> 1. Housing made of pressure die cast aluminium alloy with corrosion resistance powder coating. 2. Specially formulated UV Stabilised Injection molded PC diffuser for high Caliber light transmission, Minimal Glare and Maximum Output. 3. Min IP I66 to ensure fixture is water and dust tight . 4. Internal separate Silicon encapsulated mettalic isolated driver for ensuring better reliability and safety. 10KV/5KVA external surge arrestor. 6. Fixture should be warrantied for 3yrs for 50,000 hrs @ L70 7. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) 8. PF >=0.95 and THD <=15 % (Certificate need to be submitted from NABL Accredited lab) 9. The manufacturer should be ISO 9001 -2008 and ISO 14001 -2004 Company 10. Have their own driver Manufacturing Facility. 11. Have their own NABL accredited lab 12. Fixture should be offered in ebony black color . Light Colors 5700 deg K, 4000 deg K, 3000 deg K , light beam angles , 10 deg , 30 deg and 40 deg. 13. Selection of colour / colour temp. / throw of light will be decided by client , consultant, architect. <p>Lighting Technologies Step 10W Warm White .The Fixture Shall wall mounted. (SO1030W3S0) Equivalent in Endo / Ligman</p>	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
320	<p>"1. Supply, Installation, testing & erecting of decorative BOLLARD LIGHT 12-15w 3000k IP65. 2. Linear Rectungalur 600/900 mm bollard . Fixture Lumen Output should be greater than 80 lumen per watt. 3. Min IP 65 Ingress Protection for Fixture and IP65 for Driver . 4. 5. Fixture should be warranted for 5yrs for 50,000 hrs @ L70 6. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) 7. PF >=0.9 and THD <=10 % (Certificate need to be submitted from NABL Accredited lab) 8. 9. . The Fixture should be provided with a suitable cradle for sturdy mounting. 10. Equivalent to TISVA MAKE LB155161 Bollard or equivalent in Lighting Technologies /Endo / Ligman"</p>	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
321	<p>Supply Installation Testing Commissioning of 15w-18w Recess Mounted IP54 Spotlight downlighter with below features Pressure die cast Aluminum alloy housing for better thermal conductivity. Powder coated using Nano technology for longer durability. PS diffuser for optimum light transmission. Efficacy of Fixture above 95 Lumens /watt Available with 5700K, 4000K & 3000K CCT. CRI>80 High efficiency driver with inbuilt surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD. Tilttable. LED life of 50000 Hrs @ L70. IP20 Protection Luminaire performance & Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, Surge : IEC 61000-4-5, EMC : EN 55015. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) PF >=0.95 and THD <=5 % (Certificate need to be submitted from NABL Accredited lab) The manufacturer should be ISO 9001 -2008 and ISO 14001 -2004 Company The manufacturer should have their own driver Manufacturing Facility. The manufacturer should have their own NABL accredited lab Lighting Technologies Intenso Min OUTDOOR 15w. or Equalant in ENDO/LIGMAN</p>	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
322	Supply Installation Testing Commissioning of decorative fabric Floor lamp light 9-15w with below features Colour : steel, satin nickel / fabric, white Dimmensions: H 1575, Ø 280, Base: Ø 230 Wattage: 9-15w Output : 900-1500Lms Fixture should be more the IP20 rated EGLO make 95164 PASTERI or equilant in Lighting technologies/ENDO/LIGMAN	R/o	EACH	0.00	0.00
323	Supplying, Installation, testing & erecting of PROFILE LIGHTING of IP20 12-15w/m Flexible LEd strip with Aluminium housing and required accessories with Following specifications for Ceiling/Furniture lighting . 1. Led strip should be IP20 rating and above . 2. Provided with proper Aluminium profile for mounting led strip. 3. Should work on DC current 12V or 24V. 4. Provided with Led driver which should be minimum IP20 rated. 5. Fixture should be warrantied for 3yrs for 50,000 hrs @ L70 Approved brand : Eglo/Tisva/Lighting technologies	R/o	EACH	0.00	0.00
324	"Supply Installation Testing Commissioning of decorative fabric pendant suspended lamp light 4-8w with below features Colour : pendant light; steel, Mokka colour, brushed brass Dimmensions: H 1100, Ø 135 Wattage: 4-8w Output : 400-800Lms Fixture should be more the IP20 rated EGLO make 98838 LOSALOMAS or equilant in Lighting technologies/ENDO/LIGMAN "	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
325	<p>Supply Installation Testing Commissioning of OUTDOOR Surface mounted COB type cylinder Light 12W-15w Surface Mounted COB Spotlight downlighter with below features Pressure die cast Aluminum alloy housing for better thermal conductivity. Powder coated using Nano technology for longer durability. PS diffuser for optimum light transmission. Efficacy of Fixture above 95 Lumens /watt Available with 5700K, 4000K & 3000K CCT. CRI>80 High efficiency driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD. Tilttable. LED life of 50000 Hrs @ L70. IP20 Protection Luminaire performance & Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, Surge : IEC 61000-4-5, EMC : EN 55015. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) PF >=0.95 and THD <=5 % (Certificate need to be submitted from NABL Accredited lab) The manufacturer should be ISO 9001 -2008 and ISO 14001 -2004 Company The manufacturer should have their own driver Manufacturing Facility. The manufacturer should have their own NABL accredited lab Equivalent to Lighting Technologies Intenso Min 11P65 5w.or Equalant in ENDO/LIGMAN"</p>	R/o	EACH	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
326	Supply Installation Testing Commissioning of decorative fabric Wall lamp light 9-15w with below features Colour : steel, satin nickel / fabric, white Dimmensions: L 150, H 380, A 195 Wattage: 9-15w Output : 900-1500Lms Fixture should be more the IP20 rated EGLO make 96477 PASTERI or equilant in Lighting technologies/ENDO/LIGMAN	R/o	EACH	0.00	0.00
327	Sliding glass door with mosquito shutter : Domal section 27 x 65 mm series Supply & Fixing Sliding glass door Comprising from Domal section series 27 x 65 with powder coated as per approved make & sample by Architect/EIC. Shutter section : 27 x 65 x 1.5 mm , Glass: 5 mm thick Toughened glass . Work including Trolley Wheel (Bearing), EPDM Gasket, Woolen In Shutter, Concealed Lock, Anti Rattling Guide, Lock Guide, handle Antilifting, Shutter Corner Clit, Shutter wing Connector, Interlock EPDM Gasket, Interlock Guide, Anti Capillary Pad, Bush Bottom silicon all side & All Necessary Hardware etc. complete as per detailed drawings, mock sample and specifications.	R/o	Sq.mt	0.00	0.00
328	Removing/chipping and cleaning of existing concrete carefully by low impact high frequency hammer without damaging the existing concrete or by control sand blasting including cleaning the surface by air jet etc. complete as per direction and satisfaction of Engineer-in-charge (for payment area of R.C.C member before chipping/ removing loose concrete will be measured).For any thickness of RCC members. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Cu.mt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
329	Applying two coats of alkaline rust converting primer of approved quality and make conforming to ASTM-B-117 (Cleaning existing reinforcement with wire/rotary wire brush, making the surfaces free from loose material, dirt etc. complete) on the rebars, including cleaning the reinforcement wire brushing to remove loose rust spalls, As per the recommendation of manufacturer complete as per direction of Engineer-in-charge. for Payment exposed length of reinforcement will be measured (Alkaline rust converting primer - REEBAKLENS RR of FOSROC / Sika Rustoff 100 of Sika / BASF/ Pidilite/ Krishna Conchem).Bars upto 12 mm Diameter. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Rmt	0.00	0.00
330	" -----Do-----as per above specification for complete work . Bars above 12mm diameter	R/o	Rmt	0.00	0.00
331	Providing and laying anticorrosive Treatment of Reinforcement by any approved make rebar corrosion protection system to existing reinforcement (The application shall be by brush). Process is to be complete as per the recommendation of manufacturer and direction of Engineer-in-charge. for payment exposed length of reinforcement will be measured. (Product - NITAZINC PRIMER of FOSROC /Fiazinc® R of Sika/ MasterEmaco P 130 of BASF or equivalent of pidilite & Krishna Conchem).Bars upto 12mm Diameter. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Rmt	0.00	0.00
332	" -----Do-----as per above specification for complete work . Bars above 12mm diameter	R/o	Rmt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
333	Providing and applying of concrete penetrating Hitech corrosion inhibitor system of approved make that works on the Bipolar inhibition Mechanism (B.I.M.).B.I.M. inhibits corrosion of steel in concrete at the poles, catholic and anodic simultaneously on concretesurface. The process should be complete as per direction of Engineer-in-charge for payment area of concrete surface after chipping will be measured (Product - FOSROC/ Sika® FerroGard-903/ BASF/ Pidilite/ Krishna Conchem). Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Sq.mt	0.00	0.00
334	Making 'V' groove of 5 mm wide and 5mm deep over crack line by electrically operated angle grinder with diamond concrete saw blade and cleaning it by air blower as directed by Engineer-in-charge Sealing of exposed 'V' groove of 5mm deep and 5mm wide with solvent-free, moisture tolerant, thixotropic, two part structural adhesive and epoxy repair mortar cum surface levelling mortar the compressive strength of the epoxy repair mortar shall be ≥ 60 N/mm ² (14 Days) and Bond strength ≥ 10 N/mm ² (7 Days). (Product -NITOMORTAR S OF FOSROC/ Sikadur®- 31 of Sika/ MasterBrace 2200 BASF or equivalent of Pidilite or Krishna Conchem). Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Rmt	0.00	0.00
335	Drilling and fixing NRV nozzles in RC members, including (fixing material : Renderoc Plug of Fosroc / Sikadur-31 of Sika/ MasterBrace 2200 of BASF or equivalent of Pidilite & Krishna Conchem). Drilling Holes: Drilling 12mm dia, 50 to 75 mm deep holes in structural members of the intervals of 350 mm in staggered manner or as directed by the consultants in RC structural elements. Cleaning of holes: Clean the holes by air blower prior to fixing nozzles. Cuttting of Nozzles: Cut the nozzles by chisel after completion of grouting without damaging structural elements: all type of structure Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading,	R/o	Each	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
Total Amount					0.00
H	Part-8 (Rate Only Item)				
336	Supply and apply a polymer modified cementitious board coat. Ratio polymer : water : cement (1 Polymer: 4 Water: 6 Cement) by weight. Apply the patching mortar when the bond coat is tacky (Nito Bond SBR Latex of Fosroc/ Sika® latex of Sika/ MasterEmaco SBR2 of BASF or equivalent of Pidilite or Krishna Conchem) Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Sq.mt	0.00	0.00
337	Injecting/Grouting shrinkage free low viscosity epoxy resin grout in structural cracks, wherever required by pressure and using mechanized injector gun with accessories till nozzles refused to accept the grout. Epoxy grout material should be conforming to ASTM-881-87 type I, grade I, class B & C and compressive strength of the material shall be ≥ 55 Mpa, (7 Days), Tensile strength ≥ 20 Mpa (14 Days) & Bond strength 10 Mpa (14 Days). (Low Viscous epoxy grout : conbextra EP10 of Fosroc/ Sikadur®-52 of Sika/ MasterInject 1315 of BASF or equivalent of Pidilite & Krishna Conchem).Mixing of material : Mixing material components in required quantities as per manufacture's instruction. Grouting : Fill the grouting gun with low viscosity epoxy resin. Maintain desired pressure in the gun by air compressor: maintain the required pressure at exit. Grout the material through prefixed nozzles in structural elements till its refusal, seal the nozzles with epoxy putty after the refusal, monitor leakages through other nozzles while grouting and seal them as per the requirement, repeat the process for all the nozzles. complete the operation within pot life of the material.Cleaning the gun and accessories: Clean the gun and accessories (valves, pipes and other fixture) with thinner after the operation to avoid jamming of the gun.	R/o	Kg	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
338	Providing , mixing & applying two comonment Epoxy resin concrete Bonding coat on prepared RCC surface as per manufacture specification including preparation o) surface by chipping and throughly cleaning of surface complete wherever required and as per direction of Engineer-in-charge.Epoxy material should be conforming to A S T M-881-887 Type 1,Grade 1,class B or C (Prouduct: MasterBrace1414 of BASF/ Sikadur 32LP OF SIKA/Nitobond EP Of fosroc or equivalent of pidilite). Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Sq.mt	0.00	0.00
339	Providing and laying ready to use non shrink. Cementious free flow micro concrete of Compressive strength \geq 50 MPa (28 days) according to ASTM C 109 of approved make and manufacture complete as per direction of Engineer-in-charge for replacing the carbonated part of concrete and repairing the damaged surface of concrete after fix the form work across the profile of damaged structural element. Pour the free flow non shrink. Cementious free flow micro concrete mix in the form work. .(Product :- Renderock RG of Fosroc/ SikaRep [®] Microcrete -4 of Sika / MasterEmaco S-346 of BASF or equivalent of Pidilite)Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Ton	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
340	Rebaring/ fixing of shear connectors of new reinforcement bars for structural connections in RCC columns including power drilling holes of appropriate diameter in reinforced or plain cement concrete upto standard depth or as per specification of manufacturer, fixing the reinforcement in position using epoxy of approved make at all height level. (Rate shall include cost of labour, T & P for power drilling in concrete, epoxy cartridges, plastic nozzle etc. complete including the drilling holes and loose dust by blowing air. Reinforcement for rebar shall be paid extra.)(Product :- Lockfix of Fosroc/ AnchorFix [®] -3+ of Sika/ RE-500 of Hilti/ MasterFlow 935 AN of BASF/Fischer)a) Rebar 10 mm Dia x 14 mm holes x 100mm depth Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Nos	0.00	0.00
341	b) Rebar 12 mm Dia x 16 mm holes dia x 120 mm depth	R/o	Nos	0.00	0.00
342	c) Rebar 16 mm Dia x 20 mm holes dia x 160 mm depth	R/o	Nos	0.00	0.00
I	Part-9 -Colour work Colony quarters				



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
343	Providing and applying two coats of water proof cement paint of approved brand manufactured as per latest IS, of Snowcem , Indocem , Decocem , Colourcem , Spremcem etc. or equivalent as approved by EIC , approved tint on all Old snowcem surface with good quality brush to give an even shade including cleaning the surface to remove all dust, dirt mortar drops and other foreign matter and oil spots , other loose surfaces including curing the rendered surfaces with necessary scaffolding/Zulla etc. completed with required man power, materials, tools , tackles , machinaries etc. complete as directed and specified at all levels. NOTE: (1)Measurement will be considered for Plan area without increasing the quantity to get the equivalent plain area for the grained/sand faced surface .	27655	Smt	0.00	0.00
344	Providing and applying Two coats of Oil bound washable Distemper , of standard quality manufactured as per latest IS and approved of brand like Asian, Nerolac , burger or equivalent manufacturing brand and of required shade on previously distempered surfaces to given an even shade etc. , after throughly brushing ,washing,scraping clean of all dust dirt and other foreign matter , including preparing the surface even , smooth with sand paper and necessary scaffolding/Zulla etc complete at all level and as directed by Engineer in charge. Note:(1.) Bidders are requested to visit the site condition before quoting the rate . (2) Rates are for all height of building and at all level and including applying Lapi / Primer to match with the surface smooth and finish level , as and where required with required man power , tools , tackles, machinaries etc . (3) Scope of work include the all cleaning work which includes removing of colour stains on floors of each structures / staircase area / passages area / compound wall area after completion of colour works as directed by EIC.	35022	Smt	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
345	Providing and applying two coats (excluding priming coat) on previously painted wooden and wood based surface with enamel paint to give an even shade of approved IS make and shed, any from Asian, Burger, ICI, Nerolac, Shalimar as per approved and instruction of engineer in charge after cleaning the surface to remove all dust, dirt and other foreign matter and including necessary scaffolding, etc. complete with required materials, man powers, tools, tackles, machinaries etc. complete as directed and specified at all levels. NOTE: (1) Rates are for all height of building and at all level and including Providing and applying of Lapi/Primer to match the surface smooth and finish level, as and where required. (2) Scope of work include the all cleaning work which includes removing of colour stains on floors of each quarters/ staircase area / passages area / compound wall area after completion of colour works as directed by EIC.	6197	Smt	0.00	0.00
346	Do as above but on Metal surface	1533	Smt	0.00	0.00
347	Cutting out crack in masonry plaster slab, floor and any RCC including opening the cracks, making V shape with cement and sand slurry 1:3, cleaning, scaffolding and finishing the surface good, with required materials, tools, tackles, machinaries etc. complete as directed by EIC.	1190	Rmt	0.00	0.00
Total Amount					0.00
J	Part-10 (less Buy back amount)				
348	Part-II: Buyback items:- Note: 1) The client reserves the right for hand over of any buy back items to bidder without assigning any reason thereof. The client reserves the right for any decision. 2) The Qty may vary for any buy back item as per actual site conditions. Single Bed-Wooden Finish Bed Size-@900 x 1950 mm	44.00	Nos	0.00	0.00
349	Dressing table with mirror-Laminate Finish · Size-@900 x 450 mm Height-450 mm	22.00	Nos	0.00	0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
350	Study table-Wooden finish : Size-@1200 x 600 mm,Height-750 mm	22.00	Nos	0.00	0.00
351	Center table-Wooden finish : Size@900 x 600 x 450 mm	22.00	Nos	0.00	0.00
352	Fabric Chair	44.00	Nos	0.00	0.00
353	Wardrobe : Laminate finish shutter	22.00	Nos	0.00	0.00
354	Pantry counter storage shutter	22.00	Nos	0.00	0.00
355	Wordrobe shutter at dressing area	22.00	Nos	0.00	0.00
356	All toilet block sanitary fittings like wash basin w.c. pan, Indian and Europeon type flushing tank , Urinal , all type of cock , accessories , basin counter etc.	19.00	Per Toilet	0.00	0.00
357	Existing All type of Door , window with frame all hardware's	188.00	Nos	0.00	0.00
358	Existing Electrical light fixtures , cables , trays etc	1.00	Job	0.00	0.00
359	Existing Fabrication and steel structure as per site conditions	1106.00	Kg	0.00	0.00
Total Amount					0.00

Sr. no.	Summary Sheet				Amount
A	Sub Total : Part - 1				0.00
B	Sub Total : Part - 2				0.00
C	Sub Total : Part - 3				0.00
D	Sub Total : Part - 4				0.00
E	Sub Total : Part - 5				0.00
F	Sub Total : Part - 6				0.00
G	Sub Total : Part - 7 (Rate Only Item)				0.00
H	Sub Total : Part - 8 (Rate Only Item)				0.00
I	Sub Total : Part - 9 (Colony quarters colour works)				
Total Amount (Rs.)					0.00
J	Sub Total : Part - 10 (less Buy back amount)				0.00
Grand Total Amount (Rs.)					0.00



Addition, Alteration, Renovation, Interior furnishing with necessary services work for Existing Staff & Training Hostel and colour work to existing colony quarters and other buildings at GMDC Colony, Tarsamiya, Bharatnagar, Bhavnagar, Gujarat

Price Bid

Sr. No.	Item Description	QTY	Unit	Rate	Amount
---------	------------------	-----	------	------	--------

GST Extra as per Govt. Norms