



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
A	Part-1				
1	Demolition of brick work & stone masonry with any type of plaster, paint, skirting, dedo etc. including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (III) In cement mortar.	87.00	Cu.mt	0.00	0.00
2	Demolition of any type of R.C.C work with TMT bars, any type of plaster, paint, skirting, dedo etc. including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (I) R.C.C work.	37.00	Cu.mt	0.00	0.00
3	Dismantling all type of tiles flooring, or stone flooring laid in mortar, any type of flooring with mortar, waterproofing, including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	845.00	Sq.mt	0.00	0.00
4	Dismantling all type of wall tiles, dedo and any type of (stone/ tiles) clading laid in mortar, any type of flooring with mortar, waterproofing, including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	67.00	Sq.mt	0.00	0.00
5	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	741.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
6	Dismantling any type of doors, windows, ventilators etc. (wood of steel) shutters with chowkhats, architraves, holdfasts, any type of frame and other attachments etc complete and stacking them within all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (i) Not exceeding 3 Sq.M in area	31.00	Each	0.00	0.00
7	Dismantling any type of doors, windows, ventilators etc. (wood of steel) shutters with chowkhats, architraves, holdfasts, any type of frame and other attachments etc. work complete and stacking them within all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (II) Exceeding 3 Sq.M in area	10.00	Each	0.00	0.00
8	Dismantling fixed glazing including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge. work complete and stacking them within all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (II) Exceeding 3 Sq.M in area	38.00	Sq.mt	0.00	0.00
9	Removing dry or oil bound distemper, all type of paint and texture paint by a washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete. work complete and stacking them within all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	2516.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
10	Remove of existing Fabrication and steel structure including plates, rolled steel joists, channels, angles and all type of accessories etc. including stacking of the materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. work completed as per existing site conditions work complete as per the instruction of EIC.	1483.00	Kg	0.00	0.00
11	Removal of existing Male toilet block sanitary fittings like wash basin w.c. pan, Indian and European type flushing tank, Urinal, all type of cock, accessories, basin counter etc. including stacking of the materials with all lead and lift. As per existing site conditions work complete as per the instruction of EIC. (Male Toilet)	1.00	Per toilet	0.00	0.00
12	Removal of existing Female toilet block sanitary fittings like wash basin w.c. pan, Indian and European type flushing tank, all type of cock, accessories, basin counter etc. including stacking of the materials with all lead and lift. As per existing site conditions work complete as per the instruction of EIC. (Female Toilet)	1.00	Per toilet	0.00	0.00
13	Removal of existing Existing attached toilet block sanitary fittings like wash basin w.c. pan, Indian and European type flushing tank, all type of cock, accessories, basin counter etc. including stacking of the materials with all lead and lift. As per existing site conditions work complete as per the instruction of EIC. (attach Toilet)	2.00	Per toilet	0.00	0.00
14	RCC Core cut : Drilling with core cutting machine in RCC beams, slabs, floors etc., for laying pipes and rendering the same in RCC 1:2:4 finishing the same to the satisfaction of the Architect/EIC.etc., complete, at all levels. The rate shall also include for providing EPOXY based water proofing compound for sealing the joints around the pipes upto any depth at all heights & levels. Work complete including all type of tools, tackles, scaffolding, safety measures etc complete as per instruction of Architect/EIC. a) 100 mm dia	10.00	Nos	0.00	0.00
15	RCC Core Cut : b) 150mm dia.	5.00	Nos	0.00	0.00
16	RCC Core Cut : b) 200mm dia.	5.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
17	Providing & laying any thick Brick Masonry work using common burnt clay building bricks having crushing strength not less than 35 Kg/Sq. Cm. at all levels in cement mortar 1:6 (1 cement :6 fine sand) - including proper filling of all masonry joints, curing etc. complete. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC. (II) Conventional brick work	24.00	Cu.mt	0.00	0.00
18	Providing and laying Half brick masonry in common burnt clay building bricks having crushing strength not less than 35 Kg./Sq. Cm. in cement mortar 1:4 (1 cement : 4 coarse sand) in superstructure - at all floor levels including proper filling of all masonry joints, curing etc. complete. Work complete including all type of tools, tackles, scaffolding etc complete as per instruction of Architect/EIC. The rate includes providing and placing in position 2 Nos 6 mm dia bars at every third course of masonry work.	87.00	Sq.mt	0.00	0.00
19	15 mm thick cement plaster : Providing and laying average 15 mm. thick single coat smooth finishing using steel float (mala finish) plaster in CM 1:4 (1 cement : 4 coarse river sand), on brickwork, RCC work, blocks, sills, soffits, jambs etc. at all floors, all levels, all heights, all shapes and for all sizes with necessary scaffolding, curing, chicken mesh at the junction of masonry & RCC work using screw / dhoba nails, making moulded, grooves, drip moulds, tapak, chemical bonding agent etc., for all lead, lift, height and levels etc., complete as per specification and as directed by the EIC. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC.	529.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
20	20 mm thick Sand Faced Plaster: Providing and applying 20mm thick sand faced plaster (Using Wooden Gutka/Float) to all external surfaces at all levels and in any shape, in two coats, 12 mm thick average base coat in cement mortar 1:5 and 8mm thick finish coat in cement mortar 1:2 using fine sand for finish coat, including preparation of surface to uniform texture, staging, double scaffolding, curing, chicken mesh at the junction of masonry & RCC work using screw / dhoba nails, making moulded, grooves, drip moulds, tapak etc., complete as per specification and as directed by the EIC. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC.	63.00	Sq.mt	0.00	0.00
21	Providing 20 mm thick double coat mala cement plaster on interior brick / concrete work for plastering comprising of base coat of 12 mm thick cement plaster in cement mortar (1 Cement : 4 coarse sand) in rough finishing and 8mm thick top coat of cement mortar 1:2 (1 Cement : 2 Coarse sand) finished with trowel including scaffolding, safety measures, curing etc. complete.	2.00	Sq.mt	0.00	0.00
22	Providing and laying cement concrete 1:4:8 (1- Cement : 4- coarse sand : 8- hand broken stone aggregates 40 mm nominal size) and curing complete. including mixing laying, vibrating, consolidating, leveling and curing etc. complete with all labours and materials with formwork. The item includes finishing the top surface with trowel. Work complete including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	3.00	Cu.mt	0.00	0.00
23	Filling in plinth with sand under floors including watering ramming, consolidating and dressing complete. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	73.00	Cu.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
24	Providing and laying ordinary cement concrete 1:2:4 (1-Cement 2-coarse sand: 4-graded stone aggregates 20 mm nominal size) for R.C.C lintel including finishing smooth with, curing, safety measures etc. complete including the cost of form work but excluding the cost of reinforcement. including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	2.00	Cu.mt	0.00	0.00
25	Providing and laying controlled cement concrete M.250 and curing complete including finishing smooth with, curing, safety measures etc. complete including the cost of form work but excluding the cost of reinforcement. including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. in (C) Slabs, landing, shelves, Balconies, Lintels, Beams, Girders and Cantilever etc.	2.00	Cu.mt	0.00	0.00
26	TMT Bars: Providing, straightening, cutting, bending, binding and laying in position of TMT FE 500/500D grade steel reinforcement confirming to IS 1786 : 1990 or latest code, to correct all shape and size as per detailed drawings, specifications for all RCC work etc, at all levels and all heights with necessary chairs and laps; with correct size PVC cover blocks or approved quality concrete cover blocks of same grade of concrete and binding wire of 18 gauge etc. complete with test certificate of the steel bars from manufactures as well as approved laboratory test certificates directed by Engineer in charge, etc. complete. Rate shall be inclusive of binding wire, cover, lap, chair etc. Work shall complete up to any levels, all floor & as per the instruction of EIC.	360.00	Kg	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
27	<p>Carring out plinth treatment to post construction / existing structure by spraying chemical solution for termite control treatment including labour and material consistment with I.S.I specification. Using Chlordene and Chiorpurfiles 20 EC. As Per 6131_paret-II Consentration Weight one percent is recommended i.e one litre 20 EC chemical emulsion with 19 liter give 1 % concentration inclusive of one litre chemical emulsion appication at the rate of 5 Litre chemical / Sqm of surface is recommended as per I.S.</p> <p>The whole work is to be executed through specialized agency with a guarantee of 5 (Five) years given on a prescribed proforma duly stamped. The waterproofing work 10% will be retained from the billing amount for 5 years (without interest). The amount shall be refunded after Five years without interest. work complete including all type of tools, tackles, scaffolding, safety measures etc complete at any level and height. work complete as per the instuction of EIC/Client/Architect.</p>	613.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
28	<p>Toilet Waterproofing : Providing and Applying of waterproofing treatment in toilet block as per below specification. Surface Preparation: All loose and de-bonded concrete/ screed shall be removed and proper repairing to be carried with polymer modified mortar. Appropriate surface grinders and equipment's must be used to remove the undulations, sharp edge of the screed, broken china chips mosaic tile etc. Washing the roof - terrace surface and making it dust free. Surface must be clean, dry and in sound condition to ensure adequate adhesion. Ensure Undulations /depression in roof surface where water may stagnate shall be leveled and repair with the application of one coat of Dr. Fixit Pidicrete URP in the ratio of 1:1 (URP: Cement) by volume and apply with brush. Waterproof Coating: Apply 1st coat of Dr. Fixit HydroShield PUD plus without dilution spreading at the rate of 0.70/litre/Sq.mt/Coat until all surface is covered. Lay a 45 GSM Fiber glass mesh as a reinforcing material which is incorporated in the coating when the first coat is still in wet condition. Allow the first coat to dry for approximately 4-6 hours before applying the 2nd coat at 90° to the first coat. Ensure there are no pinholes or air bubbles on the membrane surface.</p> <p>Apply second coat of Dr. Fixit HydroShield PUD Plus without dilution spreading at the rate of 0.70/litre/Sq.mt/Coat to achieve total dry film thickness of 850 to 1000 microns at forced coverage at the rate of 1.40/ litre/ Sq.mt in 2 heavy coats. The products have following technical parameters: compressive strength of ≥ 4.00 N/ mm2 with 45 GSM glass fiber mesh confirming to ASTM D 412; Elongation at break ≥ 300% and crack bridging ability up to 3 mm, UV resistance , Green certified from GRIHA, meeting Standard as per ASTM D6083 - 97a, Solar reflective index of 105 , crack bridging upto 3mm , Low VOC contain, excellent adhesion property of 1.5 N/mm2 as per ASTM D 3359, excellent water resistance, alkali resistance and Efflorescence resistance. The whole work is to be executed through specialized agency with a guarantee of 5 (Five) years given on a prescribed proforma duly stamped. The waterproofing work 10% will be retained from the billing amount for 5 years (without interest). The amount shall be refunded after Five years without interest. work complete including all type of tools , tackles, scaffolding, safety measures etc complete at any level and height. work complete as per the instuction of EIC/Client/Architect.</p>	36.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
29	Rising Dampness and Negative side waterproofing for internal walls: For rising dampness and encapsulation treatment of dampness on internal walls treatment to be done with Diasen -Watstop, a 3 component product having resistance to water ingress of 9.5 ATM for both Negative side and positive and should have excellent resistance to Salt. Diasen - Watstop to be applied in 2 coats at consumption rate of 1 kg/m ² . The application can be done by Brush or roller to give smooth and even finish good enough for putty/paint application. Work complete including all type of tools, tackles, scaffolding etc complete at any level and height. work complete as per the instuction of EIC/Client/Architect.	18.00	Sq.mt	0.00	0.00
30	Toilet Flooring : Providing and laying Lapato/Matt/Glossy/ Non Skid/Rustic finish /Sugar finish Vitrified tiles flooring using minimum 10 mm thick tiles of as per approved make list by architect/client, tile size (600 mm X 600 mm) including preparing base for leveling with 20mm thick cement mortar 1:6 (1 cement : 6 coarse sand) and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing/ instruction and approval by architect. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of tile is Rs. 40/Sqft	36.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
31	Toilet Dado Work : Providing and laying Lapato/ Matt /Glossy/ Non skid/Rustic finish/sugar finish Vitrified tiles in dado using minimum 10 mm thick tiles as per approved make list by architect /client (tile size 600 mm X1200mm) fixed in dado on 10 mm th. Cement plaster 1:3 (1 cement: 3 coarse sand) All surfaces must be dimensionally stable according to IS 1443-1972, level, cured, undamaged, compact, rigid, resistant, dry and free from any debonding agents tiles fixed by approved tile adhesive and all application shall be done under instruction of manufacturer guideline and specification, and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction all complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. Basic rate of tile is Rs. 45/Sq.ft	158.00	Sq.mt	0.00	0.00
32	Vitrified Flooring: Providing and laying Lapato/ Glossy/ Matt/ Rustic/ Sugar/ Satin finish Vitrified tiles flooring using minimum 10 mm thick tiles as per approved make list or selected by Architect, tile size 600 x 1200 mm including preparing base for leveling with 20mm thick cement mortar 1:6 (1 cement : 6 coarse sand) and jointed with 3mm thick epoxy grouting of approved shade and colour in proper line and level as per detailed drawing/ instruction and approval by architect. The rate shall be inclusive of protecting the flooring by plaster of Paris and plastic and/or bubble top sheets. Basic rate of tile is Rs. 55/Sqft.	2.00	Sq.mt	0.00	0.00
33	Vitrified Flooring : Matt finish tile size 800 x 1600 mm " -----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 70/Sqft.	22.00	Sq.mt	0.00	0.00
34	Vitrified Flooring : tile size 1200 x 1800 mm: Matt finish Intra Gray " -----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 90/Sqft.	535.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
35	Vitrified Flooring : Matt finish tile size 600 x 600 mm "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 40/Sqft.	33.00	Sq.mt	0.00	0.00
36	Vitrified Flooring : Designer Mosaic tile size 200 x 200 mm "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 225/Sqft.	77.00	Sq.mt	0.00	0.00
37	Vitrified Skirting work : Providing and laying Lapato /Glossy finish vitrified tiles in skirting using minimum 10 mm thick vitrified tiles of approved make list or as selected by Architect of premium quality fixed in skirting on 10 mm thick Cement plaster 1:3 (1 cement : 3 coarse sand) and jointed with 6 mm thick-min. 75 mm height laticrete grouting of approved shade and colour in proper line and level for average 125 mm height as per detailed drawing/ instruction and approval by architect. Basic Rate of tile is Rs.55/Sqft.	2.00	Sq.mt	0.00	0.00
38	Vitrified Skirting work : "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 70/Sqft.	4.00	Sq.mt	0.00	0.00
39	Vitrified Skirting work : "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 40/Sqft.	2.00	Sq.mt	0.00	0.00
40	Vitrified Skirting work : "-----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 90/Sqft.	13.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
41	<p>Dry cladding : 2400 x 1200 mm : BULL BERRY GREY : Lift lobby Providing and laying Lapato/Glossy finish minimum 10 mm thick vitrified tiles in cladding of approved make list or as selected by Architect of premium quality fixed in cladding on 12mm thick cement sheet with approved adhesive. Cement sheet fixed on Aluminum framework of 25x40 mm section fixed on wall with clamps, pins & required fittings. All joint sealed with approved sealant approved shade and colour in proper line as per detailed drawing/ instruction and approval by architect. work complete including all type of fittings, fixtures etc shall be per approved make by Architect, bending, bidding, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client. Basic rate of tile is Rs. 125/Sqft.</p>	104.00	Sq.mt	0.00	0.00
42	<p>Corner Guard: Providing and fixing 1.2mm thick & 14mm high Stainless Steel profile corner guard (304 grade) with powder coated of approved make list or as selected by Architect. All joint sealed with approved sealant approved shade and colour in proper line as per detailed drawing/ instruction and approval by architect. work complete including all type of fittings, fixtures etc shall be per approved make by Architect, bending, bidding, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client.</p>	36.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
43	<p>Granite Stone Flooring : Providing & laying approved quality 18 mm thick Granite stone flooring of approved shade, in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of Granite stone is Rs. 150/ Sqft.</p>	122.00	Sq.mt	0.00	0.00
44	<p>Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias, risers of steps, dedo and pillars and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish, grooving etc. complete at all levels. work complete Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Basic rate of Granite 150/ Sq.ft</p>	56.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
45	Artificial Stone Flooring : Providing & laying approved quality 15 mm thick Artificial stone flooring , steps of approved shade, in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of Artificial stone is Rs. 150/ Sqft.	12.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
46	Artificial Stone door frame (up to 250 mm width): Providing & laying approved quality 15 mm thick Artificial stone work of approved shade (selected and sorted for its uniform colour and thickness), in door frame etc. in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. including 4 mm deep groove, at all floors, all levels, all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue .Basic rate of Artificial stone is Rs. 150/ Sqft.	81.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
47	<p>Artificial Stone window sill (up to 250 mm width) : Providing & laying approved quality 15 mm thick Artificial stone work of approved shade (selected and sorted for its uniform colour and thickness), in window sill etc. in required sizes and shapes, set with cement slurry (minimum 4.4 kg cement/sqm) including 35mm to 70 mm thick (Average thickness 50 mm) cement mortar bedding (thickness of mortar bedding to be decided as per requirement and as directed by EIC or his representative) in 1:6 laid and jointed with white cement and matching pigment including rubbing, re-polishing after fixing to remove any undulation between the joints (if required) with different grades of Emery, refilling of open joints, curing, daily cleaning and mopping, shall be done up to the satisfaction of the EIC (Only finished work will be measured.) etc. all complete as per approved sample by Architect, drawings and instruction of EIC. including 4 mm deep groove, at all floors, all levels, all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of Artificial stone is Rs. 150/ Sqft.</p>	46.00	Rmt	0.00	0.00
48	<p>Granite stone/ Artificial stone Pantry Platform: Providing & fixing two layers of Pantry Platform, first layer using 25mm thick Kotastone of approved shade and second layer using approved shade and sample of 15 mm thick Granite stone, joined together with 1:4 Cement mortar bedding / approved tile adhesive, to true plane & level or to slopes, or close jointed with cement slurry with pigment of matching shade and colour and finishing with the same, including dedo 1'6", cutting stone as per required shape & size to fit sink & 3" to 9" fascia with moulding, nosing, chamfered front edges, fixing, disposal of debris etc. finished as per design in detail drawing and instruction of Architect/EIC. sample mock shall be approved from Architect/EIC. Basic rate of stone is Rs.150/ Sqft.</p>	7.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
49	Artificial stone top Wash basin counter for toilet: Providing & fixing two layers of wash basin counter, first layer using 25mm thick Kotastone of approved shade and second layer using approved shade and sample of 15 mm thick Artificail stone, joined together with 1:4 Cement mortar beding / approved tile adhesive, to true plane & level or to slopes,or close jointed with cement slurry with pigment of matching shade and colour and finishing with the same, including dedo 1'6", cutting stone as per required shape & size to fit Wash basin & 3" to 9" facia with moulding, nosing, chamfered front edges, fixing, disposal of debris etc. finished as per design in detail drawing and instruction of Architec/EIC. sample mock shall be approved from Architect/EIC.Basic rate of Artificial stone is Rs.150/ Sqft.	7.00	Rmt	0.00	0.00
50	Double Leaf Flush Door finish with veneer & Glass view panel: Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make, finished with both side 4 mm thick veneer with matt finish monocoat polish as approved, wooden frame with matt finish monocoat polish with chamfering, 8 mm toughened Glass view panel size 2050 x 750 mm, Hardware fittings like concealed door closer or floor spring, Door handle, lock, Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures, bending, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client. Basic Rate of teak veneer - 120/Sqft.	3.00	Sq.mt	0.00	0.00
Total Amount					0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
B	Part-2				
51	Single Leaf Flush Door finish with veneer: Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make, finished with both side 4 mm thick veneer with matt finish monocoat polish as approved, wooden frame with matt finish monocoat polish, Hardware fittings like door closer, Door handle, lock, Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/Client. Basic Rate of teak veneer - 120/Sqft.	3.00	Sq.mt	0.00	0.00
52	Single Leaf Flush Door finish with one side veneer & one side laminate: Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make, finished with one side 4 mm thick veneer with matt finish monocoat polish and one side 1 mm thick Laminate as approved, wooden frame with polish, Hardware fittings like door closer, Door handle, lock , Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings , fixtures, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/Client. Basic Rate of veneer - 120/Sqft. & Equivalent to VNR series laminate.	14.00	Sq.mt	0.00	0.00
53	WPC shutter with laminate finish (Duct area): Providing and fixing in position 12 mm thick WPC shutter of approved make with laminate finish as approved, shutter fixed with floor and above pivot of approved make, pivot cover plate, safety measures, lock & handle etc fixtures of approved make list with all necessary fittings etc. aluminium frame 25x30 Complete as per detailed drawings and specifications.	15.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
54	<p>Acoustic Door: Providing & fixing Single Leaf Flush Door 50 mm thick with both side veneer finish with Polish; Door frame shall be from Ply with -Veneer with matt finish monocoat polish, infill 25mm thick rockwool (48 kg/cumt density) with necessary vinyl gripper, necessary fittings. Hardware fittings like concealed door closer Door handle, lock, Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures etc shall be per approved make by Architect, bending, bidding, safety measures as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client. Basic Rate for material only teak veneer - 120 /Sq.ft.</p>	14.00	Sq.mt	0.00	0.00
55	<p>Sliding window: Domal section : 27x65 mm series Supply & Fixing of Aluminium sliding window with powder coated as per by approved make & sample by architect/EIC. Frame section: 40 x 89 x 1.5 mm Shutter section : 27x 65 x 1.5 mm Mosquito shutter : 27 x 65 x 1.5 mm Glass : 6mm Thick SGU Toughened Glass of Saint Gobain ET125 6mm FT Neutral shade approved make list . including EPDM Gasket, Woolen In Shutter, Multiple Lock, Anti Rattling Guide, Lock Guide, handle Antilifting, Shutter Corner Clit, Shutter wing Connector, Interlock EPDM Gasket, Interlock Guide, Anti Capillary Pad, Bush Bottom silicon all side & All Necessary Hardware etc. complete as per detailed drawings, mock sample and specifications.</p>	2.00	Sqm	0.00	0.00
56	<p>Toilet ventilator : Providing and fixing standard extruded of alluminium section of size 63 mm x 38.10 mm x 1.2 mm (jindal section : 2434 @ wt. 0.643 kg per mt with colour powder coated alluminium frame for ventilation with 5 mm thick frosted / milky glass with provision of exhust fan etc complete as per drawing .</p>	2.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
57	Applying two coats of Birla (white cement based) or Asian (acrylic lapy- putty) or equivalent & two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth.	2206.00	Sq.mt	0.00	0.00
58	Interior paint : Providing & laying of 3 (three) coats with Royale luxury Emulsion paint of Asian Paint or equivalent approved brand in shades and colour as directed on wall surfaces to give an even shade incl. scaffolding to at any height with all labour and material after thoroughly brushing the surface & making free from mortar droplings and other foreign matter including surface preparation etc.complete. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift, safety measures, performance waranty certificate etc. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. The substrate must be sound, clean, dry, free from dust, oil, grease and laitance etc. All traces of release agents must be removed. On chalky and dusty surfaces, all loose material must be removed by stiff bristle brushing. The primer/ paint application is to be done with the rollers. rate shall be including crack filling and levelling as per manufacturers specification.	2310.00	Sq.mt	0.00	0.00
59	Wall Punning : Providing and applying 12 mm thick (average) premixed formulated one coat gypsum lightweight plaster having additives and light weight aggregates as vermiculite/ perlite respectively conforming to IS: 2547 (Part - 1 & II) 1976, applied on hacked / uneven background such as bare brick/ block/ RCC work on walls & ceiling at all floors and locations, finished in smooth line and level etc. complete.	507.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
60	EWC : Providing and fixing wash down water closet (European type W.C. pan with Jet) as per approved make of selection & shade with seat cover, P OR S Trap M.S. or G.I bracket, CP brass hinges and rubber buffers and Jointing the trap with soil pipe in cement mortar : 1:1 (1 cement : 1 fine sand), including cutting and making good the walls and floors where required with all labour and materials. All works to be carried out as per instructions and direction of Engineer-in-charge. Model Equivalent to Q617240110	4.00	Nos	0.00	0.00
61	EWC : Providing and fixing Automode electronic closet as per approved make of selection & shade with seat cover, P OR S Trap M.S. or G.I bracket, CP brass hinges and rubber buffers and Jointing the trap with soil pipe in cement mortar : 1:1 (1 cement : 1 fine sand), including cutting and making good the walls and floors where required with all labour and materials. All works to be carried out as per instructions and direction of Engineer-in-charge. Model Equivalent to Q777240110	1.00	Nos	0.00	0.00
62	Providing and fixing Consealed cistern tank with frame work & Flushing plate of as per approved make by architect. Model Equivalent to Q507450100 + Q507455420	4.00	Nos	0.00	0.00
63	Providing and fixing Consealed cistern tank with frame work & Flushing plate of as per approved make by architect. Model Equivalent to Q507450100 + Q507455420	1.00	Nos	0.00	0.00
64	Providing and fixing 12mm dia. Health faucet with 8 mm dia of as per approved make selected by Architect with flexible pipe of 1.mt. length and holding stands complete. Model Equivalent to Q503192520	5.00	Nos	0.00	0.00
65	Providing and fixing Counter top Wash Basin of as per approved make of selection including fittings and waste pipe etc. and fixing on wash basin counter by tile adhesive of approved make. Model Equivalent to Q367140210	4.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
66	Providing and fixing Counter top Wash Basin of as per approved make of selection including fittings and waste pipe etc. and fixing on wash basin counter by tile adhesive of approved make. Model Equivalent to Q357140510	1.00	Nos	0.00	0.00
67	Providing and fixing 15mm dia single lever Basin spout of as per approved make of selection. Model Equivalent to Q363114120	4.00	Nos	0.00	0.00
68	Providing and fixing 15mm dia single lever Basin spout (Gold finish) of as per approved make of selection. Model Equivalent to Q723111221	1.00	Nos	0.00	0.00
69	Providing and fixing 15mm dia two way Bib cock of as per approved make of selection. Model Equivalent to FLR-CHR-5041N	5.00	Nos	0.00	0.00
70	Providing and fixing chromium plated Bottle Trap of as per approved make of selection with necessary coupling of approved make for wash basin & sink. Model Equivalent to Q503191720 + Q503191520	6.00	Nos	0.00	0.00
71	Urinal : Providing and fixing urinal with zinnia sensor integral battery operated , of as per approved make of selection including connecting the urinal with waste pipe and all works related to this item etc complete. Model Equivalent to Q357610110	4.00	Nos	0.00	0.00
72	Urinal : Providing and fixing urinal with marsala sensor (with ac & dc supply) , of as per approved make of selection including connecting the urinal with waste pipe and all works related to this item etc complete. Model Equivalent to Q257630210	1.00	Nos	0.00	0.00
73	Providing and fixing in position Soap Dispenser of as per approved make of selection with soap container. Model Equivalent to ACN-CHR-1135N	6.00	Nos	0.00	0.00
74	Providing and fixing Toilet papers holder of as per approved make of selection or as directed by EIC. Model Equivalent to ACN1153N	5.00	Nos	0.00	0.00
75	Providing and fixing Towel rack of as per approved make of selection or as directed by EIC. Jaquar ACN-1121N	6.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
76	Handrayer : Providing and fixing in position of Handdrayer of as per approved make list. Work completed as per the instruction of EIC. Model Equivalent to HDR-SAP-M99ACS	5.00	Nos	0.00	0.00
77	Providing and fixing 15mm dia. Angular Stop Cock of as per approved make of selection. Model equivalent to Q503191120	6.00	Nos	0.00	0.00
78	Providing and fixing 15mm dia. Sink Cock of as per approved make of selection. Model equivalent to: FLR-5347N	1.00	Nos	0.00	0.00
79	Providing and fixing Kitchen sink as per approved make including all fitting material including Fixing of with necessary plumbing work as per detail drawing and plumbing work. Material approved by architect/EIC. Nirali : Grace Plain-510MM X 432MM	1.00	Nos	0.00	0.00
80	Dustbin : Providing and placing in position S.S. Solid Pedal Bin with inner removable container of as per approved make and as selected by the Architect. Size: 10" X 15"	25.00	Nos	0.00	0.00
81	Providing and fixing 6 mm thick mirror of Saint Gobain/ Modiguard / Asahi as per approved make shall be fixed with profile frame section (copper/brass/silver/gray/black etc.). Provision shall be made for conceal led light work as per detailed drawing/ instruction of architect complete. Rate shall be inclusive of frosting work as per detail drawing.	8.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
82	<p>Toilet Cubical : @1000(W) X 1500(D) x 2050(H) mm</p> <p>Supply & Installation of Toilet Cubicles as per as per Architect selection & approved make. 12 mm Compact Grade 1.5 mm thick laminateBoard of the approved shade by Architect. Accessories for cubicles. 1. Aluminum "U" Section with SS Exterior grade Finish. 2. Aluminum "H" Section with SS Exterior grade Finish. 3. Aluminum Top Rail with SS Exterior grade Finish. 4. SS Coat Hook (SS 316) 5. SS Privacy Thumb Turn (SS 316) 6. SS Door Knob (SS 316) 7. SS Hinges (SS 316) 8. SS Adjustable Leg (SS 316)With Rubber lining and Screw Etc. Work complete including all type of fittings, fixtures, tools, etc complete as per manufacturer specification and drawing.</p>	1.00	Nos	0.00	0.00
83	<p>JC shutter: Supply & Installation of Cubicles with shutter as per as per Architect selection & approved make. 12 mm Compact Grade 1.5 mm thick laminateBoard of the approved shade by Architect. Accessories for cubicles. 1. Aluminum "U" Section with SS Exterior grade Finish. 2. Aluminum "H" Section with SS Exterior grade Finish. 3. Aluminum Top Rail with SS Exterior grade Finish. 4. SS Coat Hook (SS 316) 5. SS Privacy Thumb Turn (SS 316) 6. SS Door Knob (SS 316) 7. SS Hinges (SS 316) 8. SS Adjustable Leg (SS 316)With Rubber lining and Screw Etc. Work complete including all type of fittings, fixtures, tools, etc complete as per manufacturer specification and drawing.</p>	1.00	Nos	0.00	0.00
84	<p>Handicap toilet accessories: Providing and fixing Handicap toilet as per approved make, like one hinged rail, 4 nos of grab rail, including all type of fixtures, fittings, etc complete as per instruction of Architect/EIC. Rate shall be inclusive of all materials, loading, unloading, all taxes, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC.</p>	1.00	Pair	0.00	0.00
85	<p>Providing and fixing S.S. Nahni trap for drain - 100 mm diameter with jali of the following nominal diameter of self cleansing design with SS/ C.I sread down or hinged grating including the cost of cutting and making good the walls.</p>	6.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
86	Urinal Partition: Providing and fixing stone slab with table rubbed, edges rounded and polished, of size 75x50 cm deep and 1.8 cm thick or required size as per drawing, fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6 mm nominal size) as per direction of Engineer-in-charge and finished smooth. Basic rate of stone is 150/ Sq.ft	3.00	Sq.mt	0.00	0.00
87	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [A] 15 mm.	2.00	Rmt	0.00	0.00
88	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [C] 25 mm.	70.00	Rmt	0.00	0.00
89	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [D] 32 mm.	35.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
90	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [E] 40 mm.	40.00	Rmt	0.00	0.00
91	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. including all necessary fittings like Elbo,Tee, Union, Nipple, Plug etc., giving water tightness test and finishing the floor, wall and ceiling including the necessary civil works involved etc.complete as directed by E.I.C. [F] 50 mm.	30.00	Rmt	0.00	0.00
92	Providing laying and jointing in true line and level 50mm dia. U.P.V.C. Pipe (SCH- 40) for cold water including fittings make PRINCE / SUPREME / ASTRAL / FINOLEX or equivalent as approved by Engineer In Charge. Pipe shall be fixed on the wall with the help of clamp at every two metre C/C or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of all materials.	35.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
93	Providing, laying and jointing in true line and level 110 diametre U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 110 mm diametre x 149 mm length x 145 mm heigh at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	65.00	Rmt	0.00	0.00
94	Providing and fixing to wall ceiling and floor 10.0 Kg. F/Cm2 working pressure polythene pipes of the following outside Dia. Low densidy, complete with special falnge compression type fittings, wall clipsetc. including making good the wall ceiling and floor.(F) 75mm	60.00	Rmt	0.00	0.00
95	Fabricated work: Providing Fabrication & erection of steel structure as per drawings including materials, consisting of plates, rolled steel joists, channels, angles, chequered plates etc and also rectangular / square hollow steel sections, insert plates in RCC/Brickwork, anchor bolts for steel structure, sleeve pipes, anchor nuts, washers etc, straightening of raw steel if required, fabrication of steel structures with primer and minimum two coats of anti corrosive paint including preparation of supplementary sketches and detailed bill of materials supply of bolts, nuts, washers, shims, packs, putty. gas, welding electrodes and all other consumables, as required and carrying out surface preparation all complete. The scope includes loading, transportation, unloading and delivery and erection site of all fabricated structures, alignment and welding of all structures true to line, level, plumb and dimension, including rectification if any, splicing, site assembly all as per technical specifications and drawings, all complete.Contactror shall provide stability certificate for the fabrication structure. Rate inclusive of shop drawing.	300.00	KG	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
96	<p>ACP Clading: Designing, fabricating, testing, installing and fixing in position Curtain Wall with Aluminium Composite Panel Cladding, with open grooves for linear as well as curvilinear portions of the building , for all heights and all levels etc. including: (a) Structural analysis & design and preparation of shop drawings for pressure equalisation or rain screen principle as required, proper drainage of water to make it watertight including checking of all the structural and functional design. (b) Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. (c) The fastening brackets of Aluminium alloy 6005 T5 / MS with Hot Dip Galvanised with serrations and serrated washers to arrest the wind load movement, fasteners, SS 316 Pins and anchor bolts of approved make in SS 316, Nylon separators to prevent bi-metallic contacts all complete required to perform as per specification and drawing The item includes cost of all material & labour component, the cost of all mock ups at site, cost of all samples of the individual components for testing in an approved laboratory, field tests on the assembled working curtain wall with aluminium composite panel cladding, cleaning and protection of the curtain wall with aluminium composite panel cladding till the handing over of the building for occupation. Base frame work for ACP cladding is payable under the relevant aluminium item.s The Contractor shall provide curtain wall with aluminium composite panel cladding, having all the performance characteristics all complete , as per the Architectural drawings, as per item description, as specified, as per the approved shop drawings and as directed by the Engineer-in-Charge. However, for the purpose of payment, only the actual area on the external face of the curtain wall with Aluminum Composite Panel Cladding (including width of groove) shall be measured in sqm. up to two decimal places.</p>	14.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
97	S.S. Railing : Vetroline 10401 T3 (M) Handrail Round 50mm Providing and fixing 1050mm high SS Railing (304 grade) system comprising 50mm dia. and 16 guage (1.6mm) Stainless steel pipe top handrail (SS 304 - Matt Finish), 35mm dia. and 16 guage (1.6mm) Stainless steel pipe at bottom & vertical support and 16mm dia. and 16 guage (1.6mm) Stainless steel vertical intermediate pipe (SS 304 - Matt Finish) placed at 100mm c/c distance and as per site requirement. Railing fixed on floor with 120x50x10mm base plate. whenever required, joints to be filled with bushings for extra strength. Rates should be inclusive of welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, including fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the side of waist slab/wall with suitable arrangement as per approval of Engineer/ Architect. Work shall complete includes all type of tools, tackles, all level & Height, labour, safety measures, mock sample etc complete as per the detailed drawing and instruction of EIC. Note :Handrail Length will be measured from Starting to End Location	58.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
98	<p>Gypsum 30min Fire Resistance ceiling: M/F Suspended 30min Fire Resistance ceiling includes Gypserra™ Perimeter Channel {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS27)} is fixed along the perimeter of existing wall/ partition with the help of HILTI HPS - 1 (6x40) impact anchor, at 600mm centres. Gypserra™ Ceiling Angle {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} is suspended by fixing it to the Gyproc® soffit cleat {GI(IS513)YS-260Mpa,Finish-Galvanised 150GSM(IS277)}. Soffit Cleat and Gyproc® Rawl Plug- Ø8x45mm {Material-IS 513 CR2 grade, Zinc coating (7 to 8 microns) pull out load-6.8kN for M30 concrete grade} creating 1220mm x 1220mm grid. Gypserra™ Intermediate channel {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277) } is fixed to the Gypserra™ Ceiling Angle with M6 x 12mm Hex Bolt & Hex Nut arrangement {Material-As per EN 10083 Finish – Zinc Plating} or with 2 Nos of Ø4.2x13 Gyproc® metal to metal screw {Material-Carbon steel EN-ISO 7049/50 Finish- Zinc Coating Thickness- 4.14micron.} The Gypserra™ Ceiling Section {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} is then fixed to the Gypserra™ Intermediate Channel {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} with the help of Gyproc® Connecting Clip {Material-High carbon spring steel wire(BS970Gr.En42)-46-48HRC,Finish- Zinc plating 4-6 micron} and in direction perpendicular to the Intermediate channel at 457mm c/c. Use 50mm thick rockwool above celing for fire insulation, then Single layer of 15mm tapered edge Gyproc Firestop Board as per (EN 520: 2004, Type F) is then screw fixed to ceiling section with 25mm drywall screws {Material-Carbon steel EN-ISO 7049/50,Finish-Case hardened Grey Phosphating} at 230mm centres on ceiling section & 150mm at periphery of ceiling. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Gyproc® Easy-fill 90 Jointing compound (Conforms to ASTM C475), Gyproc® Joint Paper tape. Serrated section has effective thickness of 2T (2xdepth), better load carrying capacity. The item includes providing and fixing trap door of size 600 X 1200 mm as per approved sample of Ceiling panels comprise of a powder-coated beaded steel frame with gypsum / plywood board door. Each panel features a push- latch closing mechanism with door retaining safety cable & hook.Suspenders from ceiling to support the frame and trap door firmly along with necessary hilti fastner, cleats, screws, angles, packing, , safety measures necessart framing work if required etc. complete work. Necessary cutting / providing openings in the ceiling for AC fixtures, grills, electrical fittings, or other utility services, hatch openings etc. shall be provided by the Contractor and cost of making such modifications shall be included in the price.</p>	553.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
99	<p>Wooden ceiling finish with Veneer: Providing and fixing IS 710 12 mm thick Marine plywood ceiling finish with 4 mm thick veneer as per drawing, instruction, sample approved & complete with Aluminium anodised section size 50x50x1.5 mm & 25x50x1.5 mm/ GI frame work. the frame work fixed as per drawing @ 600 mm c/c. finish with 4 mm thick Veneer with matt finish monocoat polish. Rate shall inclusive cost of making of all cutouts for light fixtures, gadgets, gizmo, pelmets, grooves, CNC engraving, beads and also provide support/template where ever required. The rate shall be in sq.mt for all floors and at all heights including all costs. (or a sample mock of 5 Sqm minimum of the frame work and ceiling) shall be approved from Architect. 5mm Groove shall be provided at the junction of the ceiling & the wall. (considering all levels with require all Framing work and fitting from RCC slab to ceiling level). Basic rate of teak Veneer 120/Sqft</p>	130.00	Sq.mt	0.00	0.00
100	<p>Fabric ceiling (TRANSLUCENT) : Providing & fixing CLIPSO TRANSLUCENT coverings (ceiling & wall) made out of polyester knitted fabric coated with Polyurethane (PU). The tear strength of fabric should be accordance to CH: 4,5daN; TR: 6, 5 daN. The fire rating should be accordance to B-S1, d0. The fabric should be humidity resistant and free of carcinogenic substances (CMR) or volatile organic Compounds (VOC's).A+ labeling in accordance with the French decree no. 2011-321, Oeko-Tex standard100 certified. The fabric should be paintable/printable with approved manufacturer guidelines with 10-year manufacturer guarantee. Rate shall inclusive cost of making of all cutouts for light fixtures, gadgets, gizmo, pelmets, grooves, beads and also provide support/template where ever required.The rate shall be in sq.mt for all floors and at all heights including all costs material and fittings, scaffolding.</p>	35.00	Sq.mt	0.00	0.00
Total Amount					0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
C	Part-3				
101	<p>Full Height Partition Gypsum Partition (60min. fire rating) : 100mm thick Gypserra™ stud partition which includes inner layer of tapered edge 12.5mm thick Gypboard® Plain (conforming to IS 2095 Part 1:2011, Certified board) of size 1219x2438mm and outer layer of tapered edge 12.5mm thick Gyproc®Fireline board of size 1219x2438mm is screw fixed to C-stud.48x0.5mm Gypserra™ C-stud {Material-IS 513, Y/S-300Mpa, Finish - AZ150 (IS 15961)} placed at 610mm c/c in 50x0.5mm Gypserra™ {Material-IS 513,Y/S-300Mpa, Finish - AZ150 (IS 15961)} floor and ceiling channel.Floor & Ceiling channel is anchored to the floor & True ceiling using Gyproc® Rawl plug Ø8x45mm {Material-IS 513 CR1 grade, Zinc coating, Pull Out Load-6.8kN for M30 concrete grade} /Hilti X-GN20MX anchor fasteners at 600mm c/c in centerline manner.Floor channel to be wrapped with 70µ Self Adhesive LDPE moisture barrier film to further improve corrosion resistance performance. 12.5mm thick Gypboard® Plain board strip of 50mm width is placed between ceiling channel and RCC ceiling slab when deflection is more than 10mm & fire rating is more than 30min. A Gypserra™ noggin channel {Material-IS 513,Y/S-300 Mpa, Finish - AZ150 (IS 15961)} of 50x0.5mm width has to be provided at the horizontal joints of the two boards. First layer of Gyproc® boards to be screw fixed with Gyproc® drywall screws of 25mm at minimum spacing of 600mm at centre and 600mm at periphery. Second layer to be screw fixed Gyproc® drywall screws of 35mm at minimum spacing of 300mm at centre and 300mm at periphery. 50mm Glass wool slab of density 20kg/m³ shall be placed in metal framework. Glass wool holding clip should be used to hold Glass wool slab in its position. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Gyproc® Pro-Fill Jointing compound, (Conforms to ASTM C475), Gyproc® Joint Paper tape or fiber tape. The junction of the partition with masonry & all penetration through the partition has to be treated with Hilti/Pyroplex fire and acoustic sealant. All other detailing and specifications to be followed as per approved drawing of Gyproc.Note: Applicator need 60min. fire rating certificates from Gyproc.Rate shall include cost of making of all cut-outs for light fixtures, switchboards gadgets, gizmo, pelmets, grooves, beads and also provide support/template where ever required & For door frame fixing, storages, shelves, paneling etc extra Wooden members to be used shall be of CP teak wood only. Including skirting /MDF board/wooden skirting cut out as per EIC instruction at siteThe rate shall be in sq.mt for all floors and at all heights including all costs. including ply base for fixing of TV or Overhead storage wherever required, The rates are also inclusive of necessary scaffolding, tools, tackles,, safety measures , Internal partial support (between two sturd) at 7' height.The shop drawing (or a sample mock of 5 Sqm minimum of the frame work and partition) shall be approved from EIC and Architect. All exposed corner shall be covered with perforated angle as per manufacturer's specifications or as directed by EIC.Partition ht will be measured from finish floor to false ceiling level only.</p>	32.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
102	<p>Wooden solid Partition finished with Both side VNR Laminate: Providing & fixing 12mm thick fire retardant marine plywood as per IS 710:2010 and IS 5509:2000 fixed on frame work on both side finish with 1mm thick Laminate. The frame work shall be made from square hollow aluminium section size of 50x50x1.5 mm & 25x50x1.5 mm of approved make conforming to IS code. The framework shall be fixed as per drawing vertically @ 600 mm c/c & horizontal 600 mm c/c horizontally. All ply/wooden shall be treated with anti- termite treatment . Both side finish with VNR Laminate. Rates shall also be inclusive of cost of making cut outs/ openings for MEP services & providing additional sections for strengthening around the openings/cutouts additional support for fixing of patch fittings for doors, making grooves between wall & board, in filled with termite treated wooden members if required or as per drawing /instruction of EIC. and no extra payment shall be considered for additional sections provided. work complete including all type of material, fittings, fixtures, Finish, loading, unloading, safety measures, transportation, all leads, accessories, groove, PVC edge banding, adhesive ,tape, headless nails, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications & instruction of Client/EIC. only the clear elevation area shall be measured and paid. sample mock shall be approved from Architect/Client. Equivalent to VNR series laminate.</p>	5.00	Sq.mt	0.00	0.00
103	<p>Wooden solid Partition finished with Both side Veneer finish: : " -----Do -----" as per above item specification for complete work. using 4 mm thick Veneer & matt finish monocoat polish instead of laminate for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs. Equivalent to VNR Series Laminate. Equivalent to VNR series laminate.</p>	327.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
104	<p>Thin Profile Glass Partition: Providing & Fixing of STL45 ie. Single glazed modular system consist of Aluminium section of 25*45*2.5 mm thick. All sections duly Powder coated/anodised with 6063-T6 grade and required accessories ie glass to glass aluminium I sections, T section & 90 degree sections & Glass packing to adjust the floor level. Ceiling profile, Floor profile and wall profile are 25 mm visible face and 45 mm wide with 10mm toughen glass as per approved make & insertion of Thermoplastic gasket to adhere the glass firm & airtight. The sound reduction Value is from 32 to 35 Db. With 6 mm Groove inbuilt in system to accomodate the carpet & the uneven surfaces. Work including horizontal thin profile member at lintel lvl. as per drawing.</p> <p>Accessories/Hardware: neutral cure glazed & metal silicon sealant of approved make on the periphery of the glass & wood etc. Partition ht will be measured from finish floor to false ceiling level only. The rate shall be in sq.mt for all floors and at all heights including all costs. Glass width size shall be as per suggestion by EIC. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transporation, all leads, accessories, safety measures, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications & instruction of Client/EIC.</p>	103.00	Sq.mt	0.00	0.00
105	<p>Frosted sparkling glass film (Colour film) : Providing and fixing frosted glass film of approved make Translucent, cast PVC, self-adhesive vinyl, special CRYSTAL-effect film to reproduce Sand-blasting effect on glass with customised designs. MCS warranty of 3 (if exposed to direct sunlight) to 10yrs (indoors) must be endorsed by manufacturer. Rate shall be inclusive plotter cutting design as per Architect/Client suggestion. Contractor shall provide shop drawing for approval of Architect/Client. work complete including all type of tools, tackles, scaffolding etc complete as per suggestion of Architect/Client. If in case any application finishing will not as per satisfaction contractor shall remove all film at their cost. Contractor shall do a sample mock of 5 Sqm minimum of glass film), shall be approved from Architect/Client.</p>	39.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
106	<p>Alluminium Skirting : Providing and Fixing of Aluminium Skirting as per approved make having width of 75 MM X thickness of 2mm made out of 6063 Grade Aluminium alloy duly anodised as desired in the Ral Colour code decided by the architect having neat screw fixed arrangement with Rubber seal over it as per Manufacturers Specification. work complete as per the instruction of Architect. Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, placing at all floors and for all leads,all accessories as described in item description.</p>	184.00	Rmt	0.00	0.00
107	<p>Double Leaf Glass Door: Supply & Installation of Modular Aluminium Glass door frame of Kubik or equivalent make 45mm System, Using KOPS 001 & KOPS DF 103 (45mm x 25mm) for Glass door frame Doorframe Dimension – 45mm x 25mm. Finish – SILVER finish / Powder coating as per approved sample by Architect. 10mm thk. clear toughened Glass KUBIK Glass Hinge, HAFELE Open Door closer with saddle plate, KUBIK Mortise lock with handle, KUBIK Door stoper etc complete. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transportation, all leads, accessories, sample mockup, all floor, all levels, all heights, safety measures, necessary frame work, Scaffolding etc complete as per detailed drawings, specifications & instruction of Client/EIC.</p>	6.00	Sq.mt	0.00	0.00
108	<p>Double Leaf Profile Glass Door: " -----Do-----as per above specification for complete work. Using 8mm thick toughened glass instead of 10mm thk. clear toughened Glass. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transportation, all leads, accessories, sample mockup, all floor, all levels, all heights, safety measures, necessary frame work, Scaffolding etc complete as per detailed drawings, specifications & instruction of Client/EIC.</p>	7.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
109	<p>Single Leaf Glass Door: Supply & Installation of Modular Aluminium Glass door frame of Kubik or equivalent make 45mm System, Using KOPS 001 & KOPS DF 103 (45mm x 25mm) for Glass door frame Doorframe Dimension – 45mm x 25mm. Finish – SILVER finish / Powder coating as per approved sample by Architect 10mm thk. clear toughened Glass KUBIK Glass Hinge, HAFELE Open Door closer with saddle plate, KUBIK Mortise lock with handle, KUBIK Door stoper etc complete Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, necessary frame work, Scaffolding, safety measures etc complete as per detailed drawings, specifications & instruction of Client/EIC.</p>	11.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
110	<p>Veneer panelling: Providing & fixing 12mm thick fire retardant marine plywood as per IS 710:2010 and IS 5509:2000 fixed on frame work finish with 4mm thick Veneer & matt finish monocoat polish. The frame work shall be made from square hollow aluminium anodised section size of 50x50x1.5mm & 25x50x1.5mm of approved make conforming to IS code. The framework shall be fixed as per drawing vertically @ 600 mm c/c & horizontal 600 mm c/c horizontally. All ply/wooden shall be treated with anti- termite treatment. Measurements for paneling work to be recorded upto finished false ceiling level only irrespective of aluminium frame work, which shall be provided from gr. level to RCC slab / beams soffit level. Rates shall also be inclusive of cost of making CNC/engraving /cut outs/ openings for electrical fixtures, tube lights /air-conditioners, grills, diffusers etc & providing additional sections for strengthening around the openings/cutouts additional support for fixing of patch fittings for doors, making grooves between wall & board, in filled with termite treated wooden members if required or as per drawing /instruction of EIC. and no extra payment shall be considered for additional sections provided. All curved surfaces, recesses, waffles shall be part of the paneling including openable shutter wherever required area and finished with the same material. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transportation, all leads, accessories, groove, adhesive, tape, headless nails, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications & instruction of Client/EIC. only the clear elevation area of finished plywood wall paneling with Veneer shall be measured and paid. sample mock shall be approved from Architect/Client. Basic rate of veneer is 120/ Sq.ft</p>	257.00	Sq.mt	0.00	0.00
111	<p>Veneer Fluted panelling: " -----Do -----" as per above item specification for complete work. using 12mm thick Veneer Fluted panelling & matt finish monocoat polish instead of veneer for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs.</p>	19.00	Sq.mt	0.00	0.00
112	<p>Fluted panelling: " -----Do -----" as per above item specification for complete work. using 12mm thick Fluted panelling with bronze & brass finish instead of veneer for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs.</p>	29.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
113	<p>Laminate Panelling : " -----Do -----" as per above item specification for complete work. using 1 mm thick laminate instead of veneer for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs. Equivalent to VNR Series Laminate.</p>	55.00	Sq.mt	0.00	0.00
114	<p>Fabric panelling: Providing and fixing Fabric Wall Paneling made of 50mm thick glass wool of density 24 Kg/cum and wrapped on the front side with an acoustically transparent and fire-resistant fabric with an option of colors as approved by Architect. providing a minimum sound absorption level of 0.95 NRC. Installation of Acoustic Fabric panels on GI frame work of section 50mm x 50mm on GI pipe frame factored at Sl. No. 10. GI panels fixed horizontally at spacing of 600mm center to centre and screwed aluminum extruded keel for channeled wood works. 6mm thick BWP ply (Duro/ century / Green) to be fixed on the frame work. Wall panel impellers shall be fixed to the GI frame using self tapping screws. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transportation, all leads, accessories, groove, adhesive, tape, headless nails, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications & instruction of Client/EIC. only the clear elevation area shall be measured and paid. sample mock shall be approved from Architect/Client. Basic rate of fabric Rs. 1500 / Rmt</p>	104.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
115	<p>Writable with magnetic glass board : Providing & fixing 4mm thick writable coloured magnetic glass on existing partition/wall as per approved sample by Architect/Client. work Including cost of all type of fittings, accessories, tools, tackles, all labour, scaffolding, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. etc.work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.Only the clear elevation area shall be measured and paid.</p>	5.00	Sq.mt	0.00	0.00
116	<p>Gypsum panelling: Gypsum panelling :The M/F wall lining includes 12.5mm Gyproc® Quattro Gypsum Board, screw fixed with drywall screws of 25mm at 300mm centers to one side of 45X18X0.5mm Gypliner ceiling channel (0.5mm thick having 18mm flange each made of GI Steel) placed at 600mm center to center in 195X29.5X0.9mm fixing bracket at 900mm c/c with 25X25X0.5mm Gypliner angle at bottom and top of the channel such a manner that joints staggered to avoid leakage through joints. Fixing strip of 75X0.5mm should be installed at horizontal joint of boarding. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Jointing compound and Joint Paper tape. 50mm Glasswool of density 20kg/m3 should be placed in metal frame.Necessary fabrication with anticorrosive paint work , scaffolding, anchor fasting , bolting HILTI or equivalent make with testing certified in scope of contractor)Rate shall include cost of making of all cut-outs for light fixtures, switchboards gadgets, gizmo, pelmets, grooves, beads cut out as per EIC instruction at siteThe rate shall be in sq.mt for all floors and at all heights including all costs. The shop drawing (or a sample mock of 5 Sqm minimum of the frame work and partition) shall be approved from EIC and Architect. Panelling item including openable shutter wherever required area and finish with the same material. Only the clear elevation area shall be measured and paid.</p>	63.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
117	<p>Onyx Stone Panelling : Providing and fixing 18mm thick Onyx stone panel as per approved make & Sample by Architect/ Client. 12mm thick Acrylic transparent sheet fixed on framework. The frame work shall be made from square hollow aluminium anodised section size of 50x50x1.5 mm & 25x50x1.5 mm of approved make conforming to IS code. The framework shall be fixed as per drawing vertically @ 600 mm c/c & horizontal 600 mm c/c horizontally. Work Inclusive of Cutting as per detailed drawing and instruction of Architect. Including surface preparation, Including cost of all type of tools, tackles, all labour, scaffolding, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. etc. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Rates shall also be inclusive of cost of making CNC/engraving /cut outs/ openings for electrical fixtures, tube lights /air-conditioners ,grills, diffusers etc & providing additional sections for strengthening around the openings/cutouts additional support for fixing of patch fittings for doors, making grooves between wall & board, as per drawing /instruction of EIC. Basic rate of Onyx stone Rs.1100/Sq.ft. Only the clear elevation area shall be measured and paid.</p>	10.00	Sq.mt	0.00	0.00
118	<p>Metal Profile : Providing and fixing of 5mm thick S.S. T Profile Copper or as per approved sample by Architect including necessary material, adhesive tools, tackles, fittings etc complete. Work complete including all type of tools, tackles, scaffolding, mock sample, etc complete as per instruction of Architect/ EIC.</p>	10.00	Rmt	0.00	0.00
119	<p>SS Screen/ Jali with PVDF coating : Providing and fixing of S.S. Metal jali with PVD coating of approved shade & as per approved sample by Architect. Works including necessary material, adhesive tools, tackles, fittings etc complete. Work complete including all type of tools, tackles, scaffolding, mock sample, etc complete as per instruction of Architect/EIC.</p>	11.00	Sq.mt.	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
120	<p>Soft Board : Providing and fixing on wall 12mm thick approved quality soft board with cotton cloth/fabric of approved make and shade on 12mm thick IS 710 ply 50 mm th approved Glass wool sheet with PVC grip, as approved sample and as directed by EIC. The work shall be measured & paid in Sqm. for all floors, all level and at all heights including all costs. Only the clear elevation area of the cloth/fabric shall be measured and paid. All the work complete as per the detailed drawing, mockup sample and instruction of Architect/EIC. Basic rate of cotton cloth /fabric for 54" wide shall be Rs. 200/Rmt.</p>	2.00	Sq.mt	0.00	0.00
121	<p>Ply palmet : Providing and fixing wooden pelmets of upto 200 mm x 300 mm L shape made of 19mm thick ply as per IS 710 and beading of 4mm thick and 25mm wide Ghana Teak wood for projection screen. Rate to be inclusive of lipping, cutting, wastages, necessary fixtures, nails, adhesives, necessary scaffolding, fixing at all heights and for all floors as per drawing and approved sample etc should also take load of all the all roller blinds.</p>	100.00	Rmt	0.00	0.00
122	<p>Roller Blinds : Providing and fixing blinds as per approved make as per suggested shade & spring drive system with steel ball chain/one touch with speed control action roller blind with end brackets with head rail, components, bottom bar. Fabric : screen classic 3% to 5% Fabric value : 470 Gsm , Thickness : 0.60 to 0.70 mm Construction: 75 % PVC & 25 % Polyster Fabric to be as per approved sample. All the work complete as per the detailed drawing, mockup sample and instruction of Architect/EIC. All complete as per approval of designer. The mode of Measurement: The size of the blind will be measured from end to end bracket (Left to Right bracket) height will be measured from top of the pelmet to sill bottom level and clear opening size only there will be not extra payment towered overlapping.& mockup sample approved by the Architect/ EIC.</p>	16.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
123	<p>Motorised Curtain : NANTUCKET - N23 (summer linen)AC POWER VIEW :BLACK REMOTE&WHITE PABBLE System Specification : Supply & Fixing of of Nantucket Window Shadings from Hunter Douglas in 3" vane size having head rail and bottom rail made of aluminum alloy extruded profile, powder coated and provided in standard natural white color. The rolling tube should make up of aluminum alloy from extruded profile of Ø34 mm. The head rail dimensions should be in the range of: H 58 mm x 72 mm or 62 mm x 81 mm for the larger head rail. The cassette should conceal the working mechanism rotary-clutch that raises lowers and tilts the shade contains and protects shading fabric when fully raised. All plastic parts are in white color. Operation options: endless cord loop. Installation to be done by quick release brackets (wall or ceiling) Fabric Specification (Room Darkening-N23) The fabric is anti static polyester light darkening vanes which have facings between 2 sheers layers (50 mm wide) to reduce glare. Sheer layers made of white 100% knit polyester & the selection of colors, textures and opacities from the Hunter Douglas® collection as specified by the architect. The shading to be operated by Easy rise mechanism with a continuous cord loop operating option. The FABRIC shall be constructed from spun-bonded 100% polyester fiber, having Green guard certified, trated with soil & dust repellant require minimum regular interval cleaning. The rate shall be for complete item inclusive of providing & fixing, all material, all motorised mechanism , labour, wastages, necessary tools & tackles, hardware/accessories etc for all floors, all heights, all levels and all places within campus. Work completed as per approved sample by Architect/Client.</p>	21.00	Sq.mt	0.00	0.00
124	<p>Providing and fixing screen: Providing Fabrication & erection of-12 mm thick WPC jali with cutting/Engraving as per reference image given by Architect. The work includig necessary fabrication work, fittings, fixtures, accessories etc complete. Finish : Anti corrosive paint with primer as per approved shade by Architect. The scope includes loading, transportation, unloading and delivery and erection site of all fabricated structures, alignment and welding of all structures true to line, level, plumb and dimension. sample mock shall be approved from Architect/EIC. Shop drawing shall be provided by Contractor.</p>	6.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
125	<p>Cabin table unit : Table top : 2800 x 900 x 750mm, Side Unit - 1050 x 450 mm, Back side unit : 2800 x 450 x 750 mm Pedestal Unit- 400x470x545 mm. Providing and fixing table unit consist main table, side table ,back storage with pedestal unit with all necessary accessories keyboard, CPU stand ,cable manager, modesty panel etc with all required necessary accessories. All finishes veneer with polish,powder coating /anodizing shade shall be approved by architect. Rate shall inclusive of mock up sample providing and fixing at site of unit for approval of architect. Top: 50 mm thick top comprising from 303 BWR ply , wooden framing & finish with 4 mm thick veneer. All top edges finish with approved style stone including buffing complete. Main table front & Vertical support : IS 303 BWR ply , Metal box section , veneer with PU polish. Wire management: Rate inclusive of providing and fixing as per approved and provision of as requirement Pop up box with socket electrical (WIRE MANAGEMENT BOX SS finish).Writing pad: Made from approved leather finish with require accessories. Mobile Pedestal unit : Storage body is comprising from IS 303 BWR ply with veneer finish and inner side 1 mm thick laminate finish including require nos of drawer and shutter all type of fittings , fixtures, hardware as per approved make complete .SS 304 grade conceal handle shall be provide as per approved selection &detailed drawing and instruction of Architect/EIC . The work shall be done as per the drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives consumable hardware & required SS 304 grade hardware/accessories , PU polish , PVC edge beading of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. The unit shall be manufactured in parts and these parts shall be assembled at site. Basic Rate for material only veneer - 110/Sqft.</p>	1.00	Unit	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
126	<p>PA cabin table unit: Table top : 1800 x 750 x 750 mm, Side Unit : 1200 x 450x 750 mm, Pedestal Unit-400x470X545 mm.</p> <p>Providing and fixing table unit consist main table, side table ,back storage with pedestal unit with all necessary accessories keyboard, CPU stand ,cable manager, modesty panel etc with all required necessary accessories. All finishes laminate,powder coating /anodizing shade shall be approved by architect. Rate shall inclusive of mock up sample providing and fixing at site of unit for approval of architect.</p> <p>Table top : 25 mm thick postfoam top (reverse bull nose) with 1 mm thick VNR laminate finish as per approved make and sample by Architect/ Client.</p> <p>Verticle support: Combination of alumium extrusions(6005-T6) & aluminium dia cast component (LM-24).4.Horizontal Support: Aluminium extrusion (6005-T6) Or MS support with powder coated . Wire management: Raceway :0.8 mm thick CRCA horizontal and vertical raceways with metal separator .one way or two way openable flip top box mounted on table top squeeze :A special flexible rubber component that allows easy and safe passage of wires. All the exposed edges are sealed with 2mm thick PVC Imported edge banding on sides and bottom. The top and drawer facia are sealed with 2mm thick PVC edge. The drawer unit consists of 1 box drawer and 1 file drawer. The drawer box is fitted with telescopic channel Hettich or Haffle make for free movement. The drawer unit is provided with central locking system, where in the drawer are locked with one key.SS 304 recessed handles are provided for easy opening and closing of drawer. The drawer unit is fitted on castors (optional) for easy mobility. PVC edge banding are imported from Rehau or Dolken of Germany. The complete furniture unit is factory assembled with knock down fittings. Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, monocoat polish, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing , mockup sample and instruction of Architect/Client. Equivalent to VNR Series Laminate.</p>	3.00	Unit	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
127	<p>Cabin Back side storage unit (750 H x 450 D) mm: Storage Comprising from IS 303 BWR 19 mm thick and 12 mm ply, finish with 1 mm thick Laminate finish as per approved make and shade by Architect. Storage top : 35 mm thick post foam top edge finish as per selection and laminate as per selection suede /satin/VNR finish. Solid Shutter : 25 mm thick comprising from IS 303 BWR ply & finish with 1 mm thick VNR Laminate . Shelf: 19 mm thk IS 303 BWR ply finish with both side approved laminate. Inner area shall be finished with linear laminate. Ledge/Niche comprising from IS 303 BWR ply finish with 1 mm thick Laminate , required lighting arrangement. The work shall be done as per the detailed drawing, specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives, grooves, consumable hardware & required SS 304 grade hardware/accessories, Profile handle, Wooden frame, monocoat polish, pvc edge banding, of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Equivalent to VNR series laminate.</p>	5.00	Sqmt	0.00	0.00
128	<p>Console : Providing & fixing Console complete as per drawing/Ref Image. Approx size : 1500 x 400 x 1050 mm made from up of 19 mm thick BWR grade ply & finished of Laminate as per approved make and shade and solid wooden leg with matt finish monocoat polish as per drawing. Rate shall be inclusive of providing, fixing all necessary brass satin finish nickel plated/ S.S 304 grade (hardware from Hettich like Auto Hinges, handle, Rod locks, Multipurpose lock, Rate shall be inclusive of 2nos. of drawer unit of 19mm thick IS 303 BWR ply and laminate, PVC edge beading. All external & internal exposed woodwork to be finished in PU semi gloss paint finish polish as per specified item's manufacturer's specifications. Rate shall inclusive of providing mock up sample for approval of architect. Equivalent to VNR series laminate.</p>	3.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
129	<p>Meeting room table : Table size : 6750 x 1800 x 750H mm</p> <p>Providing and fixing as per detail shape and size table unit consist table with all required necessary accessories.</p> <p>Top 50 mm thick comprising from 15-16 mm thick Artificial stone as per approved sample (reverse bull nose). Base & Vertical support comprising from ready made leg Metal finish as per approved sample by Architect. Ply box for cable runway comprising from IS 303 BWR ply with both side 4 mm thick Veneer finish with polish. Popbox: Flip open-Aluminium SS finish or approved finish open above the table top with build in soft closing mechanism and termination box below table top to accommodate electrical and data sockets Raceway : MS powder coated horizontal raceways considered below table top with intermediate legs provided to allow LAN & electrical cables.</p> <p>Rate inclusive of providing and fixing as per requirement of socket and quantity Pop up tabletop electrical WIRE MANAGEMENT BOX SS finish. The work shall be done as per the detailed drawing , specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives consumable hardware & required SS 304 grade hardware/accessories, grooves pvc edge banding , etc of approved make for all floors, monocoat polish, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Basic Rate of Veneer is Rs.120/ Sqft. Basic rate of stone is 450 / Sq.ft</p>	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
130	<p>Full Height Storage with Laminate Finish : 450 mm Depth Storage Comprising from IS 303 BWR 19 mm thick and 12 mm ply, finish with 1 mm thick Laminate finish as per approved make and shade by Architect. Solid Shutter : 25 mm thick comprising from IS 303 BWR ply & finish with 1 mm thick Laminate . Shelf: 19 mm thk IS 303 BWR ply finish with both side approved laminate. Inner area shall be finished with linear laminate. Ledge/Niche comprising from HDF / Lacquered glass finish w, required lighting arrangement. The work shall be done as per the detailed drawing, specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives, grooves, consumable hardware & required SS 304 grade hardware/accessories, Profile handle, Wooden frame, monocoat polish, pvc edge banding of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Equivalent to VNR series laminate.</p>	3.75	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
131	<p>Pantry below storage : Providing, making, fixing as per detail drawing made from 19 mm IS 710 BWP ply structure and both side 1 mm thk. laminate finish shall be of approved make & shade and as per the detail drawing. All the edges of ply shall be covered with Laminate finish Rate shall also inclusive of all necessary brass satin finish nickel plated/S.S 304 grade hardware like Hinges, locks,6"handle, 75 mm tower bolts, ball catches/Magnet, The rate shall be inclusive of shelf both side laminated finish and as per detail drawer unit with SS 304 grade kitchen basket as per selction by architect The rate shall be in sqm of elevation area for all floors and at all heights including all costs complete as per the Architectural drawings & instructions.Only the elevation area of the storage unit will be measured and paid for. Item for laminate fixing and polishing is included in this item. Approval of all loose material (sample of materials to be used) & raw manufacturing to be got approved in advance from EIC & Architect prior to the final production of the work. Manufacturing shall in parts or as whole as per the requirements & or assembled at site as per the requirement and directed by EIC & Architect. All material to be used shall be as per the drawings & confirm to the relevant detailed material specifications of this document. The work shall be measured & paid in sqm. The rates shall be inclusive of all wastages, material, labor, transportation, loading, unloading, fixing in position, etc. complete to the satisfaction of the Architect and EIC. The mock-up of 1 unit shall be approved from EIC and Architect prior to the final production. Equivalent to VNR series laminate.</p>	6.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
132	<p>Pantry above storage -350DX600 H: Providing, making, fixing as per detail drawing made from 19 mm IS 710 BWP ply structure and both side 1 mm th laminate finish shall be of approved make & shade and as per the detail drawing. All the edges of ply shall be covered with Laminate finish Rate shall also inclusive of all necessary brass satin finish nickel plated/S.S 304 grade hardware like Hinges, locks,6"handle , 75 mm tower bolts, ball catches/Magnet, The rate shall be in sqm of elevation area for all floors and at all heights including all costs complete as per the Architectural drawings & instructions.Only the elevation area of the storage unit will be measured and paid for. Item for laminate fixing and polishing is included in this item. Approval of all loose material (sample of materials to be used) & raw manufacturing to be got approved in advance from EIC & Architect prior to the final production of the work. Manufacturing shall in parts or as whole as per the requirements & or assembled at site as per the requirement and directed by EIC & Architect. All material to be used shall be as per the drawings & confirm to the relevant detailed material specifications of this document. The work shall be measured & paid in sqm. The rates shall be inclusive of all wastages, material, labor, transportation, loading, unloading, fixing in position, etc. complete to the satisfaction of the Architect and EIC. The mock-up of 1 unit shall be approved from EIC and Architect prior to the final production. Equivalent to VNR series laminate.</p>	5.00	Sq.mt	0.00	0.00
133	<p>Center Table: size of bigger table-2'6" Dia and smaller table-2' Dia Providing & fixing of center table Table top: 15 mm thick Artificial stone top. Vertical support: Metal with powder coating. Work complete including all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	7.00	Pair	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
134	<p>Corner Table: Size-1'6" Dia Table top: 15 mm thick Artificial stone top. Vertical support: solid wooden Leg with matt finish monocoat polish with busher. Work complete including Providing & fixing, all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	29.00	Nos	0.00	0.00
135	<p>Chairman cabin table : 3000 x 900 x 750 mm, Side Unit: 1050x 600x750 mm Table top: 15 mm thick Artificial stone top. Structure : Structure made in PLPB, Understructure and modesty panel is made in MS Pipe Powder coated Side Unit consists of 2nos. of Drawers and 2nos. of Shutters. Flip open-Aluminium powder coated flip open above the table top with build in soft closing mechanism and termination box below table top to accommodate electrical and data sockets. Raceway : MS powder coated horizontal raceways considered below table top with intermediate legs provided to allow LAN & electrical cables. CPU stand keyboard - as per selection with approved powder coated. Work complete including all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic Rate of Veneer is Rs.120/ Sqft. Basic rate of stone is 450 / Sq.ft</p>	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
136	<p>CM cabin Drawer & Back storage Unit : 3000 x 510 x 500 mm Providing & fixing TV drawer unit as per detail shape & size with require accessories Top 35 mm thick comprising from 12 mm th IS 303 ply & veneer finish with matt finish monocoat polish, Storage body is comprising from 19mm 303 BWR ply with veneer finish and inner side 1 mm th laminate finish including require nos of drawer with all type of fittings, cutout for air cerclulation, require fixtures, hardware Hettich/Haffle make etc complete. SS 304 grade conceal handle shall be provide as per approved selection & detailed drawing and instruction of Architect/EIC. The work shall be done as per the approved specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives consumable hardware & required SS 304 grade hardware/accessories of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. The unit shall be manufactured in parts and these parts shall be assembled at site. Basic rate of teak veneer is 120 /Sqft</p>	1.00	Nos	0.00	0.00
137	<p>One Seater Sofa : 900(L) x 870 mm (B) x 800 mm (H) comprising up of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC. all external & internal exposed woodwork to be finished in PU semi gloss finish polish. The work shall be done as per drawing, specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 800 Rmt</p>	2.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
138	<p>Two Seater Sofa: 1500mm (L) x 870 mm (B) x 800 mm (H) made up of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density thikness & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC. Leg : Solidwood All external & internal exposed woodwork to be finished in PU semi gloss finish polish.The work shall be done as per the drawing, specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 1000 Rmt</p>	6.00	Nos	0.00	0.00
139	<p>Three seater Sofa: 2100 (L) x 870 mm (B) x 800 mm (H) comprising of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC. Leg : Solidwood All external & internal exposed woodwork to be finished in PU semi gloss finish polish. The work shall be done as per the drawing, specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 1000 Rmt</p>	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
140	<p>Lounger chair :The seat shall 150 mm th 40 density & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC. Leg : Solidwood All external & internal exposed woodwork to be finished in PU semi gloss finish polish. The work shall be done as per the drawing, specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 1000 Rmt</p>	12.00	Nos	0.00	0.00
141	<p>Sofa Seating : Providing and fixing as per requirement seating base made from BWP ply with veneer finish and seating made from 40 density PU foam with fabric finish as per selection of architect complete. The work shall be done as per drawing specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. The unit shall be manufactured in parts and these parts shall be assembled at site. Basic Rate of veneer : 120 Sq.mt</p>	14.00	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
142	<p>Planter box: Providing making, fixing as per detail drawing and required length and depth shall be made from 19mm IS 710 BWP ply with both side laminate finish and providing lighting arrangement cutout and fixing as per detail drawing and instruction. Rate shall inclusive all necessary hardware and fitting, ms framing, paint. The work shall be done as per the specifications, sample approved and as directed by the Architect/ Client. Rate shall inclusive of providing mockup sample for approval of Architect/ Client. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessorie, sample mockup etc as described in item description.work complete as per the instruction of Client/EIC.</p>	6.00	Sq.mt	0.00	0.00
143	<p>Chair Type- 1A - Model equivalent make - HOF MAR-1003 High Back :</p> <ul style="list-style-type: none"> * Chair in Moulded Ply with Head Rest. * Double Cladding. * High Density PU Foam in Seat & Back. * Chrome Arms & Cushion on it. * Multi Tilt Mechanism. * Chrome Base & Gas Lift. <p>Work complete as per the approved sample & instruction of EIC. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessories as described in item description.</p>	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
144	Chair Type-2A -Model equivalent make - HOF MAR-1004 Mid Back * Chair with Moulded Ply in Seat and Back. * PU Moulded foam on Seat & Back. * Adjustable Arms with PP cladding. * Chrome Base. * Synchronized Mechanism & Gas Lift. Work complete as per the approved sample & instruction of EIC. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessories as described in item description.	18.00	Nos	0.00	0.00
145	Chair (PA Cabin) -Model equivalent make - Rockworth-KYLE Medium Back as per approved sample list. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	7.00	Nos	0.00	0.00
146	Head Chair (PA Cabin) -Model equivalent make - Rockworth-KYLE, Highback as per approved sample list. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	3.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
147	<p>Front Chair (Delegates room) -Model equivalent make as per approved sample list. Make : Solidwood, Structure : Solidwood, Outside : Fabric Finish Leg : Solidwood All exposed woodwork to be finished as per approved polish. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic rate of fabric is 1000/ Rmt</p>	10.00	Nos	0.00	0.00
148	<p>Back Chair (Delegates room) -Model equivalent make as per approved sample list. Make : Solidwood, Structure : Solidwood, Outside : Fabric Finish Leg : Solidwood All exposed woodwork to be finished as per approved polish. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic rate of fabric is 1000/ Rmt</p>	10.00	Nos	0.00	0.00
149	<p>Head Chair (Delegates room) -Model equivalent make as per approved sample list. Make : Solidwood, Structure : Solidwood, Outside : Fabric Finish Leg : Solidwood All exposed woodwork to be finished as per approved polish. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic rate of fabric is 1000/ Rmt</p>	2.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
150	CM Visitor Chair : - Model equivalent make as per approved sample list. Make : Solidwood, Structure : Solidwood, Outside : Fabric Finish Leg : Solidwood All exposed woodwork to be finished as per approved polish. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic rate of fabric is 1000/ Rmt	16.00	Nos	0.00	0.00
	Total Amount				0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
D	Part-4				
151	CM Chair -Model equivalent make - Rockworth-Monte, Highback as per approved sample list. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	2.00	Nos	0.00	0.00
152	Ottoman Chair (Ante room) -Model equivalent make as per approved make list. Finish : Fabric Finish Leg : Metal Leg Providing & Fixing of reclinear chair as per approved make. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic Rate of Fabric is Rs 1000 Per Meter	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
153	<p>Art work: Providing and fixing in position commissioned art works inside the building on the wall or ceiling and extension of the same till floor/ceiling. The composition of the commissioned art work shall be from any type of wood, metal like copper, brass, SS, MS, fabric, acrylics, rubber, plastic, tough boards, cementitious boards, fibers, gypsum, POP etc. all. The form of material may also very based on material properties like sheets, wires, blocks, inclusion of cutouts, bending of the materials, profile cutting an shaping of the materials, manufacturing at site as well as at site, covering the prepared material by means of the bubble sheets, jute bags or in wooden packing materials. The commissioned art work may require any shade, finish and texture of duco painting, specialty painting, PU painting, general painting to paintable surfaces, galvanizing, powder coating, anodizing etc. The base surface where the commissioned art work is to be installed also needs some modification to enhance the effect of art works. The use of material like fiber glass wool/ boards, filler fabric, mounting material may also essential based on the design of the art work by artist. The rate shall be inclusive of any type of lighting features to be added into it includes LED lights, neon lights including its supporting and suitable wiring for the same within the art works. Only one electrical control point connection will be given as close to art works. The rate shall be inclusive of making necessary provisions within the commissioned art works of fixing of the same. The provisions of the fixing of the art work may be in parts but it shall be inclusive of the all arrangements like LN key, studs, anchors, nuts and bolts etc. all.. The concept of the art work will be generated by architect and interior designer and based on that offers from the artists to be invited for design and execution of the artwork. The selection of the artist is to be done by architect and interior designer only. Main contractor is bind to follow the methodology suggested by architect and interior designer to be followed for development of commissioned art work. The overall outline area covered by art work is to be considered for the measurement instead of actual area of art work. Deductions of the internal cutouts, spaces in between of the art work shall not be made. Since there is huge variance in types of the commissioned art works, the same is to be completed in all respect inclusive of the materials and methodology is stated above and may not be. For any additional materials, process, methodology no extra payments shall be made. The quotations of the artist shall be got approved in advance including area of the proposed art works. Total payment of the artwork will be done as per basic rate and difference between actual cost per sqm and basic rate per sqm will added or deducted without any consideration of the, overhead and profit over the difference. It is the responsibility of the main contractor to provide scaffolding, power, water, facilitating the areas required for developments and storage of the art work etc. The protection and cleaning of the pre and post installation of the art work is the responsibility of the main contractor.</p>	5.00	Sq.mt	0.00	0.00
154	<p>Signages : Providing and fixing signages comprising form ss plate with Vinyl film letter, HDf finish as per instruction of Archiect/EIC. Contractor shall submit mock up sample.</p>	3.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
155	Logo Work : Providing and fixing standard Logo using virgin acrylic or other material like Colored HDF/cementsheet /SS plate with CNC work complete as per architect selection, letters as per detailed drawings and fixed with approved adhesive with necessary fittings and provision shall be made for conceal LED light as per detail drawing. (logo size will be aprox. Size - 600 mm dia)	1.00	Nos	0.00	0.00
156	indicator signage at Ground floor : Providing and fixing Signages comprising from ACP sheet, Vinyl letter with framing work if required with anti corrosion paint. The rate shall be for complete item inclusive of all material, buffing edge, labor, wastages, necessary tools & tackles, adhesives, consumable hardware & required SS 304 grade hardware/ accessories of approved make. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, etc complete as per drawings, specifications & instruction of Client/EIC.	5.00	Sq.mt	0.00	0.00
157	Trap Door : 12.5mm thick Gypboard® Plain Providing and fixing trap door as per approved sample of Ceiling panels comprise of a Aluminum Alloy 6063 T6 Extrusione (Powder coated) with MR gypsum Board. Each panel features a push- latch closing mechanism with door retaining safety cable & hook. Suspenders from ceiling to support the frame and trap door firmly along with necessary hilti fastner, cleats, screws, angles, packing,etc. complete work. Necessary cutting/ providing openings in the ceiling for AC fixtures, grills, electrical fittings, or other utility services, hatch openings etc. shall be provided by the Contractor and cost of making such modifications shall be included in the price. 600 x 1200 mm	5.00	Nos	0.00	0.00
158	Carpet Flooring Work: " -----Do-----" as per above specification for complete work. Carpet tiles or basic rate of carpet is Rs. 300/Sqft	146.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
159	<p>Customised wall painting Canvas painting with frame work : Providing making painting/polishing and Fixing in position of wooden frames having profile as per drawing and sizes as specified for paintings with card board mounting /canvas frames including backing of required thickness of hardboard / ply board (IS 303 BWR) backing. Frame shall be hanged on the wall using key hole chaplas fixed at the back part of the frame at all heights, all floors and all levels. The rates shall be inclusive of all material, labour, wastage, antitermite treatment, polishing all tools tackles etc complete. Sample of the frame shall be got approved by Architect prior to manufacturing on large scale. D) Wooden Frames for Canvas Work as per drawings: Frame Size - 75mm x20mm Wood Work - Burma Teak Wood Frame shall be finished with PU polish work. The art work shall be hanged on the wall using heavy duty approved key-hole chaplas</p>	6.00	Sq.mt	0.00	0.00
160	<p>Point wiring for Light / Bell with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in/ on surface on wall/ceiling complete with 6A Modular type switch / bell push & accessories and earth continuity of following type, erected on PVC / Metallic box, single mounting base frame covered with textured/metallic front plate modules erected on / in wall / ceiling as per pipe erected, with necessary Lamp holder/ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories CAT III</p>	211.00	Pt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
161	Point wiring for secondary light point with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling, complete with earth continuity and necessary connection with primary light with accessories erected on Metal / PVC box covered with 3 mm thick PC(Polycarbonet) / Acrylic sheet for open / concealed wiring. with necessary Lamp holder / ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories	89.00	Pt	0.00	0.00
162	Point wiring for Two Way Controlled Light Point with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (green) both are of .ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling ,complete with 6A Modular type switches and following type of accessories erected on PVC / Metallic box, single mounting base frame covered with textured / metallic front plate modules erected on / in wall / ceiling as per pipe erected. with necessary batten/angle holder or ceiling rose or H.D.Connector as directed CATIII	15.00	Pt	0.00	0.00
163	Point wiring for FAN with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (Green) both are of .ISI marked 1.1 KV Grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling complete with 6A Modular type switch and hum free EME four or more step type electronic fan regulator with separately mounted and accessories with earth continuity of following type erected on PVC / Metallic box, single mounting base frame covered with textured/metallic front plate modules erected on / in wall / ceiling as per pipe erected. with necessary ceiling rose / H.D.Connector as directed. (a) with medium class Rigid PVC pipe and accessories.CAT III	6.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
164	Providing following type of Modular Type Accessories mounted with PVC / metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate , modules erected with necessary connections as per site situation directed by Engineer In charge. (23)USB Charger with output of 5 V DC,2.1 A with inbuilt surge protection. Cat-III	3.00	Ea	0.00	0.00
165	Point wiring for Looped Plug with 6A Modular type switch & 5 pin socket erected on PVC / Metallic box, single mounting base frame covered with textured / metallic front plate modules erected on / in wall / ceiling with following type accessories. CAT III	10.00	Nos	0.00	0.00
166	Point wiring for Individual Plug with & earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of to be erected concealed in / on surface of wall / ceiling complete with Modular type switch & 5 pin Plug erected on PVC / Metallic box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories. For 6A Plug with 2-1.5 sq.mm Cu. Wire with medium class Rigid PVC pipe and accessories CAT III	30.00	Pt	0.00	0.00
167	Point wiring for Individual Plug with & earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of to be erected concealed in / on surface of wall / ceiling complete with Modular type switch & 5 pin Plug erected on PVC / Metallic box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories.[III] For 16A Plug with 2-2.5 sq.mm Cu. Wire (a) with medium class Rigid PVC pipe and accessories.CAT-III	4.00	Pt	0.00	0.00
168	Providing & erecting Switch board for Computer or electric apparatus consisting of following items in single board erected on PVC / Metal board with 3 mm thick PC (Polycarbonate) / Acrylic sheet erected as directed for [B] modular type accessories 1 no. 6A/16A universal plug-switch combined. CATIII 3 nos. 6A Switch 3 nos. 6A 5 pin Plug	11.00	Ea	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
169	Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling, with 1.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size (a) with medium class Rigid PVC pipe and accessories (a) 2 wire 1.5 sq. mm	2300.00	Mtr	0.00	0.00
170	Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected concealed in /flushed on wall/ceiling, with 1.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size (a) with medium class Rigid PVC pipe and accessories (B) 2 wire 2.5 sq. mm	1000.00	Mtr	0.00	0.00
171	Mains with 1.1 KV grade FRLS PVC insulated ISI marked stranded Copper conductor wire in following type of pipe to be erected in / on wall / ceiling with 2.5 sq. mm copper conductor FRLS PVC insulated stranded wire of green colour for earth continuity of following size. (a) with medium class Rigid PVC pipe and accessories (A) 2 wire 4 sq. mm	200.00	Mtr	0.00	0.00
172	Supply, Installation, Testing and Commissioning of suitable sweep, BEE 5 Star rated, Ceiling fan with Brush Less Direct Current (BLDC) permanent ferrite magnet Motor, class of insulation: B, Rust free 3 nos. Aluminium blades, 2 nos. canopies, shackle kit with earthing provision, copper winding, Power factor not < 0.9, Service Value (CMM/W) minimum 6.85, Air delivery minimum 215 CMM, 350 RPM, 230v (tolerance as per IS : 374-2019), THD < 10%, with remote unit for Speed Control and all remaining accessories including safety pin, nut bolts, washers, temperature rise = 75 degree C (Max.), suitable for 140 to 285 Voltage and rectifier circuit with surge, over current and overload protection , 50 Hz, Single phase AC Supply, earthing etc. Complete as required.[Make shall be approved by Engineer in Charge] (B) 1200 mm Sweep (48")	5.00	Nos	0.00	0.00
173	Providing 2.5mm.thick laminated acrylic sheet to cover the fan hook or Fan box.	5.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
174	Supplying and erecting 19 / 20 mm. nominal bore Medium Class M.S. Pipe down rod erected duly painted for fan complete with necessary 24/ 0.20, 3 core flexible wire with earthing.	5.00	Mtr	0.00	0.00
175	Supplying & erecting fan hook box of 10 mm M.S. round bar bounded to the RCC bars up to 50mm length each side and pierced through a 16 Gauge M.S. box / Heavy Duty PVC box complete erected concealed in Ceiling with necessary finishing.	5.00	Nos	0.00	0.00
176	Supplying & erecting approved make low noise decorative Exhaust fan having size 200mm with 1350 RPM with square frame ABS body with inbuilt lowers & square frame.	3.00	Nos	0.00	0.00
177	Supply Installation Testing Commissioning of Indoor deep Recessed Round downlight 18-21W Recess Mounted Round backlit downlighter with below features 1. Pressure die cast Aluminum alloy housing for better thermal conductivity. 2. PS diffuser for optimum light transmission. Round Version. 3. Efficacy of Fixture more then or equal to 85 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80 High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 5. LED life of more then 35000 Hrs @ L70. Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva	37.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
178	<p>Supply, Supervision during installation, testing & commissioning of Round ceiling recessed luminaire, the fixed Led down light made of aluminium injected body. Main optics in shiny anodised aluminium with a glass or plastic diffuser element, depending on the version. The LED modules installed on the LED Array versions have cutting-edge technology that permits a lower average temperature in the electronics. antiglare Powder coated white painted antiglare reflector, suitable size of heat sink to be integrated with in the fixture for better performance, system delivered lumen output should not be less than 1045 lumen, the power consumption should not be more than 13W-15W, Mac Adam step 2-3 LED, 50° beam angle with tolerance of ±10 degree, CRI ≥90, UGR ≤10-≤20, CCT 4000K, L80-B50-50000h@ Ta 25°C, remote LED DALI driver, complete product should be minimum IP54, the physical dimensions of the fixture should not be more than (Dia)80mm X (H)95mm., Luminaire Finish : Matt White Approved Make :ERCO, Flos, Castaldi, BEGA, Simes</p>	42.00	Nos	0.00	0.00
179	<p>Supply, Supervision during installation, testing & commissioning of Ceiling Recessed Rectangular shaped fixed linear Led Downlight, Housing made of aluminium profile, designed as heat sink, with connection cable L 500mm. Mounting frame: polymer, Trim Finish white (RAL9002) with black louver. Fixing springs for ceiling thicknesses of 1-40mm. Includes DALI control gear. with 0.1%-100% dimming range, 4-pole terminal block. LED module: high-power LEDs on metal-core PCB with 1.5 SDCM, CRI 82, L90/B10 ≤50000h, L90 ≤100000h, failure rate 0.1% ≤50000h, Cut-off angle 30 °. Protection Class II Weight 1.38kg. System wattage should not be more than 29W, Led 24W 3300 lumens, delivered 2603 lumens, Optics should not be more than 60 ° wide flood, 4000K, IP20, the physical dimension of the fixture should not be more than (L)390mm X (W)62mm X (H)100mm Approved Make :ERCO, Flos, Castaldi, BEGA, Simes</p>	8.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
180	Supply, Supervision during installation, testing & commissioning of Ceiling Recessed adjustable led spotlight cum downlight, suitable for Interior lighting for embedded installation with high power LED technology light sources, in Dali versions. In an upper position it functions as a downlight, and in a lower position it functions as a swivelling projector. The optical body of the luminaire is manufactured in high pressure die-cast aluminium, finished in black or white powder paint. System wattage 18W, Led 1879 lumens, delivered 918 lumens, 4000K, IP20, CRI ≥90, UGR ≤10-≤20, CCT 4000K, L80-B50-50000h@ Ta 25°C, Dali dimmable drivers, 21 degree emission, Honeycomb louver, Elliptical lens louver, flood lens louver included for desired application. Dimension Ceiling Recessed Dia : 98mm X Spot Snoot Dia : 57mm X H : below ceiling 115mm, above ceiling 156mm Approved Make :ERCO, Flos, Castaldi, BEGA, Simes	29.00	Nos	0.00	0.00
181	Supply Installation Testing Commissioning of Indoor Office Lighting 7-9w Recess Mounted Tilttable Spotlight downlighter with below features 1.Pressure die cast Aluminum alloy housing for better thermal conductivity. 2. With COB with Lens of 36-40 degree 3. Efficacy of Fixture more then or equal to 85 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80, High efficiency driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 5. LED life of more then 35000 Hrs @ L70. REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) recess mounted Galaxy Pro COB 7w DL072381Y Approved makes : Philips,Havells,Lighting technologies, Wipro,Tisva	26.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
182	Supply Installation Testing Commissioning of Multipule lines of led strip with alumnum profile for backlighting the STRECH CEILING stone with a dotless effect and complete even lighting Remote driver to be kept for maintatinance purpose Should be around 90w-120w per square meter Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva	20.00	SQ. MTR	0.00	0.00
183	"Supplying, Installation, testing & erecting of 80-90w Indoor decorative Circular complete backlit type Lighting, Dia=1200 mm, H=70 mm Suspended profile with below features System wattage-80-90w, Luminous Flux of luminaire to be more than 90 lumens per watt, 4000 K, CRI >80, 230V, Direct Emission, Profile in high quality powder coated, Halogen free internal wiring, should haver Prismatic Diffuser for Homogenous Light distribution. Protection Class I, IP 40, .Fixture should be available in 600mm dia. Body color shall be as per architects choice, manufacturer shall provide powder coated fine finish as per Architects selected RAL code. Fixture could be suspended using MS/SS/aluminium rod with height as per site requirement Ref : Lighting technologies Geomet fullit 1200mm Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva	3.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
184	"Supply Installation Testing Commissioning of Chandelier light with below features Product with premium mitsubishi acrylic material Better ambience creation and illumination for the space Long life and highly durable product Premium aesthetics maintained for a long time Brilliant light effect. Gives a notion light getting emitted for curved acrylic edges Easy height adjustment Made from non-toxic materials Colour: Iron / Gold Power: 24 W, INTEGRAL LEDs, SMD 2835 Dimensions per hanging (Length X Width X Height): 500 mm x 500 mm x 15000 mm Ref : TISVA LIGHTING (USHA INTERNATIONAL LTD): SL24217K Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
185	<p>Supply, Installation, Testing & Commissioning of 2200-2400 mm 70-77 W Suspended luminaire with Housing: SINGLE PC Extruded aluminium housing fitted with metal end cap suitable for Up/Down light application.</p> <p>Diffuser: Easy fit opal acrylic diffuser provides smooth light distribution, LEDs: Mounted on MCPCB and connected in series parallel combination. 100lm/w , PF >=0.95 and THD <=10 % , Surge protection:- 2KV, IP20.</p> <p>Luminaire is available with different colour temperature: White (WH) : 4000K Driver: 1 no., Constant current output driver, operating range 150–275V AC supply voltages.</p> <p>Mounting type: Luminaire is suspended with the help of 2 nos., of suspension system. (1.5 mtr.Length) which comes along with luminaire.</p> <p>The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only)</p> <p>Dimmensions: Length (in mm):2400, Width (in mm):113, Height (in mm):18.</p> <p>Fixture Lighting Technologies Make:- ILEAN V3 70W UP/DOWN or Equalant in ENDO/LIGMAN</p> <p>Design of the fixture should be approved by the architect</p> <p>Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva</p>	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
186	"Supply Installation Testing Commissioning of Indoor recess mounted profile light 1200mm 23W-25w lighting fixture with below features Fixture output efficacy 2300-2600Lumens. Cut out required 60mm. Extruded Aluminium alloy Housing and polycarbonate diffuser profile for continous decorative illumination Anodised aluminium end caps firmly fixed on the aluminium extrusion Silver anodised finish for elegant look . Efficacy of Fixture >=100 Lumens/Watt suitable for self adhesive HARD PCD LED Strips with driver for Installation/ PCB Mounted solution Available only in PCB option. Should be 4 feet length High end Metallic driver for better life and performance. LED life of 50000 Hrs @ L70. IP20 Protection Luminaire performance & Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, Surge : IEC 61000-4-5, EMC : EN 55015. The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only) PF >=0.95 and THD <=5 % Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva	30.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
187	Supply, Supervision during installation, testing & commissioning of Ceiling Recessed Rectangular shaped fixed linear Diffused Led Downlight, suitable for Interior lighting, Housing made of extruded aluminium profile, diffuser made of Premium High Transmission Opal PMMA. High Quality Led with 3 Step MacAdam LED Life Time @ L70/B10 >50,000 hrs, System wattage should not be more than 40W, Led 34.3W, delivered 4295 lumens, IP20, the physical Lengths of the fixture should as per drawings, width should not be more than 75mm X (H)82mm Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva	58.00	Mtr	0.00	0.00
188	"Supplying, Installation, testing & erecting of Indoor Linear Lighting 34W-38w 1200MM Suspended profile with below features Extuded Aluminum alloy housing for better thermal conductivity. Powder coated using Nano technology for longer durability. PS diffuser for optimum light transmission or opiton of Lens Based profile for better task lighting. Option to be selected by Architect / Consultant Efficacy of Fixture 95 Lumens /watt Available with 5700K, 4000K & 3000K CCT. CRI>80 High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD LED life of 50000 Hrs @ L70. IP20 Protection Luminaire performance & Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, Surge : IEC 61000-4-5, EMC : EN 55015. Ref: Philips make :suspended profile 4ft Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva	5.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
189	<p>Supply Installation Testing Commissioning of Indoor cove mounted Heavy 18X18mm corner 45degree customized Extruded Aluminium alloy Housing and polycarbonate diffuser profile for continous decorative illumination</p> <p>Anodised aluminium end caps firmly fixed on the aluminium extrusion</p> <p>Silver anodised finish for elegant look . Efficacy of Fixture >=100 Lumens/Watt suitable for self adhesive Strips with driver.</p> <p>Wattage should be 14-17w/m Should have a dotless continuos effect. Should be operated using remote driver of 24V Dc kept at suitable locations for future maintainance.</p> <p>Quantity in metres</p> <p>REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) Lume series Strip light LSX20Y145S4</p> <p>Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva</p>	12.00	Mtr	0.00	0.00
190	<p>Supplying and erecting LED indoor fittings with LEDs of wattage 0.2 Watt to 0.5 Watt assembled on single MCPCB, with housing used as a heat sink shall be made of thick sheet Steel conforming to IS: 513/CRCA polyester powder coated and high U.V. & corrosion resistance with diffuser and/or Polycarbonate optics with company mark/name</p> <p>120 to 300 V,Power Factor more than 0.9, THD < 10 %,</p> <p>CCT 4000 K to 6500K, Uniformity ratio >0.7,</p> <p>Luminaire efficacy> 85 lumens/watt ,</p> <p>LED driver efficiency > 85 %</p> <p>CREE / OSRAM / PHILIPS Lumileds / NICHIA / SEOUL/Bridgelux(U.S.A.) make LED used for luminaire. (Each fitting required LM-79 & LM-80 Certificates)</p> <p>(A) Tube Light with integral/ non-integral driver</p> <p>(c)10-12 Watts, Surge - 4KV,IP-20 Cat-III</p>	10.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
191	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, Conforms to IS 8623-1 & 3, IEC 61439-1 & 3 without MCB to house appropriate nos. of MCBs.(The DBs should be used of same company of MCB to be used) suitable for. (A) single phase incoming and horizontal single phase outgoing. (iv) Single phase 12 way SS Double door	2.00	Each	0.00	0.00
192	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs N) Three phase 6 way SS Double door for horizontal single phase outgoing	1.00	Ea	0.00	0.00
193	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs N) Three phase 8 way SS Double door for horizontal single phase outgoing	2.00	Ea	0.00	0.00
194	providing and erecting Miniature circuit breaker single pole 6A to 25A suitable to operate on 240 V A.C. system and having breaking capacity 10 KA to be erected in existing box. confirming to IS 8828/1996 with ISI Mark Cat.III	68.00	EA	0.00	0.00
195	Providing & erecting 240 V MCB double pole switch for motor & inductive load (C Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (A) 6 to 32 Amp.	1.00	Ea	0.00	0.00
196	Providing & erecting 240 V MCB double pole switch for motor & inductive load (C Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (B) 40 Amp.	1.00	Ea	0.00	0.00
197	Providing & erecting 415 V MCB Four Pole for Motor & Inductive Load (C Curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity (a) 6 to 32 Amp. Cat.III	2.00	Ea	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
198	Providing & erecting 415 V MCB Four Pole for Motor & Inductive Load (C Curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity (b)40 Amp. Cat.III	1.00	Ea	0.00	0.00
199	Approved make ELCBs / RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed (i) 25 Amps.DP Cat. III	1.00	Ea	0.00	0.00
200	Approved make ELCBs / RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed (i) 40 Amps.DP Cat. III	7.00	Ea	0.00	0.00
Total Amount					0.00
E	Part-5				
201	Approved make ELCBs / RCCBs conforming to IS: 12640 and having sensitivity of 30 mA and Short Circuit withstand capacity of 6 KA and suitable for operation on single phase 240 V. having characteristic of quick action & tripping with all advance feature & do not incorporate any electronic component. for following Max. rating erected as directed (i) 63 Amps.DP Cat. III	6.00	Ea	0.00	0.00
202	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables (B) 3 1/2 core 35 Sq. mm (16 Sq. mm 1/2 core)	50.00	Mtr	0.00	0.00
203	Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables. A)4 core 16 Sq. mm	600.00	Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
204	Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables (B) 4 core 6 Sq. mm	100.00	Mtr	0.00	0.00
205	Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables C) 4 core 10 Sq. mm	50.00	Mtr	0.00	0.00
206	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Copper conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe at road crossing or floor of following size of cable. (C) 3 core 6 Sq. mm	70.00	MTR	0.00	0.00
207	Providing and, fixing heavy duty flange type brass double compression type cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables. (B) 3 & 1/2 core 35/50 Sq. mm	2.00	EA	0.00	0.00
208	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables.D) 2 to 4 core 16 Sq. mm	10.00	Ea	0.00	0.00
209	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables.(B) 2 to 4 core 6 Sq. mm	8.00	Ea	0.00	0.00
210	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables.C) 2 to 4 core 10 Sq. mm	2.00	Ea	0.00	0.00
211	Solder less crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (D) 35/50 Sq.mm.	8.00	Ea	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
212	Solderless crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (C) 16/25 Sq.mm.	40.00	Ea	0.00	0.00
213	Solderless crimping type Aluminium lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. B)10 Sq. mm	8.00	Ea	0.00	0.00
214	Solder less crimping type Copper lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (B) 6 Sq.mm	16.00	Ea	0.00	0.00
215	Solder less crimping type Copper lugs conforming to IS suitable for cable of following size evenly crimped with high pressure tool & connected to switchgear terminals with brass/cadmium plated nut bolts in an approved manner. (A) 1.5/2.5 to 6 Sq.mm	16.00	Ea	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
216	Providing & erecting weather proof, dust & vermin proof, floor mounted front operated indoor type cubical panel board having IP-64 protection made from 14 SWG thick CRC M.S. sheet for outer body & doors, 16 SWG thick CRC M.S. sheet for internal partitions with necessary supporting angles, flats including cutting, bending, drilling, welding, riveting with internal partitions & cable alley as per requirements & instruction of engineer-in-charge with erection of supplied switch gears, BUSBARS, with suitable size of inter connecting PVC copper wire / copper-aluminium strips, rubber grommets, rib, bakelite control fuses for measuring instruments, earth bus & earth bolts, foundation flange - bolts-base Plates, sufficient nos. of hinged doors, handles with locking arrangement and rubber gasket complete. The Panel shall be painted with epoxy powder coating. (The rates excludes the cost of switchgears, bus bars, inter connecting mains & Copper Aluminium strips, meters, Fuses etc. The dimension shall be measured excluding base beams) The panel shall be supplied with following approved manufacturers with following size. (A) The standard companies switch gear shall be used and only manufacturers at CPRI approved factory and shall be certified by that company whose switch gears are used after fabrication for beneficial use and having Logo on the Panel (ii) with 550 mm. Depth	6.00	SQMT	0.00	0.00
217	Supplying and erecting triple pole & neutral 440V/ 500V panel mounting Aluminium Busbars with four equal Nos. of bus having current density not more than 0.8 Amp. / sq.mm (Rated current / cross section area) duly wrapped with colour insulating tape for phase sequence of following current carrying capacity, erected with necessary bus bar supports /insulators, main cable socket to each busbar,erected in existing cubical panel with necessary connections. (C) Suitable for 300 Amp. Capacity	5.00	Ru Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
218	Supplying and erecting approved make panel mounting type Digital Voltmeter having 3 digits LED display, 0 to 750 AC Volts range erected on existing panel board with all connection, wiring etc .with manufacturers calibration certificate.	1.00	Each	0.00	0.00
219	Supplying and erecting approved make panel mounting type Digital Ammeter having 3 digits LED display, external CT operated, calibrated for 0 to 1000 Amps suitable to operate on 500 Volt AC , erected on existing panel board with all connection, wiring etc .with manufacturers calibration certificate.	1.00	Each	0.00	0.00
220	Supplying and erecting Ammeter / Voltmeter selector switch for 3 phase AC Supply 500 V on existing panel board with necessary connections.	1.00	Each	0.00	0.00
221	Providing & erecting L.T. Current Transformer with bar primary 50/5 to 1000/5 ratio 15 VA burden erected in existing CRCA box duly secured with insulating materials connected to the meter	6.00	Each	0.00	0.00
222	Supplying and erecting approved make set of indicator lamps of LED type lamp, lens cover, Bakelite holder complete erected with necessary connections.	6.00	Each	0.00	0.00
223	Providing , erecting , fabricating the M.S. structure as per requirement on site incorporating proper size of M.S. angles, flats, bars, channels, sections complete with cutting, welding, grinding & finishing duly painted with one coat of red oxide with erection on site as per direction of engineer in charge with necessary grouting, cementing, plastering & finishing complete.	50.00	Kg.	0.00	0.00
224	providing and erecting Approved make Four pole moulded case circuit breaker having breaking capacity ICU of 25 KA. at 415 V, having normal current rating up to 25 A to 100A. with Fixed thermal & magnetic release suitable to work on A.C. supply 50 c/s. with all internal connections & complete erected in existing 16 G.M.S. housing. ICS=100% of ICU only. Cat III	16.00	Each	0.00	0.00
225	Providing and erecting HOT deep Galvanised iron strip wire 8 to 16 SWG.	30.00	KG	0.00	0.00
226	Providing and erecting required size HOT deep Galvanised iron strip for earthing of H.T. , OCB/ ACB/ Transformer LT panel board, Motors etc. using proper clamp.	50.00	KG	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
227	Supplying and erecting approved make online Un-interruptible Power Supply system comprising flat cum-boost charger, static Inverter & sealed maintenance free SMF batteries. The charger having operating capacity for input 160-270V AC & inverter having output 230V,50 Hz Ac with 0.8 load power factor with battery, over/under voltage output with over load & short circuit protection equipment. The system housed in CRC sheet duly powder coated paint with following power backup.with MS painted batteries stand, 10% Overload capacity for momentary load.(D) 5 KVA 3 - phase with 1Hr Backup	1.00	EA	0.00	0.00
228	Providing and erecting ISI mark Medium class RIGID PVC PIPES of following size complete to be erected on/in wall or ceiling erected with necessary PVC fittings & Junction boxes fixed with adhesive solution & Clamps with following dia of pipes, in approved manner as directed (b) 25 mm	50.00	Mtr.	0.00	0.00
229	Providing and erecting ISI mark Medium class RIGID PVC PIPES of following size complete to be erected on/in wall or ceiling erected with necessary PVC fittings & Junction boxes fixed with adhesive solution & Clamps with following dia of pipes, in approved manner as directed (c) 32 mm	50.00	Mtr.	0.00	0.00
230	Supplying and laying UPVC cable trunking system comprising unplasticised polyvinyl, chloride rigid material with ignition free and flame proof confirming BS with necessary end caps Internal and external bend, flat bends, coupler, tee etc..All necessary accessories and measuring of following sizes (1) 75 mm x 50 mm trunking	50.00	RMT	0.00	0.00
231	(2) 100 mm x 50 mm trunking	25.00	RMT	0.00	0.00
232	Providing and fixing approved make Perforated C type cable tray. Made from pre- galvanized CR sheet steel. The cable tray should be bended as per IS 2062/1079 . with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..150 X 50 X 1.5 mm Thick	200.00	RMT	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
233	Providing and fixing approved make Perforated C type cable tray. Made from pre- galvanized CR sheet steel. The cable tray should be bended as per IS 2062/1079 . with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge.300 X 50 X 1.5 mm Thick	20.00	RMT	0.00	0.00
234	Providing and fixing approved make '90° Elbow' for Perforated C type cable tray. Made from pre galvanized CR sheet steel. The Junction should be bended as per IS 2062/1079. with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..(b)90° Elbow (3) 150 X 50 X 1.6 mm Thick 90° Elbow	2.00	EA	0.00	0.00
235	Providing and fixing approved make '90° Elbow' for Perforated C type cable tray. Made from pre galvanized CR sheet steel. The Junction should be bended as per IS 2062/1079. with coupler plate / Fish plate and GI hardware like nut - bolt and washers etc. erected on existing support as per Specification and as per instruction of engineer in charge..(b)90° Elbow (5)300 X 50 X 2.0 mm Thick 90° Elbow	2.00	EA	0.00	0.00
236	Supplying under floor pregalvanised corrosion proof rectangular sheet steel cable trunking of 1.6 mm thick having with stand point load up to 1.33 Ton & free from seepage of concrete of screed water with all accessories,Junction Box,Joins as required and demanded by engineer-incharge and laying/erecting as per OEM guidelines and as per instruction of engineer incharge having following size of dimensions and No of compartments (W x D x T) Cat-III.[10] 150mm x 38mm x 1.6mm with Three Compartments	50.00	Mtr	0.00	0.00
237	[12] 250mm x 38mm x 1.6mm with Three Compartments	15.00	Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
238	Supplying under floor pregalvanised corrosion proof rectangular sheet steel cable trunking Junction Box of 1.6 mm thick having with stand point load up to 1.33 Ton & free from seepage of concrete of screed water with all accessories, Joints as required and demanded by engineer-incharge and laying/erecting as per OEM guidelines and as per instruction of engineer incharge having following size of dimensions and No of compartments (W x D x T) Cat-III.[10] 200mm x 50mm x 1.6mm with Three Compartments	5.00	Mtr	0.00	0.00
239	[12] 300mm x 50mm x 1.6mm with Three Compartments	3.00	Mtr	0.00	0.00
240	[13] 400mm x 50mm x 1.6 mm with Three Compartments	1.00	Mtr	0.00	0.00
241	SITC of 4MP Fixed Lens Dome Type Camera, H.265 4MP IR Vandal Proof Dome N/W Camera, 2.8mm/3.6mm, 30M IR, Micro SD, DC12V/PoE, IP67/IK10, Basic IVA, 1 / 2.7" CMOS, 2560 × 1440, 0.01 Lux, F1.2, AGC ON; Defog, True day/night, Digital WDR, 3D DNR, HLC & BLC, Triple streams, Smart codec by ROI, Cyber Security, Basic intelligent video analytics, NDAA Compliance, UL, CE, FCC Certified	3.00	Nos.	0.00	0.00
242	SITC of 5 MP Motorised Varifocal Lens Bullet Camera - H.265 5MP IR Bullet N/W Camera, 25/30FPS, Motorised Varifocal 2.8-12mm, IR up to 70M, Micro SD support up to 128GB, DC12V/PoE, IP67/IK10, Basic IVA, 2 MP resolution (2592 × 1944), True day/night, Digital WDR, 3D DNR, HLC & BLC, Triple streams, Smart codec by ROI, Cyber Security, Intelligent video analytics, NDAA Compliance, UL, WEEE, REACH CE, FCC Certified, IK10 & IP67, Opp Temp - 30 °C to 60 °C, ONVIF S,G,T	5.00	Nos.	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
243	SITC of 32 Channel Network Video Recorder (NVR), Dual OS design, HDD Hot Swap with RAID support, N+1 hot spare configuration, Support 16CH@2MP, H.265/H.264 Video Compression, HDMI, VGA output, upto 8 SATA interface each with max 10 TB support and 1 eSATA, 16-ch synchronous playback at up to 1080p resolution, Gigabit Ethernet network interfaces, bandwidth 320 mbps, CE FCC, BIS, Operating Temp -10 deg to 50 deg C, USB and serial Interface, RAID supported	1.00	Nos.	0.00	0.00
244	SITC of Patch Panel Cat 6 UTP Keystone Type- 24 Port-Fully Loaded	1.00	Nos.	0.00	0.00
245	SITC of CAT6 UTP 24AWG PATCH CORD:1M,Plug 30U' Snag less	24.00	Nos.	0.00	0.00
246	SITC of Jack Cat 6 Keystone UTP	8.00	Nos.	0.00	0.00
247	SITC of 24 x 10/100/1000BASE-T PoE ports 4 x Gigabit RJ45/SFP Combo ports Advanced L2 switching and security features L2+ Static Routing Optional "standard mode" or "surveillance mode" management user interface 193 W PoE budget	1.00	Nos.	0.00	0.00
248	SITC of 43 Inch 500 NTS Brightness professional Display with Direct-Type LED, Viewing Angle : 178 Degree Verti, 178 Degree Hor. Operation 27x7, Native Resolution 3840 x 2160 (16:9) - UHD, 4 x USB (2 x 2.0, 1 x 2.0 internal, 1 x Type C), 0-40°C, ≤0.5 W, HTML 5 Browser Opera(4.9), Yes(internal) IEEE 802.11 a/b/g/n Dual WiFi certificated, BIS, YES CLASS A 3dB margin. (Including Five year free maintenance with guarantee)	1.00	Nos.	0.00	0.00
249	SITC of 6 TB Enterprise Harddisk	4.00	Nos.	0.00	0.00
250	SITC of Work Station with i5 Intel processor with minimum 500Gb HDD, 4 GB RAM, 21" TFT Monitor, with Keyboard and Mouse	1.00	Nos.	0.00	0.00
Total Amount					0.00
F	Part-6				
251	SITC of 4 Pair LSZH CAT6 UTP Cable	660.00	Mtr.	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
252	SITC of 9U/600 Rack/ Welded/WM/Off White,Glass Door/9U/WM/Gray,Server /IT Rack mount power distribution unit, 1Ph, 230V, 16A, 50/60Hz, 2U standard with 6 X Indian Round Pin 5/15A, Inlet Plug type 16A Indian Round Pin, 16A MCB - PDU Rating 3.6KVA/Side feed-1.5Mt/ Black,Horz. Cable Organiser/1U/Loop,Cantilever Shelf/Type2/1U/Off White,Mounting Hardware-CR (Pack of 20),ITE / Server Rack Air Circulation module/90CFM	1.00	Nos.	0.00	0.00
253	SITC of Conduit Box for CCTV	8.00	Nos.	0.00	0.00
254	SITC of Addressable Combined Fire Alarm and Emergency Lighting Control Panel features 4 loop complete with Network Card. The Panel shall be compliant with EN54-2 and EN54-4. Each loop shall have a capacity of 127 Fire Alarm and Emergency Lighting devices, Each loop current rated at 1 AMP. The Panel shall have 240 x 64 pixel graphic LCD display. The Panel must have 4 inbuilt sounder circuits, 4 programmable inputs, 4 programmable relays, 4.5Amps @ 33 VAC power supply, 20 character location text message. The Panel shall have ability to store 500 events. The panel shall have the capability to charge battery of up to 60 Ah. The panel shall have IP30 protection cabinet. Approved by EN54	1.00	Nos.	0.00	0.00
255	SITC of Analogue Addressable Smoke Sensor which is fully compatible with Analogue Addressable Protocol, having removable high performance chamber with Twin fire LED's allow 360 degree viewing, User selectable sensitivity modes 1% to 4.5% obs/m, Incorporate Optical elements, lock mechanism (sensor to base), Electronically addressed, Pulsing/non-pulsing controlled from panel. Approved by LPCB & VdS.	18.00	Nos.	0.00	0.00
256	SITC of IP67 Rated Waterproof Addressable Multi-Heat Sensor which can be used externally and is supplied with its own fixing base which is used to fix the sensor. Flying leads from the sensor connect directly to the loop via waterproof connectors. Approved by LPCB & Vds.	1.00	Nos.	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
257	Supply, Installation, Testing and Commissioning of infra-red beam smoke detectors With ground Level adjust controller, Combined transmitter and receiver unit in one discrete unit. The detector shall have Range 5 to 120 metres With Light cancellation technology, Detector Should have Optional transmitter powering from controller only Approved by EN54:12, UL268 and VdS.	0.00	Nos.	0.00	0.00
258	SITC of Analogue Addressable Manual Call Point with Integral Short Circuit Isolator, Analogue Addressable Protocol having, Bi-coloured status LED (red for alarm, amber for (short-circuit), Non-frangible element fitted as standard (conforms to EN54), pulsing/non-pulsing can selectable via panel, Electronically addressed, Approved by LPCB.	2.00	Nos.	0.00	0.00
259	SITC of Intelligent Loop Powered Wall Sounder Beacon, Variable Sound Output 90 ~ 102 dB(A) (± 2 dB(A)) output at 1 metre, High Intensity LED technology, 51 User-Selectable Tones (all tones EN54-3 compatible). Approved by LPCB & VdS	1.00	Nos.	0.00	0.00
260	SITC of Analogue Addressable Single Input Module. which Includes a single monitored input, flying leads for easy installation. Electronically addressed, Approved by LPCB & Vds.	1.00	Nos.	0.00	0.00
261	SITC of Analogue Addressable Single Output Module . which Includes a single output, flying leads for easy installation. Electronically addressed, Approved by LPCB & Vds.	1.00	Nos.	0.00	0.00
262	Supply,Instllation,Testing and Commissioning of Addressable Exit Signage visible from 20 mtrs. with integral battery capacity of 3 hrs and bicoloured LED status indicator. Exit signage shall be comply with ISO 3864/ISO7010	4.00	Nos.	0.00	0.00
263	Supply, Installation, Testing and Commissioning of 2 Core 1.5 Sq.mm FRLS Cable (Red Color)	500.00	Mtrs.	0.00	0.00
264	SITC of O. F.Cable 06F Outdoor - Armoured Unitube SM - HDPE Sheath	150.00	Mtr.	0.00	0.00
265	SITC of LIU 24 PORT Rack Mount - Loaded (LC) SM	4.00	Nos	0.00	0.00
266	SITC of PATCH CORD LC-LC SM DUPLEX LENGTH- 3m	6.00	Nos	0.00	0.00
267	SITC of 42 U 550*600*1000 Rack	1.00	Nos	0.00	0.00
268	SITC of Patch Panel Cat 6 UTP Keystone Type- 24 Port-Fully Loaded	4.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
269	SITC of CAT6 UTP 24AWG PATCH CORD:1M,Plug 30U' Snag less	74.00	Nos	0.00	0.00
270	SITC of CAT6 UTP 24AWG PATCH CORD:2M,Plug 30U' Snag less	10.00	Nos	0.00	0.00
271	SITC of CAT6 UTP 23AWG Solid: Per Meter	3 355.00	Mtr.	0.00	0.00
272	SITC of Jack Cat 6 Keystone UTP	49.00	Nos	0.00	0.00
273	SITC of Face Plate - Single (Keystone Jack,square)	49.00	Nos	0.00	0.00
274	SITC of Back Box	49.00	Nos	0.00	0.00
275	SITC of 25MM PVC Conduit with Accessories	1 200.00	Mtr	0.00	0.00
276	SITC of 32mm PVC Flexible Pipe with Accessories	100.00	Mtr	0.00	0.00
277	SITC of 25mm HDPE Pipe with Accessories	120.00	Mtr	0.00	0.00
278	SITC of 32mm GI Flexible Pipe with Accessories	25.00	Mtr	0.00	0.00
279	SITC of 50MM PVC Flexible Pipe with Accessories	75.00	Mtr	0.00	0.00
280	SITC of 24 x 10/100/1000 Base-T Switch with additional 4 x 10G SFP+ Ports, Rack-mountable, It should support stacking, should support features like static routing, RIP, DHCP, ACL, QoS, VLANs, LAGs, LACP, and port mirroring, Switch's Operating System should be tested under Common Criteria Certification. and complying to details technical specs in attacehd sheet	2.00	Nos	0.00	0.00
281	SITC of 24 x 10/100/1000 Base-T PoE+ Switch with additional 4 x 10G SFP+ Ports, switch should provide 370W of PoE Power, Rack-mountable, It should support stacking, should support features like static routing, RIP, DHCP, ACL, QoS, VLANs, LAGs, LACP, and port mirroring, Switch's Operating System should be tested under Common Criteria Certification. and complying to details technical specs in attacehd sheet	1.00	Nos	0.00	0.00
282	SITC of Maximum distance of up to 10 km Hot-pluggable Single-mode fiber 10GBASE-LX Duplex Fiber module with LC connector	6.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
283	SITC of Next generation enterprise Wi-Fi 6 (802.11ax) access points, It should be resilient, secure, and intelligent. Comes with Embedded Wireless Controller, Minimum 4 nos of 2.4 GHz 2 dBi/5 GHz 4 dBi Dipole Extranal Antenna, AP's should be tested under Common Criteria Certification. and complying to details technical specs in attacehd sheet	10.00	Nos	0.00	0.00
284	SITC Of 98 NON INTRACTIVE, Resolution 3840 x 2160 (UHD-4K),Brightness 350 nit,Contrast ratio 1200:1,Panel type Non-glare, IP Rating IP5X,Connectivity HDMI 2.0(2), USB2.0(2),Dvi-D,Display Port,Stereo Mini Jack, Ext: RS232C(in/out), RJ45, Soc SSSP 6.0 - CM CABIN	1.00	Nos	0.00	0.00
285	SITC Of 55 inch Resolution 3840 x 2160(UHD-4K),PQI (Picture Quality Index) 2200,Contrast ratio: Mega Contrast,Panel type:Non-glare,AirSlim:Yes,Connectivity:WiFi, Bluetooth, HDMI(3), HDCP1.4/2.2, USB(1), RJ45,Web browser, Youtube,3 Side Bezel Less - CM ANTE ROOM	1.00	Nos	0.00	0.00
286	SITC Of 75 inch Resolution 3840 x 2160 (UHD-4K),Brightness 300 nit,Contrast ratio 4000:1,Panel type Direct LED BLU, IP Rating IP5X,Connectivity HDMI 2.0(2), HDCP 2.2, Stereo Mini Jack, USB 2.0,Stereo Mini Jack, Ext: RS232C(in/out), RJ45,3 Side Bezel Less - BREAKOUT AND LOUNGE AREA	2.00	Nos	0.00	0.00
287	SITC of Cables & Conenctor for CM cabin with hdmi wall plate	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
288	SITC OF 98 INCH ARM Cortex-A73*2 + Cortex-A53*2 1.5GHz, 4GB DDR4 or better, storage-32GB or better, TFT LCD Module with DLED Backlight, 2171.85 (H) x 1232.35 (V) (97.52" diagonal), 16:09:00, UHD 3840x2160 (Pixels), 1.07B colors (10bit), 20 points touch, 10 points writing, 1.07B colors (10bit), 350 nits or better, OPS:-01, 5000:1 (DCR)8ms, H = 178, V = 178 typ, 30,000 Hours (Min), Hardness: 9H, Anti-glare coating, USB2.0: Front x2, Rear x1 (SmartPort™ for all), Slim - Landscape, IR Recognition, 32767 x 32767, HDMI:-2.0-2, RGB / VGA:-01, Audio:-01 (PC audio in), RS232:-01, OUTPUT Audio:x1 (Earphone out), SPDIF:1 (optical), RJ45:-01, USB3.0: Front x1, Rear x3 (SmartPort™ for Rear x3), x2, for touch, spk-10W x 2 + 15W x 1 subwoofers, HDMI (3840 x 2160), Android 8, All-in-one USB port: - Front "SmartPort™ USB" to all channels., required for window /android /mac, 10M/100M/ for Android, 10M/100M/1000M for slot-in PC, Wall Mount (VESA®): - yes, 0°C to 40°C, 10% ~ 90% RH non-condensing, cTUVus, FCC, ES8, EPEAT, EMC/CE, CB, RoHS & DOC, REACH, WEEE, ErP, EAC, UKrSEPRO, RCM, BSMI, 1. Power cable (3 meters). VSAx1, VSEx2, VSIx4 2. Remote control 3. USB cable (3 meters) 4. Touching pen x 2 5. Quick Start Guide 6. RS232	1.00	Nos	0.00	0.00
289	SITC of Tiled wall Mounting Bracket	1.00	Nos	0.00	0.00
290	Supply, Installation Testing & Commissioning of 15.6" Touch display, Easily extend your content from laptops and mobile devices, Built-in 6H hardness screen, it's resistant to surface damage, even if accidentally scratched by your keys, Avoid damage during carry, the detachable magnetic cover is easy to put on. Used as a mat, its anti-slip surface prevents the monitor from sliding away, Up to 60 Degree Tilt, Temperature: 32°F to 104°F (0°C to 40°C) Humidity (non-condensing): 20% to 90%	1.00	Nos	0.00	0.00
291	Supply, Installation Testing & Commissioning of 30/25fps and Full HD @ 60fps PTZ camera, minimum 30X Optical Zoom, min 200 Presets, Ethernet Out, HDMI Out, 3G-SDI Out, Audio In, IP/RS232/422 Controls, -170° ~ +170° Panning angle, -30° ~ +90° Tilting angle , Should support PoE+. Should be CE, ROHS, BIS and FCC Certified. WITH 3 YEAR WARRANTY	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
292	Supply, Installation Testing & Commissioning of Wireless and Wired Presentation and Collaboration Device with Airplay, Miracast Technology. 6 user can present simultaneously on single display mode and upto 12 user in dual display mode. 1X HDMI Input for Hardwiring Input, 1X HDMI Output, 1X Display Port OUT, 1x Mic IN and 1x Line Out Ports, 3x USB 3.0 and 2x USB 2.0 Ports, additionally have 128GB SSD for Storage, 8 GB RAM with Windows Platform. Login using conventional Wi-Fi or LAN connections. Powerful security features: user authentication, 1024-bit encryption, dynamic room code. Supports Windows laptops and MAC, as well as iOS and Android mobile operating systems. High quality video streaming, supports 4K@60 (using the VIA app). Multimedia features: connect & collaborate. Third Party VC Install Support, Should have Via versa feature to access professional grade camera wirelessly.	1.00	Nos	0.00	0.00
293	Supplying, installation, testing and commissioning of 4K@60 HDBaseT Receiver (1X HDBaseT IN, 1X HDMI OUT), Should have built-in IR and RS-232 port for controlling the connected display or an external control port, support cable length minimum 70 Mtr. at 1080P and 40 Mtr. at 4K@60Hz.	4.00	Nos	0.00	0.00
294	Supplying, installation, testing and commissioning of 4X4 matrix switcher that transmits video, audio, Ethernet, RS-232 and IR signals over extended distances. Should have 4 HDMI Inputs, 4 HDBaseT Outputs with 2 HDMI Simultaneous Output, should have max resolution support of 4K@60Hz, Should Support HDBaseT Range — Up to 130m (430ft) at normal mode (2K), up to 100m at normal mode (4K); up to 180m (590ft) ultra mode (1080p @60Hz @24bpp) when using BC-UNIKAT cables.	1.00	Nos	0.00	0.00
295	Supplying, installation, testing and commissioning of Pop-Up Box / Cable cubby. Includes a Universal power outlet X 2 Nos, HDMI Port X 1nos, RJ-45 X 2 Nos., 1 Double Power Socket Slot, 6 Insert Slots (Includes 4 Blank & 2 Cable Pass-Through Inserts). TBUS Dual Power Socket - Universal, Wall Plate Insert - Dual RJ-45 - Black, W-HDMI Wall Plate Insert - Black, TBUS AC Power Cord - Right-Angle India 6ft 250V AC.	3.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
296	Supply, Installation, Testing and Commissioning of UHF wireless microphone system, sound clarity, impeccable performance, make the er 58 series one of the most popular wireless microphone system currently available. With head mic and inbuilt battery.	1.00	Nos	0.00	0.00
297	Supply, Installation, Testing and Commissioning of Wall or ceiling Mounted 2 way Passive Speaker ,having power 40W RMS, LF Transducer 6.5" Woofer, HF Transducer 1" Tweeter and frequency range of 80 Hz - 20 KHz.	4.00	Pairs	0.00	0.00
298	Supply Installation Testing & Commissioning of Digital Signal Processor with 1 Unbalanced 3.5mm input, 4 mic/Line input with two AEC support and 2 outputs. should have additional 2 HDMI Inputs and 1 HDMI output with 4K@60HZ (4:4:4). Supports HDMI Audio De-Embedding. Internal processing should be on 24-bit, USB interface port for PC configuration software and processing audio through laptop, RS-232 interface, RJ-45 interface etc.	1.00	Nos	0.00	0.00
299	Supply, Installation, Testing & Commissioning of Audio Server 240w with designed output as per selected speaker, minimum 1X balanced input, 1X Unbalanced Input, Frequency response 50 Hz - 22 kHz, DSP features: Per channel presets for high-pass filter, parametric EQ, multi-band compressor, and look-ahead limiter.	1.00	Nos	0.00	0.00
300	Supply, Installation, Testing and Commissioning of Room Controller with BIDIRECTIONAL PORTS, 4 RS-232 serial on 3-pin terminal blocks, 4 GPI/O on 2-pin terminal blocks, 1 Ethernet on a RJ-45 connector with POE , 1 micro-USB connector for sending P3K commands and performing a firmware upgrade, INPUTS- 1 built-in IR sensor (for learning) OUTPUT-4 IR out and 4 relays on 2-pin terminal block connectors INDICATORS- LED indicator for each port and function PROCESSOR SPEED -1GHz MEMORY -512MB RAM, 4GB Flash POWER CONSUMPTION -100-240V AC, 200mA with all accessories	1.00	Nos	0.00	0.00
Total Amount					0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
G	Part-7				
301	Supply, Installation, Testing & Commissioning of 7" Table or Wall mount Touch Panel with 10 points, 2-finger gesture support. Supports Advanced Android Operating System with rich Kramer and market-available applications from cloud/store offerings, such as K-Touch Control and EventBoard Scheduling applications. Support Kramer Aware app on the touch panel to control devices connected to compatible products. Should Support WIFI 802.11 b/g/n/ac as well as POE Connectivity, Should have 2GB of RAM and 16GB ROM with Quad Core CPU. Should have Superior IPS 1280x800 hi-resolution screen with ±80° horizontal and vertical wide viewing angles, built-in lighting sensor for auto-adaptable brightness, Should Support Bluetooth 4.0 Connectivity, Should have Versatile Powering Option PoE, PSU and battery. Should have 2x1W Speakers. Firmware Update via USB Port.	1.00	Nos	0.00	0.00
302	Supply, Installation, Testing and Commissioning of Smart controller to Seamless connectivity & smart control of all devices through touch circuit display, touch glass panel and required all retrofit module. system has along with software & own app to customize control of all IR/Zwave tech devices in entire conference room like dimmable light, AC, Display, Curtain in individual or group. complete as per approved by consultant.	1.00	Nos	0.00	0.00
303	Supply, Installation, Testing and Commissioning of Smart customized programmable touch panel as per electrical circuit complete as per approved by consultant	2.00	Nos	0.00	0.00
304	Supply, Installation, Testing and Commissioning of Ethernet & WiFi Access Point Connectivity, 2/3 node, RGBW, Light/Fan/Plug type retrofit module as per electrical circuit 8 Port High Voltage Relay with RS-232 Control	2.00	Nos	0.00	0.00
305	Supply, Installation Testing & Commissioning of System Rack along with require accessories as per site requirement complete as per approve by consultant	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
306	Supply, Installation Testing & Commissioning of high-performance, HDMI cable.It supports signals up to 4K@60Hz (4:4:4), Deep Color, x.v.Color™, Lip Sync, 7.1 PCM, Dolby TrueHD, DTS-HD, CEC., 24K gold-plated connectors resist corrosion, Provides 15lbs of restraining force for a non-slip connection.	3.00	Nos	0.00	0.00
307	Supply, Installation Testing & Commissioning , high-performance type C to HDMI cable/ Convertor .It supports signals up to 4K@60Hz (4:4:4), Deep Color, x.v.Color™, Lip Sync, 7.1 PCM, Dolby TrueHD, DTS-HD, CEC., 24K gold-plated connectors resist corrosion, Provides 15lbs of restraining force for a non-slip connection	1.00	Nos	0.00	0.00
308	Supply, Laying, Testing and Commissioning of Active High Speed HDMI Cable long length. ,HDMI 2.0 Cable Male to Male, support Deep Color, 4K 4096 x 2160 @60Hz; 3840 x 2160 @ 60Hz 4:4:0, Minimum conductor gauge - 30AWG, gold Plating as per site condition and approved by consultant	4.00	Nos	0.00	0.00
309	Supply, Installation Testing & Commissioning , high-performance Active USB 3.0 A to A Male-Female Extender Cable .High Quality Construction 2 pair 24AWG + 1 pair 26AWG + 2 wires 22AWG + 2 drain wires 24AWG.USB 3.0 Super Speed (5Gbps) Standard Compliant with USB 3.0 .No External Power Required Pulls power from the USB source device. Also it should include needful extension cables for system to work efficiently	4.00	Nos	0.00	0.00
310	Supply, Laying, Testing and Commissioning of Cables & Connectors including Two 20 AWG conductors Audio/Mono Cable with Drain Wire High performance, 16 AWG conductors non-plenum, for High performance cable, RJ 45 Connector for 24AWG to 23AWG twisted pair cables with insulation diameter of 1.40mm to 1.50mm. and other needful cables for entire solution to work & approved by consultants and OEM Brands. 100 mtr	100.00	Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
311	Supply, Laying of Shielded Twisted Pair (STP) 4Pairs 24 AWG Cable with connector. CAT6A U/FTP Video & LAN Bulk Cable — Low Smoke & Halogen Free 100 Mtr.	200.00	Mtr	0.00	0.00
312	SITC of 24 x 10/100/1000BASE-T ports 4 x Gigabit RJ45/SFP Combo ports Advanced L2 switching and security features L2+ Static Routing Optional "standard mode" or "surveillance mode" management user interface	1.00	Nos	0.00	0.00
313	SITC of CAT6 UTP 23AWG PATCH CORD:1M,Plug 30U' Snag less	10.00	Nos	0.00	0.00
314	Supply, Installation, testing & commisioning of high performance wireless connectivity for govt. office. and supports dual band concurrent WiFi 6 operations at 2.4GHz and 5GHz with a combined throughput of 1.8Gbps (600Mbps at 2.4GHz and 1200Mbps at 5GHz). WiFi 6 Access Point provides standalone configuration with easy setup for a reliable, WiFi 6 802.11ax high performance	1.00	Nos	0.00	0.00
315	SITC of 4x4 USB 3.2 Gen 1 Industrial Hub Switch Enables four computers to share USB peripheral up to four devices ,USB 3.2 Gen 1 compatibility with maximum data transfer rates up to 5 Gbps , Multiplatform support — Windows, Mac and Linux , Displays port focus via LED indicators , Metal mechanical cassis with wall mountable design, Supports aftermarket USB M2 screw locking cable, Supports port selection via remote controller or RS-422 / RS-485 link through 5-pin terminal block, Supports hot plugging , Supports DC 9 - 24V power input through terminal block , Supports USB BC 1.2 and over current protection ,Power on detection - The computer focus automatically switches to a newly plugged-in or powered-on computer - The computer focus automatically switches to port 1 when the focused computer is unplugged or powered-off , Firmware upgradable ,Supports either of the following, power supplies	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
316	SITC of The condenser microphone design is for a through desk/ceiling/panel mount boundary layer type with a cardioid polar pattern. The microphone is made of a robust high quality brass construction with a low profile robust brass top. It is terminated with a male 3 Pin XLR. The microphone is powered by a 9 to 48 volts phantom power adaptor. The Phantom Power Adaptor includes filters which will eliminate all cellular frequencies (GSM/2G, 3G, 4G & 5G). Frequency response 50 Hz to 18 KHz; Sensitivity -37dB +/- 3dB @ 1Khz (0dB=1V/Pa) Impedance 200 Ohms. Total harmonic distortion (THD) at an operating level of 120dB is no greater than 1%. Also included are rubber shock mounts to minimize the transfer of mechanical noise from table, ceiling or panel. Length 90.00mm (3.55") Table Cardioid Condenser Boundary Layer Microphone with Frequency Response	11.00	Nos	0.00	0.00
317	SITC of extension cable between the units or between the controller and unit -10 meter long	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
318	Supply, Installation, Testing & Commissioning of Each input supports 12-band parametric equalizer (PEQ), signal generator, compressor, expander, ducker, and 48 V phantom power • Each output supports 31-band graphic equalizer (GEO), audio crossover, delayer, limiter • Up to 16 settings can be preset • DSP Configurator software tool for managing all audio operations, minimum 1X balanced input, 1X Unbalanced Input, Frequency response 50 Hz - 22 kHz, DSP features: Per channel presets for high-pass filter, parametric EQ, multi-band compressor, and look-ahead limiter. 16 sets of presets, each preset working independently. Independent adaptive feedback inhibition per channel. Automatically detects feedback points and automatically suppresses them. ADI SHARC 21489 processor • Upto 20 balanced microphone or line level inputs on Terminal Block connectors • Upto 20 balanced line level outputs on Terminal Block connectors • Needful GPI/O multi-function ports on Terminal Block connectors • Supports adaptive echo cancellation (AEC), adaptive feedback control (AFC), automatic gain control (AGC), automatic mixture control (AMC), automatic noise suppression (ANS)	2.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
319	SITC Of 86 INCH ARM Cortex-A73*2 + Cortex-A53*2 1.5GHz, 3GB DDR4 or better, storage-32GB or better, TFT LCD Module with DLED Backlight, 1895.04 (H) x 1065.96 (V) (85.6" diagonal), 16:09:00, UHD 3840x2160 (Pixels), 1.07B colors (10bit), 20 points touch, 10 points writing, 1.07B colors (10bit), 350 nits or better, OPS:-01, 5000:1 (DCR)8ms, H = 178, V = 178 typ, 30,000 Hours (Min), Hardness: 9H, Anti-glare coating, USB2.0: Front x2, Rear x1 (SmartPort™ for all), Slim - Landscape, IR Recognition, 32767 x 32767, HDMI:-2.0-2, RGB / VGA:-01, Audio:-01 (PC audio in), RS232:-01, OUTPUT Audio:x1 (Earphone out), SPDIF:1 (optical), RJ45:-01, USB3.0: Front x1, Rear x3 (SmartPort™ for Rear x3), x2, for touch, spk-10W x 2 + 15W x 1 subwoofers, TOP CAMERA PLATE - yes, HDMI (3840 x 2160), Android 8, All-in-one USB port: - Front "SmartPort™ USB" to all channels., required for window /android /mac, 10M/100M/ for Android, 10M/100M/1000M for slot-in PC, Wall Mount (VESA®): - yes, 0°C to 40°C, 10% ~ 90% RH non-condensing, cTUVus, FCC, ES8, EPEAT, EMC/CE, CB, RoHS & DOC, REACH, WEEE, ErP, EAC, UKrSEPRO, RCM, BSMI, 1. Power cable (3 meters). VSAx1, VSEx2, VSIx4 2. Remote control 3. USB cable (3 meters) 4. Touching pen x 2 5. Quick Start Guide 6. RS232 adapter 7. Clamp x 5 8. Plate 9. Screw x 8 10. HDMI cable 3M - APPROVED MAKE :- Foxcon, Christie, Benq, Viewsonic,	1.00	Nos	0.00	0.00
320	SITC of Tiled wall Mounting Bracket	1.00	Nos	0.00	0.00
321	Supply, Installation, Testing and Commissioning of Wall or ceiling Mounted 2 way Passive Speaker ,having power 40W RMS, LF Transducer 6.5" Woofer, HF Transducer 1" Tweeter and frequency range of 80 Hz - 20 KHz.	3.00	Pairs	0.00	0.00
322	Supply, Installation, Testing & Commissioning of Audio Server 240w with designed output as per selected speaker, minimum 1X balanced input, 1X Unbalanced Input, Frequency response 50 Hz - 22 kHz, DSP features: Per channel presets for high-pass filter, parametric EQ, multi-band compressor, and look-ahead limiter.	1.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
323	Supply, Installation, Testing and Commissioning of UHF wireless microphone system, sound clarity, impeccable performance, make the er 58 series one of the most popular wireless microphone system currently available. With head mic and inbuilt battery.	1.00	Nos	0.00	0.00
324	SITC of Speaker Cable	100.00	MTR	0.00	0.00
325	SITC OF System Rack 600/600/800 along with require accessories as per site requirement complete as per approve by consultant	1.00	Nos	0.00	0.00
326	SITC 65 INCH DISPLAY One physical power button, Bottom loudspeaker, 4K ultra HD display, IR (Infrared Ray) touch technology, AG tempered glass 4mm Mohs level 7, Compatible with detachable PC module, USB 3.0 Auto switch to android, Front USB 2.0 Auto switch to current channel, Low parallax, 1 mm air gap, System Version Android 8.0, CPU A73×2+A53×2, GPU Mali-G51×4, RAM 4GB, ROM 32GB, Sensing Type Infrared recognition, Touch Tool Finger, Passive infrared pen, Touch point 20 points touch	1.00	Nos	0.00	0.00
327	SITC of Fixed wall Mounting Bracket with Tilting Option	1.00	NOS	0.00	0.00
328	SITC of Cables & Conenctor	1.00	NOS	0.00	0.00
329	SITC OF Lumens Video Bar Broadcast Camera 4K Video Soundbar All-in-One Video Conferencing Solution with Auto-Framing Camera, Complete voice and video VC system, 4K sensor with auto-framing, Designed for monitor or wall mounting (TV mounting kit included), USB connectivity with Ethernet and IR control, ultra-wide 120° field of view	1.00	NOS	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
330	SITC of online Un-interruptible Power Supply system with IGBT Based rectifier and Inverter & sealed maintenance free batteries. Three phase Input and Three Phase output with Inbuilt Isolation transformer with 0.9 load power factor with battery, over under voltage output with over load & short circuit protection equipment. The system housed in CRC sheet duly powder coated paint with following capacity & with Following size of batteries for 30 Min Backup (Minimum 8160 VAh) 10 KVA UPS with 34 AH, 20 Nos. Battery Certification : BIS	1.00	Nos.	0.00	0.00
331	SUPPLY OF SAMSUNG MAKE or Equivalent make : VARIABLE REFRIGERANT FLOW SYSTEM Outdoor Units 46 HP (Top Discharge Cooling Only)	1	Nos.	0.00	0.00
332	4 Way Cassette Type Indoor Unit : 4.0 TR	2	Nos.	0.00	0.00
333	4 Way Cassette Type Indoor Unit : 3.2 TR	1	Nos.	0.00	0.00
334	4 Way Cassette Type Indoor Unit : 2.6 TR	5	Nos.	0.00	0.00
335	4 Way Cassette Type Indoor Unit 2.0 TR	1	Nos.	0.00	0.00
336	1 Way Cassette Type Indoor Unit : 2.0 TR	8	Nos.	0.00	0.00
337	1 Way Cassette Type Indoor Unit ; 0.8 TR	2	Nos.	0.00	0.00
338	Remote : Cordless Remote for Cassette unit	19	Nos.	0.00	0.00
339	All refrigerant Joints	19	Nos.	0.00	0.00
340	INSTALLATION OF SAMSUNG MAKE VARIABLE REFRIGERANT FLOW SYSTEM - INDOOR & OUTDOOR UNITS AS PER DRAWINGS Outdoor Units : 46 HP (Top Discharge Cooling Only)	1	Nos.	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
341	4 Way Cassette Type Indoor Unit : 4.0 TR	2	Nos.	0.00	0.00
342	4 Way Cassette Type Indoor Unit : 3.2 TR	1	Nos.	0.00	0.00
343	4 Way Cassette Type Indoor Unit : 2.6 TR	5	Nos.	0.00	0.00
344	4 Way Cassette Type Indoor Unit : 2.0 TR	1	Nos.	0.00	0.00
345	1 Way Cassette Type Indoor Unit : 2.0 TR	8	Nos.	0.00	0.00
346	1 Way Cassette Type Indoor Unit : 0.8 TR	2	Nos.	0.00	0.00
347	Remote : Cordless Remote for Cassette unit	19	Nos.	0.00	0.00
348	All refrigerant Joints	19	Nos.	0.00	0.00
349	All refrigerant piping between indoor & outdoor units. Refrigerant pipes should be insulated with Nitrile Rubber Insulation.	1	Lot	0.00	0.00
350	Control cables between indoor and outdoor unit. Providing & fixing control cum transmission wiring Cabling of 2 core x 0.75 sqmm copper between indoor and out door unit.	1	Lot	0.00	0.00
Total Amount					0.00
H	Part-8				
351	PVC Drain piping for the units with Insulation. 32 mm dia	120	Rmt	0.00	0.00
352	Testing & Commissioning charges along with topping-up of refrigerant.	1	Lot	0.00	0.00
353	Ms Patala Stand for VRF Outdoor Unit	2	Nos	0.00	0.00
TOTAL AMOUNT					0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
I	Part-9 (Rate Only Item)				
354	Providing and laying controlled cement concrete M.250 and curing complete including finishing smooth with, curing, safety measures etc. complete including the cost of form work but excluding the cost of reinforcement. including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. in (D) Columns, Pillars posts and struts etc.	R/o	Cu.mt	0.00	0.00
355	Vitrified Flooring : tile size 800 x 1600 mm : Lift Lobby " -----Do-----" as per above specification for complete work. Basic rate of tile is Rs. 70/Sqft.	R/o	Sq.mt	0.00	0.00
356	Italian Marble Stone Flooring : Providing and laying machine cut, mirror polished 18 mm thick Italian Marble stone flooring laid in required pattern in linear portion of the building all complete as per architectural drawings, with 18 mm thick stone slab laid over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with white cement slurry @ 4.4 kg/sqm including pointing with white cement slurry admixed with pigment to match the marble shade including rubbing, curing and polishing etc. All complete as per approved sample by Architect, drawings and instruction of EIC. at all floors / all levels / all heights and all shapes. The rate includes machine cut edges of uniform thickness and beveling and mirror polishing of edges. The rate shall be inclusive of protecting the flooring by plaster of Paris applying and after completion of work remove or 4 mm thick protection sheet of Supreme make EPE+HM Blue. Basic rate of Granite stone is Rs. 420/ Sqft.	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
357	<p>Single Leaf Flush Door with glass view panel: Providing and fixing in position 40 mm thick BWP grade single leaf flush doors of approved make, finished with both side 1 mm thick VNR laminate s approved, 8mm toughened milky Glass view panel, door fixed on frame (excluding stone frame), Hardware fittings like concealed door closer or floor spring, Door handle, lock, Door stopper, Hinges etc. as per approved make & sample. work complete including all type of hardware, fittings, fixtures, bending, bidding, safety measures, as per instruction of Client/ Architect etc complete as per detailed drawings and specifications. sample mock shall be approved from Architect/ Client. Equivalent to VNR series laminate. (Toilet Door)</p>	R/o	Sq.mt	0.00	0.00
358	<p>Fixed Glass Aluminium Window: Domal section : R40 mm series Supply & Fixing Fixed glass window Comprising from Domal section series R40 mm series with powder coated as per approved make & sample by Architect/EIC. Frame section: 40 x 39.4 x 1.25 mm Glass : 6mm Thick Toughened Glass of Saint Gobain ET125 6mm FT Neutral shadeapproved make list . including EPDM Gasket and All Necessary Hardware etc. complete as per detailed drawings, mock sample and specifications.</p>	R/o	Sqm	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
359	S. S. Railing : Vetroline 11T3 (M) Handrail Round 50mm Providing and fixing 1050mm high SS Railing (304 grade) system comprising 50mm dia. and 16 guage (1.6mm) Stainless steel pipe top handrail (SS 304 - Matt Finish), 35mm dia. and 16 guage (1.6mm) Stainless steel pipe of baluster and 12mm dia. Stainless steel inclined/ horizontal intermediate pipe (SS 304 - Matt Finish) placed at 100mm c/c distance and as per site requirement. Railing fixed on floor with 120x50x10mm base plate. whenever required, joints to be filled with bushings for extra strength. Rates should be inclusive of welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, including fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the side of waist slab/wall with suitable arrangement as per approval of Engineer/ Architect. Work shall complete includes all type of tools, tackles, all level & Height, labour, safety measures, mock sample etc complete as per the detailed drawing and instruction of EIC. Note :Handrail Length will be measured from Starting to End Location.	R/o	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
360	<p>Grid Ceiling:Providimg & Fixing of Eco- Friendly Light weight Calcium Silicate Ceiling .Providing and Fixing False ceiling at all heights 100% Eco Friendly , Non Cementitious light weight calcium silicate false ceiling tiles having having 15 mm thick integral densified edges (for extra Strength) reinforced with Eco-friendly fibres and natural filler with a eco-friendly recycled content of more than 50% (For Green Building Leed Accreditation) . False ceiling tiles of Size 595x595 mm of approved texture, design and patterns Viz Spintone/ Cosmos/ Spectra /Globe/Hexa/Quadra having NRC (Noise Reduction coefficient) 0.50 to 0.75 (for semi perforated and fully perforated range of tiles), Light reflectance of 85% (minimum) . Non-combustible as per BS: 476 (part-4), fire performance as per BS: 476 (part 6 & 7 (High Fire resistivity for very high fire safety), humidity resistance of 100% RH (Suitable for any weather conditions) , Thermal conductivity of 0.050 W/m°KC to 0.050 W/m°KC as per IS 3346/1980 (High Thermal Insulation). 100% Antifungal , Antibacterial, Anti termite.The ceiling Tiles should be free from Chemicals, asbestos having Zero VOC Property for better indoor Air quality The tiles shall have average body density of 370 kg/m³ as per ECBC code 2007 and average edge density of 450 Kg/m³. The tile shall be primer coated on both sides and the fair surface shall be having a factory finish in two coats of white dispersion type solvent free paint.The framework shall be suspended from ceiling by slotted cleats of size 25X35X1.6mm fixed to ceiling with 12.5mm dia and 50mm long dash fasteners, 4mm G.I. adjustable rods with galvanized steel level clips of size 85X30X0.8mm, spaced at 1200mm centre to centre The tile shall be laid on 24x38mm wide T section flanges colour white having rotary stitching on all T sections, i.e., the main runner, 1200 mm & 600 mm cross tees with a web height of 38mm & load carrying capacity of 11-13kgs/Sqm. The work shall be carried out as per specifications, drawing and as per directions of the Engineer-in-Charge/Manufacturers Specification. Necessary cutting / providing openings in the ceiling for AC fixtures, grills, electrical fittings, or other utility services, hatch openings etc. shall be provided by the Contractor and cost of making such modifications shall be included in the price., safety measures , No separate charges for cutting / providing opening will be paid. Trap doors with necessary ply frame workto be provided as required at no extra cost. Work complete as per the detailed drawing and instruction of Architect/EIC.</p>	R/o	Sqmt	0.00	0.00
361	<p>Wooden ceiling finish with Laminate : " -----Do-----" as per above specification for complete work. Only finish with laminate instead of veneer. Equivalent to VNR series laminate.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
362	Fluted panel ceiling : " -----Do-----" as per above specification for complete work. Only finish with Fluted panel instead of veneer. Rate shall inclusive cost of making of all cutouts for light fixtures, gadgets, gizmo, pelmets, grooves, CNC engraving , beads and also provide support/template where ever required. The rate shall be in sq.mt for all floors and at all heights including all costs. (or a sample mock of 5 Sqm minimum of the frame work and ceiling) shall be approved from Architect.(considering all levels with require all Framing work and fitting from RCC slab to ceiling level).	R/o	Sq.mt	0.00	0.00
363	Wooden solid Partition finished with one side Veneer finish and one side laminate: : " -----Do -----" as per above item specification for complete work. using 4 mm thick Veneer & matt finish monocoat polish instead of laminate for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs. Equivalent to VNR Series Laminate. Equivalent to VNR series laminate.	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
364	<p>Wooden solid Partition finished with Both side VNR Laminate: (3' ht Wooden + 1'-0" glass) Providing & fixing 12mm thick fire retardant marine plywood as per IS 710:2010 and IS 5509:2000 fixed on frame work on both side finish with 1mm thick Laminate. The frame work shall be made from square hollow aluminium section size of 50x50x1.5 mm & 25x50x1.5 mm of approved make conforming to IS code. The framework shall be fixed as per drawing vertically @ 600 mm c/c & horizontal 600 mm c/c horizontally.</p> <p>All ply/wooden shall be treated with anti- termite treatment . Both side finish with VNR Laminate. Glass shall be Lacquered glass as per selection by Architect / EIC. Rates shall also be inclusive of cost of making cut outs/ openings for MEP services & providing additional sections for strengthening around the openings/cutouts additional support for fixing of patch fittings for doors, making grooves between wall & board, in filled with termite treated wooden members if required or as per drawing /instruction of EIC. and no extra payment shall be considered for additional sections provided. work complete including all type of material, fittings, fixtures, Finish, loading, unloading, safety measures, transportation, all leads, accessories, groove, PVC edge banding, adhesive ,tape, headless nails, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications & instruction of Client/EIC. only the clear elevation area shall be measured and paid. sample mock shall be approved from Architect/Client. Equivalent to VNR series laminate.</p>	R/o	Sq.mt	0.00	0.00
365	<p>Fluted Glass partition: " -----Do -----" as per above item specification for complete work. using 5 mm thick Fluted glass instead of thin profile glass for partition work, as per approved by Architect/Client. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transporation, all leads, accessories, safety measures, sample mockup, all floor, all levels, all heights etc complete as per detailed drawings, specifications & instruction of Client/EIC. Basic rate of Fluted glass Rs.220/Sq.ft.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
366	Alabaster panelling: " -----Do -----" as per above item specification for complete work. Using 6/8 mm thick Alabaster instead of veneer for panelling work. The rate shall be for all floors, at all heights, all shapes including all costs. Basic rate of Alabaster is Rs. 600/Sqft	R/o	Sq.mt	0.00	0.00
367	Lacquered glass / Coloured glass Panelling : " -----Do-----" as per above item specification for complete work. using 4mm thick coloured magnetic glass / Coloured glass for panelling work, as per approved by Architect/Client. TThe rate shall be for all floors, at all heights, all shapes including all costs.	R/o	Sq.mt	0.00	0.00
368	Overhead storage : " -----Do-----" as per above specification for complete work.	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
369	<p>Full height storage with Artificial stone niche : Storage Comprising from IS 303 BWR 19 mm thick and 12 mm ply, finish with 1 mm thick Laminate finish as per approved make and shade by Architect. Solid Shutter : 25 mm thick comprising from IS 303 BWR ply & finish with 1 mm thick Laminate . Shelf: 19 mm thk IS 303 BWR ply finish with both side approved laminate. Inner area shall be finished with linear laminate. Ledge/Niche comprising from 15mm thick artificial stone (four side), required lighting arrangement. The work shall be done as per the detailed drawing, specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives, grooves, consumable hardware & required SS 304 grade hardware/accessories, Profile handle, Wooden frame, monocoat polish, pvc edge banding of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Equivalent to VNR series laminate. Elevation area shall be measure for payments.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
370	<p>Glass profile storages : Equivalent to Amardeep/Godrej/Civom/Methodex/EPL/Wipro or approved brand by Architect/Client. Frame: Frame shall be made of IS 303 BWR grade ply 35 mm thick with both side laminate finish as per approved sample. Shutter : 4 mm thick clear glass as per approved sample. Shelves : IS 303 BWR grade ply 25 mm thick with both side laminate finish as per approved sample(adjustable shelving system) Back : IS 303 BWR grade ply 19 mm thick with both side laminate finish as per approved sample. Two side Postforming edge and other side 2mm PVC edge Imported banding & sealed edges are with 0.8mm thick PVC Imported edge banding. Having premium lock with wave key technology and side and hinged shutters are sealed with 2mm thick PVC edge banding. SS 304 recessed handles are provided for easy opening and closing of shutter. The units are assembled by knock down fittings such as Minifix & Dowels. All the hardware and Hinges are from Hettich/Ebco. PVC edge banding are imported from Rehau or Dolken of Germany . Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessories, sample mockup etc as described in item description. work complete as per the instruction of Client/EIC.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
371	Waiting area Table: 900 x 900 x 400 mm Center table : 25 mm thick Solid wooden top with matt finish monocoat polish. Vertical support: solid wooden Leg with matt finish monocoat polish with busher. Work complete including Providing & fixing, all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	R/o	Nos	0.00	0.00
372	Waiting Lounge area Corner table : 450 x 450x 400 mm " -----Do-----" as per above specification for complete work.	R/o	Nos	0.00	0.00
373	Cabin Center Table: 900 x 600 x 400 mm Table top: 15 mm thick Artificial stone top. Vertical support: solid wooden Leg with matt finish monocoat polish with busher. Work complete including Providing & fixing, all necessary hardware and fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	R/o	Nos	0.00	0.00
374	Cabin Corner Table: 450 x 450x 400 mm " -----Do-----" as per above specification for complete work.	R/o	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
375	Cabin Sofa (Three seater): 2100 (L) x 870 mm (B) x 800 mm (H) comprising of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC all external & internal exposed woodwork to be finished in PU semi gloss finish polish. The work shall be done as per the drawing, specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 800 Rmt	R/o	Nos	0.00	0.00
376	Cabin Sofa (Two seater): 1500 (L) x 870 mm (B) x 800 mm (H) " -----Do-----" as per above specification for complete work. Basic Rate of Fabric : 800 Rmt	R/o	Nos	0.00	0.00
377	Cabin Sofa (One seater): 900 (L) x 870 mm (B) x 800 mm (H) " -----Do-----" as per above specification for complete work. Basic Rate of Fabric : 800 Rmt	R/o	Nos	0.00	0.00
378	Chair Type-3A -Model equivalent make - Amardeep Lotus 01 High Back Model equivalent to Lotus 01 : High Back Revolving Chair as per approved make list. Chair With frame in MS, PU foam in back & Moulded PU Seat, Chrome Arms with PU cladding & Synchro Mechanism, Chrome base, & Gas Lift. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	R/o	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
379	<p>Chair Type-4A -Model equivalent make - Amardeep Lotus 02 Mid Back Model equivalent to Lotus 02 : Medium Back Revolving Chair as per approved make list. Chair With frame in MS, PU foam in back & Moulded PU Seat, Chrome Arms with PU cladding & Synchro Mechanism, Chrome base, & Gas Lift. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	R/o	Nos	0.00	0.00
380	<p>Wooden benches (3 seater) at passage area. size: 1500mmx 450mmx 450mm : Providing, making, and placing in position with all necessary accessories. Seat, Back & Base: wooden/ply 25 mm thick with Polish finish. All wooden surfaces are to finished with PU polish. Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per drawings, specifications & instruction of Client/EIC.</p>	R/o	Nos	0.00	0.00
381	<p>Carpet Flooring Work: Providing & laying carpet flooring as per approved make & Sample by Architect. Carpet fixed with SR 505 Pidilite or equivalent tile adhesive and underlay foam material. carpet should be laid as closure to each other. Contractor will take care for level matching with other area flooring. Scope includes labour, under lay material, disposal of debris, necessary cutting of tiles without damaging the edges, including to provide & fixing of SS 304 finish end profile, skirting, edge profile etc to protect and cleaning, etc. complete. All works are carried as per detail drawing / instruction of architect / EIC. Before laying carpet contractor shall prepare even surface as per required. equivalent Welspun Relay Welspun : Carpet tiles Lime AC:CT000702 : Iron AC:CT000705. Carpet tiles or basic rate of carpet is Rs. 140/Sqft</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
382	<p>Texture paint(Stucco) :Wall painting two coats with Stucco of Asian or equivalent approved brand in any shades and colour as directed on wall surface to give an even shade including applying of a one coat of Penetrating primer or equivalent and two coats of paint, scaffolding to at any height with all labour and material thoroughly brushing the surface free from mortar droppings and other foreign matter and sand prepared smooth etc. complete. The substrate must be sound, clean, dry, free from dust, oil, grease and laitance etc. All traces of release agents must be removed. On chalky and dusty surfaces, all loose material must be removed by stiff bristle brushing. The primer / paint application is to be done with the rollers. rate shall be including, safety measures, crack filling and levelling as per manufacturers specification. Top coat should have. 1) Low VOC content. 2) Crack Bridging ability upto 2.6 mm. 3) 100% pure acrylic emulsion 4) Anti-Carbonation concrete protection 5) Very Low Flame spread 6) Superior Washability.</p>	R/o	Sq.mt	0.00	0.00
383	<p>Wallpaper: " -----Do-----" as per above specification for complete work. Basic rate of wallpaper is 155 / Sq.ft</p>	R/o	Sq.mt	0.00	0.00
384	<p>VERTICAL GREENARY : Providing and fixing vertical garden including Plants,Vertical Garden Pots would be places on aluminium rails with plastic sheet as a backdrop to protect the wall from coming in contact with water. potting soil, Irrigation will be done with 8 liter per hour dripper via drip irrigation and installation of the same. Work including All the excess water shall be collected in the aluminium drainage channel placed at the bottom, GROW LIGHTS etc complete as per instruction by Architect. Work complete including all type of material, fittings, fixtures,Finish, loading , unloading, transportation, all leads, accessories, sample mockup, all floor, all levels, all heights, necessary frame work, Scaffolding etc complete as per detailed drawings, specifications & instruction of Client/EIC.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
385	<p>Artificial Grass : Providing and fixing Artificial Grasses per approved make & Sample by Architect. Work complete including all type of finishing. Material content : Pile Weight 1.65 Kg/sq.mtr, Total Weight 3.00 Kg/sq.mtr, Pile Height 40 mm, Stitch Rate 16 Stitch / 10 cm, Tufted Dencity 16800 D/sq.mtr, Primary Back PP + Non Woven Layer, Pile Material PP+PE, Backing Synthetic Glue, Yarn Denier 11400.</p> <p>Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, necessary frame work, Scaffolding etc complete as per detailed drawings, specifications & instruction of Client/EIC.</p>	R/o	Sq.mt	0.00	0.00
386	<p>Removing/chipping and cleaning of existing concrete carefully by low impact high frequency hammer without damaging the existing concrete or by control sand blasting including cleaning the surface by air jet etc. complete as per direction and satisfaction of Engineer-in-charge (for payment area of R.C.C member before chipping/ removing loose concrete will be measured).For any thickness of RCC members. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.</p>	R/o	Cu.mt	0.00	0.00
387	<p>Applying two coats of alkaline rust converting primer of approved quality and make conforming to ASTMB-117 (Cleaning existing reinforcement with wire/rotary wire brush, making the surfaces free from loose material, dirt etc. complete) on the rebars, including cleaning the reinforcement wire brushing to remove loose rust spalls, As per the recommendation of manufacturer complete as per direction of Engineerin-charge. for Payment exposed length of reinforcement will be measured (Alkaline rust converting primer - REEBAKLENS RR of FOSROC / Sika Rustoff 100 of Sika / BASF/ Pidilite/ Krishna Conchem).Bars upto 12 mm Diameter. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.</p>	R/o	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
388	" -----Do-----as per above specification for complete work . Bars above 12mm diameter	R/o	Rmt	0.00	0.00
389	Providing and laying anticorrosive Treatment of Reinforcement by any approved make rebar corrosion protection system to existing reinforcement (The application shall be by brush). Process is to be complete as per the recommendation of manufacturer and direction of Engineer-in-charge. for payment exposed length of reinforcement will be measured. (Product - NITAZINC PRIMER of FOSROC /Fiazinc® R of Sika/ MasterEmaco P 130 of BASF or equivalent of pidilite & Krishna Conchem).Bars upto 12mm Diameter. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Rmt	0.00	0.00
390	" -----Do-----as per above specification for complete work . Bars above 12mm diameter	R/o	Rmt	0.00	0.00
391	Makeing 'V' groove of 5 mm wide and 5mm deep over crack line by electrically operated angle grinder with diamond concrete saw blade and cleaning it by air blower as directed by Engineer-in-charge Sealing of exposed 'V' groove of 5mm deep and 5mm wide with solvent-free, moisture tolerant, thixotropic, two part structural adhesive and epoxy repair mortar cum surface levelling mortar the compressive strength of the epoxy repair mortar shall be ≥ 60 N/mm ² (14 Days) and Bond strength ≥ 10 N/mm ² (7 Days). (Product -NITOMORTAR S OF FOSROC/ Sikadur®- 31 of Sika/ MasterBrace 2200 BASF or equivalent of Pidilite or Krishna Conchem). Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	R/o	Rmt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
392	<p>Driling and fixing NRV nozzles in RC members, including (fixing material : Renderoc Plug of Fosroc / Sikadur-31 of Sika/ MasterBrace 2200 of BASF or equivalent of Pidilite & Krishna Conchem). Drilling Holes: Drilling 12mm dia, 50 to 75 mm deep holes in structural members of the intervals of 350 mm in staggered manner or as directed by the consultants in RC structural elements. Cleaning of holes: Clean the holes by air blower prior to fixing nozzles.</p> <p>Cuttting of Nozzles: Cut the nozzles by chisel after completion of grouting without damaging structural elements: all type of structure</p> <p>Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.</p>	R/o	Each	0.00	0.00
393	<p>Supply and apply a polymer modified cementious board coat. Ratio polymer : water : cement (1 Polymer: 4 Water: 6 Cement) by weight. Apply the patching mortar when the bond coat is tacky (Nito Bond SBR Latex of Fosroc/ Sika® latex of Sika/ MasterEmaco SBR2 of BASF or equivalent of Pidilite or Krishna Conchem)</p> <p>Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.</p>	R/o	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
394	<p>Injecting/Grouting shrinkage free low viscosity epoxy resin grout in structural cracks, wherever required by pressure and using mechanized injector gun with accessories till nozzles refused to accept the grout. Epoxy grout material should be conforming to ASTM-881-87 type I, grade I, class B & C and compressive strength of the material shall be ≥ 55 Mpa, (7 Days), Tensile strength ≥ 20 Mpa (14 Days) & Bond strength 10 Mpa (14 Days). (Low Viscous epoxy grout : conbextra EP10 of Fosroc/ Sikadur®-52 of Sika/ MasterInject 1315 of BASF or equivalent of Pidilite & Krishna Conchem). Mixing of material : Mixing material components in required quantities as per manufacture's instruction. Grouting : Fill the grouting gun with low viscosity epoxy resin. Maintain desired pressure in the gun by air compressor: maintain the required pressure at exit. Grout the material through prefixed nozzles in structural elements till its refusal, seal the nozzles with epoxy putty after the refusal, monitor leakages through other nozzles while grouting and seal them as per the requirement, repeat the process for all the nozzles. complete the operation within pot life of the material. Cleaning the gun and accessories: Clean the gun and accessories (valves, pipes and other fixture) with thinner after the operation to avoid jamming of the gun.</p> <p>Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.</p>	R/o	Kg	0.00	0.00
395	<p>Supplying and erecting approved make oscillating type bracket fan A.C. 230V. 50cy/s 400/450 mm sweep wall mounted with height adjustment and rotary tilting device complete with guard, flexible Core plug top complete erected with lead wires as directed.</p>	R/o	Nos	0.00	0.00
396	<p>Supplying & erecting Electronic Type Cordless Call Bell erected on PVC/Metal board having portable bell push working on D.C. & bell on 230V A.C. supply with cells / battery</p>	R/o	Ea	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
397	Supplying & erecting Approved make call bell indicator with buzzing sound and Red light indicating lamp with Red light button to attend the call suitable for 240 v 50 c/s supply to be erected.	R/o	Ea	0.00	0.00
398	"Supply Installation Testing Commissioning of Indoor deep Recessed Round COB downlight 18-21W Recess Mounted Round 36-40 DEGREE COB downlighter with below features 1. Pressure die cast Aluminum alloy housing for better thermal conductivity. 2. . Round Version. 3. Efficacy of Fixture more then or equal to 85 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80, High efficiency driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 5. LED life of more then 35000 Hrs @ L70. REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) recess mounted die cast ORRIN 20w Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva	R/o	Nos	0.00	0.00
399	"Supply Installation Testing Commissioning of Indoor deep Recessed Round COB downlight 27-30W Recess Mounted Round 36-40 DEGREE COB downlighter with below features 1. Pressure die cast Aluminum alloy housing for better thermal conductivity. 2. . Round Version. 3. Efficacy of Fixture more then or equal to 85 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80, High efficiency driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 5. LED life of more then 35000 Hrs @ L70. REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) recess mounted die cast Legend Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva	R/o	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
400	Supply Installation Testing Commissioning of Multipule lines of led strip with alumniun profile for backlighting the Onyx stone with a dotless effect and complete even lighting Remote driver to be kept for maintatinance purpose Should be around 90w-120w per square meter Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva	R/o	SQ. MTR	0.00	0.00
401	""""Supply Installation Testing Commissioning of Pendant luminaire Amoeba with LED, system power: 80 W(16 W Up and 64 W Dn), the luminous flux of luminaire:8800 lm, the color temperature of 3000 K up and 5700 K dn,Warm white up and cool white down, 230 V constant currentdriver, 70% of luminous flux after 50,000 operating hours,direct/indirect light emission (23 % up and 77 %dn), luminaire housing in CRCA, white polyester powder coatapplied over a 5 stage pre-treatment, prismatic diffuser forhomogenous and uniform illumination, Dimmable digital Dalicontrol gear, protection class I, IP20, L = 1194 mm, B = 1832 mm, H = 150 mm. REGENT Make Amoeba suspended Equalant in ENDO/TISVA/Lighting technologies""""	R/o	Nos	0.00	0.00
402	""""Supply Installation Testing Commissioning of Pendant luminaire Evoke with LED bulb and e27 holder,system power: 15 W, colour temperature of 4000K,Neutral white, 230 constanst current voltage, luminairehousing in CRCA, polyster powder coated white, wood finishat top, REGENT Make EVOKE suspended Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva, Regent	R/o	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
403	"Supply Installation Testing Commissioning of Indoor Surface mounted round downlight 15-18W surface Mounted round backlit downlighter with below features Pressure die cast Aluminum alloy housing for better thermal conductivity. 1. Powder coated using Nano technology for longer durability. 2. PS diffuser for optimum light transmission. Round Version. 3. Efficacy of Fixture 95 Lumens /watt Available with 5700K, 4000K & 3000K CCT. 4. CRI>80 High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD 0 deg K, 4000 deg K, 3000 deg K Lighting technologies DLCR 18w D/L Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva	R/o	Nos	0.00	0.00
TOTAL AMOUNT					0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
J	Part-10 (Rate Only Item)				
404	<p>Indoor BATTEN Lighting 28W-33w 1200MM Surface mounted TUBE LIGHT/batten with below features</p> <p>Extuded Aluminum alloy housing for better thermal conductivity.</p> <p>Powder coated using Nano technology for longer durability. PS diffuser for optimum light transmission or opiton of Lens Based profile for better task lighting. Option to be selected by Architect / Consultant</p> <p>Efficacy of Fixture 95 Lumens /watt</p> <p>Available with 5700K, 4000K & 3000K CCT. CRI>80</p> <p>High efficiency Mettalic driver with inbuild surge protection, over voltage protection, short circuit protection and operating at >0.9 PF. <5% THD</p> <p>LED life of 50000 Hrs @ L70. IP20 Protection</p> <p>Luminaire performance & Safety :IEC 60598, IS 10322-5, IS 161-03/05/06/07, Surge : IEC 61000-4-5, EMC : EN 55015.</p> <p>The product should be Manufactured in India (all the Components should be manufactured in India except the Led source which can be imported . (Approved Led source Nichia , Cree, Lumileds , Osram Only)</p> <p>PF >=0.95 and THD <=5 % (Certificate need to be submitted from NABL Accredited lab)</p> <p>Equivalent to Lighting Technologies INDO BATTEN 28W 4ft</p> <p>Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva</p>	R/o	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
405	<p>Supply, Installation Testing and Commissioning of LED high bay luminaire of 70W having System Efficacy, Should be in Narrow beam angle optics of 30 degree >145 lm/W, system output 10000 Lumens, THD <10%, Power Factor >0.95, CRI >70, CCT 5700K, Full IP</p> <p>65 protected single piece die cast aluminium housing having integrated PC lens cover having integrated optics with Impact resistance IK08, Life L70B50 @ 50k hrs. BIS compliant driver, EMC - EMI compliant. Driver shall have 4KV Surge protection. Luminaire should have option of wide and narrow beam angle options with Operating temperature range from 0 to 55 deg C. LM79 and LM80 reports must be submitted from a NABL accredited laboratory. BIS certificate for driver as well as the luminaire must be submitted for records. Driver and luminaire shall be of same make.</p> <p>REF :Lighting technologies Eterne 70w Approved makes : Philips,Havells,Lighting technologies, Wipro,Tisva</p>	R/o	Nos	0.00	0.00
406	<p>Supply Installation Testing Commissioning of Indoor recess mounted 35mm cut out (35x35mm profile light), Heavy aluminium Extruded Aluminium alloy Housing and polycarbonate diffuser profile for continous decorative illumination</p> <p>Anodised aluminium end caps firmly fixed on the aluminium extrusion</p> <p>Silver anodised finish for elegant look . Efficacy of Fixture >=100 Lumens/Watt suitable for self adhesive Strips with driver.</p> <p>Wattage should be 40-55w/m. Should have a dotless continuos effect. Should be operated using remote driver of 24V Dc kept at suitable locations for future maintainance.</p> <p>REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) Lume series Strip light LSX20Y145S4 Approved makes : Philips,Havells,Lighting technologies, Wipro,Tisva</p>	R/o	Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
407	<p>Supply Installation Testing Commissioning of Indoor recess mounted 17-20mm cut out (17x16mm profile light), Heavy aluminium Extruded Aluminium alloy Housing and polycarbonate diffuser profile for continous decorative illumination Anodised aluminium end caps firmly fixed on the aluminium extrusion Silver anodised finish for elegant look . Efficacy of Fixture >=100 Lumens/Watt suitable for self adhesive Strips with driver. Wattage should be 14-17w/m. Should have a dotless continuos effect. Should be operated using remote driver of 24V Dc kept at suitable locations for future maintainance. REF :TISVA LIGHTING (USHA INTERNATIONAL LTD) Lume series Strip light LSX20Y145S4 Approved makes : Philips,Havells,Lighting technolgies, Wipro,Tisva</p>	R/o	Mtr	0.00	0.00
408	<p>Supply Installation Testing Commissioning of decorative Glas two head Wall lamp light 10-15w with below features Colour : Matt Gold Dimmensions: Height (in mm): 260, Width : (in mm): 120 Wattage: 10-15w Output : 900-1300Lms Holder type: 2 X G9 Fixture should be more the IP20 rated Ref : TISVA LIGHTING (USHA INTERNATIONAL LTD) :WG2020</p>	R/o	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
409	"Supply Installation Testing Commissioning of 600w Chandelier light with 5,000mm dIA SS BASE PLATE of Colour: Iron / Gold, with 25 pcs of pendant light with below features Product with premium mitsubishi acrylic material Better ambience creation and illumination for the space Long life and highly durable product Premium aesthetics maintained for a long time Brilliant light effect. Gives a notion light getting emitted for curved acrylic edges Easy height adjustment Made from non-toxic materials Colour: Iron / Gold Power: 24 W, INTEGRAL LEDs, SMD 2835 Dimensions per hanging (Length X Width X Height): 500 mm x 500 mm x 15000 mm Ref : For every hanging : TISVA LIGHTING (USHA INTERNATIONAL LTD): SL24217K	R/o	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
410	"Supply Installation Testing Commissioning of 112w 16 head mitsubishi acrylic Chandelier light with below features Protection class: Class I IP Rating: IP20 Dimming: Non-dimmable / Non-tunable lamp include: Integral LEDs, SMD 2835 Crafted with premium Mitsubishi acrylic material Light gets emitted from the curved acrylic edges,Better ambience creation and illumination for the space Long life and highly durable luminaire,Premium aesthetics maintained for a long time Average Weight: 13.7 Kg Power: 112 W Dimensions (Diameter X Height): 1000 mm x 3000 mm Ref : TISVA LIGHTING (USHA INTERNATIONAL LTD): SL112162K	R/o	Nos	0.00	0.00
411	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs.(The DBs should be used of same company of MCB to be used) (F) Single phase 8 way SS Double door	R/o	Each	0.00	0.00
412	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs N) Three phase 16 way SS Double door for horizontal single phase outgoing	R/o	Ea	0.00	0.00
413	Providing & erecting 240 V MCB double pole switch for lighting Load (B Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (B) 40 Amp. Cat.III	R/o	Ea	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
414	Providing & erecting 415V MCB Four Pole Switch for Lighting Load (B curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity (b)40 Amp. Cat.III	R/o	Ea	0.00	0.00
415	Providing & erecting 415 V MCB Four Pole for Motor & Inductive Load (C Curve) having 10KA breaking capacity & confirms to IS :8828 in existing box having following capacity C) 63 Amp. CAT-III	R/o	Ea	0.00	0.00
416	Providing and erecting XLPE (IS:7098)(I)-88 ISI armoured cable multistrand Aluminium conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe of following size of cables. B)4 core25 Sq. mm	R/o	Mtr	0.00	0.00
417	Providing and erecting XLPE(IS:7098)(I)-88 ISI armoured cable multistrand Copper conductor for 1.1 KV. to be laid on wall with necessary clamps or in existing trench / pipe at road crossing or floor of following size of cable. (B) 3 core 4 Sq. mm	R/o	MTR	0.00	0.00
418	Providing and fixing heavy duty flange type brass cable gland with rubber ring for PVC insulated armoured cable complete with out going tails, insulating tape etc for following size of cables.E) 2 to 4 core 25 Sq. mm	R/o	EA	0.00	0.00
419	Supplying & erecting approved make Four Pole 415V change over switch interior for panel mounting with operating mechanism A.C.23 duty confirming to IS for (C)100-125A Cat-III	R/o	Each	0.00	0.00
420	Providing and erecting Approved make Four pole moulded case circuit breaker having breaking capacity ICU of 35 KA. and above at 415 V . having normal current rating 250A. with variable thermal & magnetic release suitable to work on A.C.supply 50 c/s. with all internal connections, spreader tinned copper & complete erected in existing 16 G.M.S. housing. ICS=100% of ICU only Cat III	R/o	Each	0.00	0.00
421	Providing and erecting Annealed bare Copper wire 8 to 16 SWG.	R/o	KG	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
422	Supplying and erecting approved make online Un-interruptible Power Supply system comprising flat cum-boost charger, static Inverter & sealed maintenance free SMF batteries. The charger having operating capacity for input 160-270V AC & inverter having output 230V,50 Hz Ac with 0.8 load power factor with battery, over/under voltage output with over load & short circuit protection equipment. The system housed in CRC sheet duly powder coated paint with following power backup.with MS painted batteries stand, 10% Overload capacity for momentary load. (E) 10 KVA 3 - phase with 1Hr Backup	R/o	EA	0.00	0.00
423	Supplying under floor pregalvanised corrosion proof rectangular sheet steel cable trunking of 1.6 mm thick having with stand point load up to 1.33 Ton & free from seepage of concrete of screed water with all accessories,Junction Box,Joints as required and demanded by engineer-incharge and laying/erecting as per OEM guidelines and as per instruction of engineer incharge having following size of dimensions and No of compartments (W x D x T) Cat-III [13] 300mm x 38mm x 1.6 mm with Three Compartments	R/o	Mtr	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
424	<p>SITC of EN-54 & ISO 7240-16 Certified EVAC PA controller capable of adding 12 zones in the system and expandable upto 400 zones with 14x 4 Audio matrix with full DSP functionality. 8 audio inputs, 4 audio outputs, 4 channel output matrix. Shall support the following: single line switching or redundant group A/B switching, amplifier redundancy, 4 x 100V audio inputs and 12 speaker line outputs. Fault, warning and event conditions log. Built in message manager for 100 emergency/business calls up to 85 minutes. 18 control inputs and 18 control outputs. Impedance measurement and Pilot Tone supervision for speaker line monitoring. The network controllers shall have a possibility to be integrated using an interface module which is able to send and receive Audio to and from other Controllers. Frequency response (ref. 1 kHz) 20 Hz to 20 kHz (-0.5 dB), Signal-to-noise ratio (A-weighted): Line in to line out: 106 dB typical, THD+N < 0.05%, Crosstalk (line level) Line in to line out (0 dB gain): < 100 dB at 1 kHz, Sample rate 48 kHz, DSP processing resolution 24-bit linear A/D and D/A conversion, 48-bit processing. Graphics User Interface software should be considered for Monitoring and control of signal and EN54 Certified EVAC Router for adding 24 zones in the system and to route 4 channels into 8 100V audio inputs to 24 loudspeaker line outputs. 2-in-6 matrix. 20 Control Inputs, 26 Control Outputs. Shall support single line switching or redundant group A/B switching, amplifier redundancy. Impedance measurement and Pilot Tone supervision for speaker line monitoring.</p>	R/O	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
425	SITC of The Digital call station shall be an EN54-16 & ISO 7240-16 certified user interface. It shall be designed in a modern and robust chassis with a graphical display. As standard, the call station shall have a gooseneck microphone with pop shield and permanent monitoring, an illuminated LC-display and an integrated loudspeaker to be used for system sounds It shall be possible to modify the call station to suit the user's requirements by connecting up to five remote call station extensions, each with 20 free customizable functions and selection buttons. The Call station shall have a built-in numerical keypad; it shall be possible to enable or disable the keypad during configuration • Five menu/function keys (pre-programmed) – four buttons shall provide each 1 LED (two LED's shall be 2 green and 2 LED's shall be yellow). • Green led on the microphone which is active during a call • 15 function and speed dial buttons (customizable), two LEDs (green/red) per button. • Button functions shall be programmable such as: • Zone select, source select, level control, emergency on/off, message on/off, failure acknowledge/reset. • switching output trigger on/off or 0 to 10V, select scheduled events, scheduled event on/off. • CAT5 cable for data and audio connection to controller (can bus, up to 1000 meter).	R/O	Nos	0.00	0.00
426	SITC of EN-54 & ISO 7240-16 certified 2x 500W Class D, high efficiency amplifier. 70/100V loudspeaker output voltages, galvanically separated, 4 automatic selectable audio inputs on RJ45, local input. THD ≤1%. Frequency response, ref. 1 kHz, rated load, -3 dB : 50 Hz to 25 kHz. Signal-to-noise ratio (Aweighted) > 104 dB, Output noise (A-weighted) < -62 dBu, Crosstalk , ref. 1 kHz < -85 dB. Audio input level limiter, RMS output power limiter, high temperature, DC, short circuit, mains undervoltage protection, DC supply undervoltage protection, inrush current limiter, ground fault	R/O	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
427	SITC of 6W Metal Grill ceiling mount speaker with excellent speech & music reproduction - Max Power: 9W, Rated Power: 6Watts, Power Tapping: 6/3/1.5W - Effective frequency range(-10 dB) : 75 Hz to 18 kHz - SPL at rated power (1Khz at 1 m) 92 dB - Opening Angle 1 KHz / 4 KHz:: 180°/65° Dimensions (DxH) 170 mm x 70 mm	R/O	Nos	0.00	0.00
428	SITC of Back box for LC3 speaker Easy to install Water- and dust protected Prevents sound traveling via the ceiling cavity to adjacent areas	R/O	Nos	0.00	0.00
429	SITC Of Cable 2 Core 1.5 Sq MM Cable With Standard accessories	R/O	Mtr	0.00	0.00
430	SITC of 12 U 550X600 Rack	R/O	Nos	0.00	0.00
431	SITC of Analogue Addressable Multi- Sensor which is fully compatible with Analogue Addressable Protocol, having removable high performance chamber with Twin fire LED's allow 360 degree viewing, User selectable sensitivity modes 1% to 4.5% obs/m, Incorporate Optical and dual Heat elements, lock mechanism (sensor to base), Electronically addressed, Pulsing/non-pulsing controlled from panel. Approved by LPCB & VdS.	R/O	Nos.	0.00	0.00
432	SITC of LIU 6 PORT Rack Mount - Loaded (LC) SM	R/o	Nos	0.00	0.00
433	SITC of OPS with Core i5 Processor 8 GB Ram, 256 GB SSD 4k Resolution	R/O	Nos	0.00	0.00
434	SITC of Tiled wall Mounting Bracket	R/O	Nos	0.00	0.00
435	Supplying, installation, testing and commissioning of Pop-Up Box / Cable cubby Includes a Universal power outlet X 2 Nos, HDMI Port X 1nos, RJ-45 X 2 Nos., 1 Double Power Socket Slot, 6 Insert Slots (Includes 4 Blank & 2 Cable Pass-Through Inserts). TBUS Dual Power Socket - Universal, Wall Plate Insert – Dual RJ-45 - Black , W-HDMI Wall Plate Insert - Black, TBUS AC Power Cord - Right-Angle India 6ft 250V AC.	R/O	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
436	SITC of 16 Port POE Switch with necessary power requirements as per site condition.	R/O	Nos	0.00	0.00
437	Supply, Installation Testing & Commissioning of 65"UHD resolution, ultra high-definition 4K resolution. Crystal Processor 4K, The flat back and slim depth , Built-in WiFi and Bluetooth, Resolution 3840*2160 (4K UHD), Built in Speaker(10W + 10W), HDMI 2.0 (2), HDCP 2.2USB 2.0 x 2, S232C(in/out) thru stereo jack, RJ45, 9.2mm(U/L/R), 11.2mm(B) with mounting bracket with tilting option & necessary Cables	R/O	Nos	0.00	0.00
438	SITC Of 98 NON INTRACTIVE, Resolution 3840 x 2160 (UHD-4K),Brightness 350 nit,Contrast ratio 1200:1,Panel type Non-glare, IP Rating IP5X,Connectivity HDMI 2.0(2), USB2.0(2),Dvi-D,Display Port,Stereo Mini Jack, Ext: RS232C(in/out), RJ45, Soc SSSP 6.0	R/O	Nos	0.00	0.00
439	Supply, Installation Testing & Commissioning of Full HD @ 60fps PTZ camera, minimum 20X Optical Zoom, min 100 Presets, Ethernet Out, HDMI Out, 3G-SDI Out, Audio In, IP/RS232/422 Controls, - 170° ~ +170° Panning angle, -30° ~ +90° Tilting angle , Should support PoE+. Should be CE, ROHS, BIS and FCC Certified.	R/O	NOS	0.00	0.00
TOTAL AMOUNT					0.00
K	Part-11 (Buy Back Item)				
440	Buyback items:- WING A Note: 1) The client reserves the right for hand over of any buy back items to bidder without assigning any reason thereof. The client reserves the right for any decision. 2) The Qty may vary for any buy back item as per actual site conditions. GIDC Office : Wooden Table (Working desk) : 1800 x 800 x 750 mm HT	20.00	Nos	0.00	0.00
441	GIDC Office : Chair	25.00	Nos	0.00	0.00
442	GIDC Office : Wooden Full Height storage	11.00	Nos	0.00	0.00
443	GIDC Office : Wooden Full Height storage	6.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
444	GIDC Office : Metal Full Height storage	1.00	Nos	0.00	0.00
445	GIDC Office : Low Height storage:1500 x 500 x 750 mm HT	2.00	Nos	0.00	0.00
446	GIDC Office : Metal Half Height storage	1.00	Nos	0.00	0.00
447	GIDC Office : Wooden Half Height storage:1200 x 500 x 750 mm HT	2.00	Nos	0.00	0.00
448	Cashier Cabin Wooden Counter:1500 x 600 x 900 mm HT	1.00	Nos	0.00	0.00
449	Cashier Cabin Chair :	1.00	Nos	0.00	0.00
450	Cabin : Main Table with side unit:1800 x 900 x 750 mm HT Laminate Finish table	4.00	Nos	0.00	0.00
451	Cabin : Half Height Back side unit :1800x500x 750 mm HT Laminate finish Storage	8.00	Nos	0.00	0.00
452	Cabin Chair	16.00	Nos	0.00	0.00
453	CM Cabin Full Height Storage :2200 x 500x 2100 mm HT Veneer Finish Storage	1.00	Nos	0.00	0.00
454	CM Cabin Table :1500x750x750 mm HT Laminate finish table	3.00	Nos	0.00	0.00
455	CM Cabin Center Table : 900x750x450 mm HT Glass top & Wooden finish bottom	3.00	Nos	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
456	CM Cabin ; Highback Chair	5.00	Nos	0.00	0.00
457	CM Cabin : Chair	5.00	Nos	0.00	0.00
458	CM Cabin Console Table	4.00	Nos	0.00	0.00
459	CM Cabin Sofa	2.00	Nos	0.00	0.00
460	Driver Room : C Shape sofa	1.00	Nos	0.00	0.00
461	Driver Room : Low Height Storage-1500 x 400 x 750 Ht Laminate finish storage	3.00	Nos	0.00	0.00
462	Driver Room : Workstation-1050 x 600 x 750 HT Laminate finish workstation	2.00	Nos	0.00	0.00
463	Driver Room : Table with side unit -1800 x 900 x750 Ht Laminate finish table & top glass	1.00	Nos	0.00	0.00
464	Driver Room : 3 seater sofa	2.00	Nos	0.00	0.00
465	Driver Room single seater sofa	2.00	Nos	0.00	0.00
466	Driver Room : Side Unit - 450 x 400 x 450 HT Laminate finish unit	2.00	Nos	0.00	0.00
467	All toilet block sanitary fittings like wash basin w.c. pan, Indian and European type flushing tank, Urinal, all type of cock, accessories, basin counter etc. (Male & Female toilet)	3.00	Job	0.00	0.00
468	Tiled or stone floors, wall tiled / any type of cladding material	881.00	Sq.mt	0.00	0.00



Renovation, Interior Furniture, Electrical, Fire Fighting, HVAC At Ground Floor-Wing A, GMDC, Khanij Bhavan, 132 Feet Ring Road, Near Gujarat University Ground, Vastrapur, Ahmedabad, Gujarat 380052

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
469	Existing All type of Door with frame all hardware's	41.00	Nos	0.00	0.00
470	Existing Glazing with frame work : Elevation facade & Atrium side	36.00	Sq.mt	0.00	0.00
471	Existing Electrical light fixtures, cables, trays etc	1.00	Job	0.00	0.00
472	Existing fabrication/ Steel structure / S.S. railing etc. work	1346.63	Kg	0.00	0.00
Total Amount					0.00

Sr. no.	Summary Sheet				Amount
A	Sub Total : Part - 1				0.00
B	Sub Total : Part - 2				0.00
C	Sub Total : Part - 3				0.00
D	Sub Total : Part - 4				0.00
E	Sub Total : Part - 5				0.00
F	Sub Total : Part - 6				0.00
G	Sub Total : Part - 7				0.00
H	Sub Total : Part - 8				0.00
I	Sub Total : Part - 9 (Rate Only Item)				0.00
J	Sub Total : Part - 10 (Rate Only Item)				0.00
	Total Amount (Rs.)				0.00
K	Sub Total : Part -11 (Less Bay back Amount)				0.00
	Grand Total Amount (Rs.)				0.00

GST Extra as per Govt. Norms