



Name of work: Interior Furnishing of ATPS Hostel & VIP Guest house at GMDC campus, Lakhpat, Kutchh.

PRICE BID

Sr. No.	Item Description	Qty	Unit	Rate	Amount
A	Part-1				
1	<p>Gypsum MR grade Ceiling : M/F Suspended MR Ceiling includes Gypserra™ Perimeter Channel {Material-GI(IS513),YS-260Mpa,Finish- Galvanised 150GSM(IS27)} is fixed along the perimeter of existing wall/ partition with the help of HILTI HPS-1 (6x40) impact anchor, at 600mm centres. Gypserra™ Ceiling Angle {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} is suspended by fixing it to the Gyproc® soffit cleat {GI(IS513)YS-260Mpa,Finish-Galvanised 150GSM(IS277)}. Soffit Cleat and Gyproc® Rawl Plug- Ø8x45mm {Material-IS 513 CR2 grade, Zinc coating (7 to 8 microns) pull out load-6.8kN for M30 concrete grade} creating 1220mm x 1220mm grid. Gypserra™ Intermediate channel {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277) } is fixed to the Gypserra™ Ceiling Angle with M6 x 12mm Hex Bolt & Hex Nut arrangement {Material-As per EN 10083 Finish – Zinc Plating} or with 2 Nos of Ø4.2x13 Gyproc® metal to metal screw {Material-Carbon steel EN-ISO 7049/50 Finish- Zinc Coating Thickness- 4.14micron.} The Gypserra™ Ceiling Section {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} is then fixed to the Gypserra™ Intermediate Channel {Material-GI(IS513),YS-260Mpa,Finish-Galvanised 150GSM(IS277)} with the help of Gyproc® Connecting Clip {Material-High carbon spring steel wire(BS970Gr.En42)-46-48HRC,Finish-Zinc plating 4-6 micron} and in direction perpendicular to the Intermediate channel at 457mm c/c. Single layer of 12.5mm tapered edge Gyproc® MR (conforming to IS 2095 Part 1:2011/ EN 520:2004, Type-A & H1/ASTM C1396) is then screw fixed to ceiling section with 25mm drywall screws {Material-Carbon steel EN-ISO 7049/50,Finish-Case hardened Grey Phosphating} at 230mm centres on ceiling section & 150mm at periphery of ceiling. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Gyproc® Pro-Fill Jointing compound (Conforms to ASTM C475), Gyproc® Joint Paper tape. Serrated section has effective thickness of 2T (2xdepth), better load carrying capacity, enhanced screw retention, Improved acoustic performance & fire resistance as compared to plain steel section. All Gypserra™ metal components are patent applied for.(Application No. 201741018271) The item includes providing and fixing trap door of size 600 X 1200 mm as per approved sample of Ceiling panels comprise of a powder-coated beaded steel frame with gypsum / plywood board door. Each panel features a push- latch closing mechanism with door retaining safety cable & hook.Suspenders from ceiling to support the frame and trap door firmly along with necessary hilti fastner, cleats, screws, angles, packing, , safety measures etc. complete work. Necessary cutting / providing openings in the ceiling for AC fixtures, grills, electrical fittings, or other utility services, hatch openings etc. shall be provided by the Contractor and cost of making such modifications shall be included in the price.</p>	884.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
2	<p>Full Height Gypsum Partition (60min. fire rating) : 100mm thick Gypserra™ stud partition which includes inner layer of tapered edge 12.5mm thick Gypboard® Plain (conforming to IS 2095 Part 1:2011, Certified board) of size 1219x2438mm and outer layer of tapered edge 12.5mm thick Gyproc® Fireline board of size 1219x2438mm is screw fixed to C-stud. 48x0.5mm Gypserra™ C-stud {Material-IS 513, Y/S-300Mpa, Finish - AZ150 (IS 15961)} placed at 610mm c/c in 50x0.5mm Gypserra™ {Material-IS 513, Y/S-300Mpa, Finish - AZ150 (IS 15961)} floor and ceiling channel. Floor & Ceiling channel is anchored to the floor & True ceiling using Gyproc® Rawl plug Ø8x45mm {Material-IS 513 CR1 grade, Zinc coating, Pull Out Load-6.8kN for M30 concrete grade} /Hilti X-GN20MX anchor fasteners at 600mm c/c in centerline manner. Floor channel to be wrapped with 70µ Self Adhesive LDPE moisture barrier film to further improve corrosion resistance performance. 12.5mm thick Gypboard® Plain board strip of 50mm width is placed between ceiling channel and RCC ceiling slab when deflection is more than 10mm & fire rating is more than 30min. A Gypserra™ noggin channel {Material-IS 513, Y/S-300 Mpa, Finish - AZ150 (IS 15961)} of 50x0.5mm width has to be provided at the horizontal joints of the two boards. First layer of Gyproc® boards to be screw fixed with Gyproc® drywall screws of 25mm at minimum spacing of 600mm at centre and 600mm at periphery. Second layer to be screw fixed Gyproc® drywall screws of 35mm at minimum spacing of 300mm at centre and 300mm at periphery. 50mm Glass wool slab of density 20kg/m³ shall be placed in metal framework. Glass wool holding clip should be used to hold Glass wool slab in its position. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Gyproc® Pro- Fill Jointing compound, (Conforms to ASTM C475), Gyproc® Joint Paper tape or fiber tape. The junction of the partition with masonry & all penetration through the partition has to be treated with Hilti/Pyroplex fire and acoustic sealant. All other detailing and specifications to be followed as per approved drawing of Gyproc. Note: Applicator need 60min. fire rating certificates from Gyproc. Rate shall include cost of making of all cut-outs for light fixtures, switchboards gadgets, gizmo, pelmets, grooves, beads and also provide support/template where ever required & For door frame fixing, storages, shelves, paneling etc extra Wooden members to be used shall be of CP teak wood only. Including skirting /MDF board/wooden skirting cut out as per EIC instruction at site. The rate shall be in sq.mt for all floors and at all heights including all costs. including ply base for fixing of TV or Overhead storage wherever required, The rates are also inclusive of necessary scaffolding, tools, tackles,, safety measures , Internal partial support (between two sturd) at 7' height. The shop drawing (or a sample mock of 5 Sqm minimum of the frame work and partition) shall be approved from EIC and Architect. All exposed corner shall be covered with perforated angle as per manufacturer's specifications or as directed by EIC. Partition ht will be measured from finish floor to false ceiling level only.</p> <p>Gypsum partition above FLC & True slab of 1275mm ht to be considered (for 5th floor) Gypsum partition above FLC & True slab of 1950mm ht to be considered</p>	54.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
3	<p>Thin Profile Glass Partition: Providing & Fixing of STL45 ie. Single glazed modular system consist of Aluminium section of 25*45*2.5 mm thick. All sections duly powder coated with 6063-T6 grade and required accessories ie glass to glass aluminium I sections, T section & 90 degree sections & Glass packing to adjust the floor level. Ceiling profile, Floor profile and wall profile are 25 mm visible face and 45 mm wide with 10mm toughen glass as per approved make & insertion of Thermoplastic gasket to adhere the glass firm & airtight. The sound reduction Value is from 32 to 35 Db. With 6 mm Groove inbuilt in system to accomodate the carpet & the uneven surfaces. Accessories/Hardware: neutral cure glazed & metal silicon sealant of approved make on the periphery of the glass & wood etc.</p> <p>Partition ht will be measured from finish floor to false ceiling level only. The rate shall be in sq.mt for all floors and at all heights including all costs. Glass width size shall be as per suggestion by EIC. Work complete including all type of material, fittings, fixtures, Finish, safety measures, loading, unloading, transportation, all leads, accessories, sample mockup, all floor, all levels, all heights etc. complete as per detailed drawings, specifications & instruction of Client/EIC.</p>	38.00	Sq.mt	0.00	0.00
4	<p>Thin Profile Double leaf glass door :</p> <p>Supply & Installation of Modular Aluminium Glass door frame of Kubik or equivalent make 45mm System, Using KOPS 001 & KOPS DF 103 (45mm x 25mm) for Glass door frame</p> <p>Doorframe Dimension – 45mm x 25mm.</p> <p>Finish – SILVER finish / Powder coating as per approved sample by Architect</p> <p>10mm thk. clear toughened Glass</p> <p>KUBIK Glass Hinge, HAFELE Open Door closer with saddle plate, KUBIK Mortise lock with handle (Handle Size 4'), KUBIK Door stoper</p> <p>Item includes all necessary fitting / fixing, fixtures of approved make complete as per specification, drawing, approval and instructions of the Architect/Client. Rate shall be inclusive of all material loading unloading at all height and all floor. Sample mock shall be approved from Architect/Client.</p>	22.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
5	<p>Thin Profile Single leaf Glass Door: Supply & Installation of Modular Aluminium Glass door frame of Kubik or equivalent make 45mm System, Using KOPS 001 & KOPS DF 103 (45mm x 25mm) for Glass door frame Doorframe Dimension – 45mm x 25mm. Finish – SILVER finish / Powder coating as per approved sample by Architect 10mm thk. clear toughened Glass KUBIK Glass Hinge , HAFELE Open Door closer with saddle plate , KUBIK Mortise lock with handle (Handle Size 4'), KUBIK Door stoper.Item includes all necessary fitting / fixing, fixtures of approved make complete as per specification, drawing, approval and instructions of the Architect/Client. Rate shall be inclusive of all material loading unloading at all height and all floor. Sample mock shall be approved from Architect/Client.</p>	6.00	Sq.mt	0.00	0.00
6	<p>Frosted sparkling glass film (Colour film) : Providing and fixing frosted glass film of approved make Translucent, cast PVC, self-adhesive vinyl, special CRYSTAL-effect film to reproduce Sand-blasting effect on glass with customised designs. MCS warranty of 3 (if exposed to direct sunlight) to 10yrs (indoors) must be endorsed by manufacturer. Rate shall be inclusive plotter cutting design as per Architect/Client suggestion. Contractor shall provide shop drawing for approval of Architect/Client.work complete including all type of tools, tackles, scaffolding etc complete as per suggestion of Architect/Client. If in case any application finishing will not as per satisfaction contractor shall remove all film at their cost. Contractor shall do a sample mock of 5 Sqm minimum of glass film), shall be approved from Architect/Client.</p>	24.00	Sq.mt	0.00	0.00
7	<p>Woody ACP ceiling/cladding with grooves: Providing and fixing 3 mm thick ACP sheet (Woody finish- PVDF coating - 0.25 mm top layer) with necessary framing work of aluminium alloy 6005 T5 Size as per design. Spacer Tape , wood screw , silicone sealant ,including all type of fittings , accessories etc complete. Including cost of all type of tools, tackles, all labour, scaffolding etc. Including cost of all type of materials, transportation. Including cost of cleaning etc. Work complete for at all floor, all level, all depth, all Height, all lead and lift etc. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. The whole work is to be executed with a guarantee of 10 years. Sample mock shall be approved from Architect/EIC. Basic rate ACP sheet Rs. 160/ sq.ft.</p>	122.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
8	<p>VNR Laminate Panelling : Providing & fixing 12mm thick fire retardant marine plywood as per IS 710:2010 and IS 5509:2000 fixed on frame work finish with 1mm thick Laminate finish. The frame work shall be made from square hollow aluminium anodised section size of 50x50x1.5 mm & 25x50x1.5 mm of approved make conforming to IS code. The framework shall be fixed as per drawing vertically @ 600 mm c/c & horizontal 600 mm c/c horizontally. All ply/wooden shall be treated with anti- termite treatment. Measurements for paneling work to be recorded upto finished false ceiling level only irrespective of aluminium frame work, which shall be provided from gr. level to RCC slab / beams soffit level. Rates shall also be inclusive of cost of making CNC/engraving /cut outs/ openings for electrical fixtures, tube lights /air-conditioners ,grills, diffusers etc & providing additional sections for strengthening around the openings/cutouts additional support for fixing of patch fittings for doors, making grooves between wall & board, in filled with termite treated wooden members if required or as per drawing /instruction of EIC. and no extra payment shall be considered for additional sections provided. All curved surfaces, recesses, waffles shall be part of the paneling including openable shutter wherever required area and finished with the same material. Work complete including all type of material, fittings , fixtures, Finish, loading , unloading , transportation, all leads ,accessories, groove, adhesive ,tape, headless nails, sample mockup, all floor , all levels, all heights etc complete as per detailed drawings ,specifications & instruction of Client/EIC. only the clear elevation area of finished plywood wall paneling with Laminate shall be measured and paid. sample mock shall be approved from Architect/Client. Equivalent to VNR Series Laminate.</p>	30.00	Sq.mt	0.00	0.00
9	<p>Cement sheet paneling/ Shera Boards (at ATPS VIP Rooms Bed Back Wall): " -----Do -----" as per above item specification for complete work . using 6 mm thick cement sheet board instead of veneer for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including CNC / Engraving and all costs.</p>	36.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
10	<p>Gypsum panelling: Gypsum panelling :The M/F wall lining includes 12.5mm Gyproc® Quattro Gypsum Board, screw fixed with drywall screws of 25mm at 300mm centers to one side of 45X18X0.5mm Gypliner ceiling channel (0.5mm thick having 18mm flange each made of GI Steel) placed at 600mm center to center in 195X29.5X0.9mm fixing bracket at 900mm c/c with 25X25X0.5mm Gypliner angle at bottom and top of the channel such a manner that joints staggered to avoid leakage through joints. Fixing strip of 75X0.5mm should be installed at horizontal joint of boarding. Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look which includes filling and finishing with Jointing compound and Joint Paper tape. 50mm Glasswool of density 20kg/m3 should be placed in metal frame.Necessary fabrication with anticorrosive paint work , scaffolding, anchor fasting , bolting HILTI or equivalent make with testing certified in scope of contractor)Rate shall include cost of making of all cut-outs for light fixtures, switchboards gadgets, gizmo, pelmets, grooves, beads cut out as per EIC instruction at siteThe rate shall be in sq.mt for all floors and at all heights including all costs. The shop drawing (or a sample mock of 5 Sqm minimum of the frame work and partition) shall be approved from EIC and Architect. Panelling item including openable shutter wherever required area and finish with the same material. Only the clear elevation area shall be measured and paid.</p>	185.00	Sq.mt	0.00	0.00
11	<p>Ply palmet : Providing and fixing wooden pelmets of upto 200 mm x 300 mm L shape made of 19mm thick ply as per IS 710 and beading of 4mm thick and 25mm wide Ghana Teak wood for projection screen. Rate to be inclusive of lipping, cutting, wastages, necessary fixtures, nails, adhesives, necessary scaffolding, fixing at all heights and for all floors as per drawing and approved sample etc should also take load of all the all roller blinds.</p>	219.00	Rmt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
12	<p>Roller Blinds : Providing and fixing blinds as per approved make as per suggested shade & spring drive system with steel ball chain/one touch with speed control action roller blind with end brackets with head rail, components, bottom bar. Fabric : screen classic 1% to 3% .Fabric value : 470 Gsm ,Thickness : 0.60 to 0.70 mm Construction: 75 % PVC & 25 % Polyster Fabric to be as per approved sample. All the work complete as per the detailed drawing , mockup sample and instruction of Architect/EIC. All complete as per approval of designer. The mode of Measurement: The size of the blind will be measured from end to end bracket (Left to Right bracket) height will be measured from top of the pelmet to sill bottom level and clear opening size only there will be not extra payment towered overlapping.& mockup sample approved by the Architect/ EIC.</p>	37.00	Sq.mt	0.00	0.00
13	<p>Black out curtain: Providing and fixing Blackout curtain/blinds as per approved make as per suggested shade & spring drive system with steel ball chain/one touch with speed control action roller blind with end brackets with head rail, components, bottom bar. Construction: 100 % Polyster Coating: Blackout 3 pass foam coating Thickness : 0.60 mm Fabric value: 390 Gsm , Fabric to be as per approved sample. All the work complete as per the detailed drawing , mockup sample and instruction of Architect/EIC.All complete as per approval of designer. The mode of Measurement: The size of the blind will be measured from end to end bracket (Left to Right bracket) height will be measured from top of the pelmet to sill bottom level and clear opening size only there will be not extra payment towered overlapping.& mockup sample approved by the Architect/ EIC.</p>	12.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
14	<p>Eyelet Curtain : For Suite room & Other room Supply and installation of Eyelet curtains (3 Plit curtain) of approved make as per architect selection . Double rod with front sheer curtain and back main curtain as per selection of architect. Work complete incldung all type of stiching , fixing , accessories ,nclusive of installation, material cost, labor, wastage, operating system all tools tackles, scaffoldings, hardware at all floors, all levels and heights, necessary edge binding with approved fabric and thread of colour similar to the colour of the blinds. Same rate shall be applicable for all heights and for all floors. height will be measured from top of the palmet to sill bottom lvl.height will be measured from top of the palmet to sill bottom lvl. MAIN FABRICS + SHEER FABRICS+ BLACKOUT : rate of Fabric is 900 / Rmt .</p>	247.00	Sq.mt	0.00	0.00
15	<p>Eyelet Curtain : For other area Supply and installation of Eyelet curtains(3 Plit curtain) of approved make as per architect selection . "-----Do-----" as per above specification for complete work. MAIN FABRICS : rate of Fabric is 450 / Rmt.</p>	371.00	Sq.mt	0.00	0.00
16	<p>Writable with magnetic glass board : Providing & fixing 04 mm SGG Pristine Tan Glossy Finish writable & Magnetic CEP board on existing partition/wall as per approved sample by Architect/Client. work Including cost of all type of fittings , accessories , tools, tackles, all labour, scaffolding, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. etc.work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.Only the clear elevation area shall be measured and paid.</p>	2.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
17	<p>PA cabin table unit : all top 25 mm thick Main Table of size : 1500mm x 750mm x 750ht, Side storage : 1050mm(L) x 450mm(D)x 750mm(H), Pedestal Unit-400x470X545.</p> <p>Providing and fixing table unit consist main table, side table ,back storage with pedestal unit with all necessary accessories keyboard, CPU stand ,cable manager, modesty panel etc with all required necessary accessories. All finishes VNR laminate,powder coating /anodizing shade shall be approved by architect. Rate shall inclusive of mock up sample providing and fixing at site of unit for approval of architect.Contractor shall submit as per site condition shop drawing for modular furniture layout and send detail drawing for each furniture with 3D and plan section for approval of architect/client.</p> <p>Table Top:- 25 mm thick postfoam top (reverse bull nose) with 1 mm thick VNR laminate finish as per approved make and sample by Architect/ Client. Flip Open:-450mmx150mm Aluminium Powder coated flip open above the table top with build in Soft closing mechanism and Termination Box below table top to accommodate electrical and data socket.Vertical cable riser consider below the table top for wire entry from the floor.</p> <p>Understructure; Work top is supported on 18mm Gable end/MS/Aluminium powder coated legs with Supporting Beams. Front Modesty, Laminated Plyboard Modesty as per drawing.</p> <p>Side storage: top is 36mm The structure is made out of 18mm thick pre-laminated boards (PLB). The shelves are made out of 18mm(PLB), which are adjustable in height. The shutters are made out of 18mm(PLB), and fitted by hinges. Reverse waterfall handles,normal locking unit and levelers are considered. storage with sliding storage.</p> <p>Prelam Pedestal : The unit to be build prelaminated particle board having 2 drawers +1 filing unit with normal lock and reverse waterfall handle is considered.</p> <p>All the exposed edges are sealed with 2mm thick PVC Imported edge banding on sides and bottom. The top and drawer facia are sealed with 2mm thick PVC edge. The drawer unit consists of 1 box drawer and 1 file drawer. The drawer box is fitted with telescopic channel Hettich or Haffle make for free movement. The drawer unit is provided with central locking system, where in the drawer are locked with one key.SS 304 recessed handles are provided for easy opening and closing of drawer. The drawer unit is fitted on castors (optional) for easy mobility. PVC edge banding are imported from Rehau or Dolken of Germany. The complete furniture unit is factory assembled with knock down fittings.Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, monocoat polish, placing at all floors and for all leads, all accessories as described in item description. Equivalent to VNR Series Laminate.</p>	1.00	Per Unit	0.00	0.00
18	<p>cabin table unit : all top 25 mm thick Main Table of size : 1500mm x 750mm x 750ht, Side storage : 1050mm(L) x 450mm(D)x 750mm(H), Pedestal Unit-400x470X545. Back side unit : 1500 x 450 x 750 mm " -----Do-----as per above specification for complete work.</p>	1.00	Per Unit	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
19	<p>Reception Table : Table of size : 1800 mm x 750mm x 1050 mm ht Providing and fixing Reception table unit consist main table with pedestal unit with all necessary accessories keyboard, CPU stand , cable manager, etc with all required necessary accessories. Front panel top: 15-18 mm thick Artificial stone / Quartz with ply structure finish with required all edge finish as per given detail Working Desk Top: 25 mm th post forming top with 1 mm thick VNR laminate finish as per approved make and sample by Architect/ Client. Flip Open:-450mmx150mm Aluminium Powder coated flip open above the table top with build in Soft closing mechanism and Termination Box below table top to accommodate electrical and data socket.Vertical cable riser consider below the table top for wire entry from the floor. Table front: As per detail drawing and reference image made from Artificial stone / 4 mm thick veneer with polish , backlit and logo engraving work complete as per detail drawing The work shall be done as per the detailed drawing , specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives consumable hardware & required SS 304 grade hardware/ accessories, grooves pvc edge banding , etc of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Basic rate of stone is 300/ Sq.ft .</p>	1.00	Nos	0.00	0.00
20	<p>Reception Table Table of size : 1500mm x 600mm x 1050 mm ht Providing and fixing Reception table unit consist main table with pedestal unit with all necessary accessories keyboard, CPU stand , cable manager, etc with all required necessary accessories. ---Do---as per above specification for complete work. Only Finish : Comprising from BWR ply / wood / VNR laminate finish instead of stone.</p>	1.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
21	<p>Meeting room table: Table size :3000L x 1500B x 750H mm</p> <p>Providing and fixing Meeting room table as per detail shape and size table unit consist table with all required necessary accessories.</p> <p>Table top to be made up of 35 mm thk prelaminated particle board with reverse waterfall edgebanding.(only user side)Flipopen (450mm x 150mm)Aluminium Powder coated Flip open with a build Soft closure with Termination box below the table top to accommodate electrical and data socket.</p> <p>Raceway MS Powder coated Horizontal raceway considered below table top with Intermidate legs provided to allow the LAN & electrical Cables.</p> <p>Understructure Work top is supported on MS powder coated leg with MS powder coated Supporting Beams / solid wooden leg with polish as per drawing.</p> <p>Rate inclusive of providing and fixing as per requirement of socket and quantity Pop up tabletop electrical WIRE MANAGEMENT BOX SS finish. The work shall be done as per the detailed drawing , specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives consumable hardware & required SS 304 grade hardware/accessories, grooves pvc edge banding , etc of approved make for all floors, monocoat polish, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.</p>	1.00	Nos	0.00	0.00
22	<p>Console : @1500 x 400 x 600 mm</p> <p>Providing & fixing Console complete as per drawing/Ref Image . made from up of 19 mm thick BWR grade ply & finished of Laminate as per approved make and shade and solid wooden leg with matt finish monocoat polish as per drawing. Rate shall be inclusive of providing, fixing all necessary brass satin finish nickel plated/ S.S 304 grade (hardware from Hettich like Auto Hinges, handle, Rod locks, Multipurpose lock, Rate shall be inclusive of internal shelves of 19mm thick IS 303 BWR ply and laminate , PVC edge beading . All external & internal exposed woodwork to be finished in PU semi gloss paint finish polish as per specified item's manufacturer's specifications.Rate shall inclusive of providing mock up sample for approval of architect. Equivalent to VNR series laminate.</p>	2.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
23	<p>4'ft height storage: 450 mm Depth Storage unit top made up of 25 mm thk MDF Exterior grade The top has a post formation round edge finish with both side laminate .Storage body is made of 18mm thick MDF top with exterior grade finish with both side 1 mm th laminate . Shutter finish with both side 1 mm th laminate. The back of the unit is made from 9mm prelaminated board. All the exposed edges are with 2mm PVC edge Imported banding & sealed edges are with 0.8mm thick PVC Imported edge banding. Having premium lock with wave key technology and side and hinged shutters are sealed with 2mm thick PVC edge banding.SS 304 recessed handles are provided for easy opening and closing of shutter. The units are assembled by knock down fittings such as Minifix & Dowels. All the hardware and Hinges are from Enox/Ebco. PVC edge banding are imported from Rehau or Dolken of Germany .Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, monocoat polish, placing at all floors and for all leads, all accessories as described in item description. As approval of EIC. All the work complete as per the detailed drawing , mockup sample and instruction of Architect/EIC. Work complete as per the instruction of EIC.Contractors shall submit as per site condition shop drawing for modular furniture layout and send detail drawing for each furniture with 3D and plan section for approval of architect/client Equivalent to VNR series laminate.</p>	2.00	Sq.mt	0.00	0.00
24	<p>Full Height Storage with Laminate Finish : 450 mm Depth Storage Comprising from IS 303 BWR 19 mm thick and 12 mm ply, finish with 1 mm thick Laminate finish as per approved make and shade by Architect. Solid Shutter : 25 mm thick comprising from IS 303 BWR ply & finish with 1 mm thick Laminate . Shelf: 19 mm thk IS 303 BWR ply finish with both side approved laminate. Inner area shall be finished with linear laminate. Ledge/Niche comprising from HDF / Lacquered glass finish w, required lighting arrangement. The work shall be done as per the detailed drawing , specifications, sample approved and as directed by the Architect/Client. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles, adhesives , grooves , consumable hardware & required SS 304 grade hardware/accessories , Profile handle, Wooden frame, monocoat polish, pvc edge banding of approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this. Equivalent to VNR series laminate.</p>	6.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
25	Vanity counter Storage with VNR laminate finish : " -----Do----- as per above specification for complete work . Using 1 mm thick VNR laminate instead of Veneer . Basic Rate of VNR laminate is 50/ Sq.ft	19.00	Sq.mt	0.00	0.00
26	Vanity counter Facia with VNR laminate finish : " -----Do----- as per above specification for complete work .	4.00	Sq.mt	0.00	0.00
27	Wooden open shelf with polsih : " -----Do----- as per above specification for complete work .	4.00	Sq.mt	0.00	0.00
28	Pantry below storage : Providing, making, fixing as per detail drawing made from 19 mm IS 710 BWP ply structure and both side 1 mm th laminate finish shall be of approved make & shade and as per the detail drawing. All the edges of ply shall be covered with Laminate finish Rate shall also inclusive of all necessary brass satin finish nickel plated/S.S 304 grade hardware like Hinges, locks,6"handle , 75 mm tower bolts, ball catches/Magnet, The rate shall be inclusive of shelf both side laminated finish and as per detail drawer unit with SS 304 grade kitchen basket as per selction by architect The rate shall be in sqm of elevation area for all floors and at all heights including all costs complete as per the Architectural drawings & instructions.Only the elevation area of the storage unit will be measured and paid for. Item for laminate fixing and polishing is included in this item. Approval of all loose material (sample of materials to be used) & raw manufacturing to be got approved in advance from EIC & Architect prior to the final production of the work. Manufacturing shall in parts or as whole as per the requirements & or assembled at site as per the requirement and directed by EIC & Architect. All material to be used shall be as per the drawings & confirm to the relevant detailed material specifications of this document. The work shall be measured & paid in sqm The rates shall be inclusive of all wastages, material, labor, transportation, loading, unloading, fixing in position, etc. complete to the satisfaction of the Architect and EIC. The mock-up of 1 unit shall be approved from EIC and Architect prior to the final production. Equivalent to VNR series laminate.	6.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
29	<p>Pantry above storage -350DX600 H: Providing, making, fixing as per detail drawing made from 19 mm IS 710 BWP ply structure aand both side 1 mm th laminate finish shall be of approved make & shade and as per the detail drawing. All the edges of ply shall be covered with Laminate finish Rate shall also inclusive of all necessary brass satin finish nickel plated/S.S 304 grade hardware like Hinges, locks,6"handle , 75 mm tower bolts, ball catches/Magnet, The rate shall be in sqm of elevation area for all floors and at all heights including all costs complete as per the Architectural drawings & instructions.Only the elevation area of the storage unit will be measured and paid for. Item for laminate fixing and polishing is included in this item. Approval of all loose material (sample of materials to be used) & raw manufacturing to be got approved in advance from EIC & Architect prior to the final production of the work. Manufacturing shall in parts or as whole as per the requirements & or assembled at site as per the requirement and directed by EIC & Architect. All material to be used shall be as per the drawings & confirm to the relevant detailed material specifications of this document. The work shall be measured & paid in sqm. The rates shall be inclusive of all wastages, material, labor, transportation, loading, unloading, fixing in position, etc. complete to the satisfaction of the Architect and EIC. The mock-up of 1 unit shall be approved from EIC and Architect prior to the final production. Equivalent to VNR series laminate.</p>	5.00	Sq.mt	0.00	0.00
30	<p>Coffee table- 750 mm dia top & ht-750 mm (size may be vary as per slection by 100 -200 mm)Supplying and placing Coffee table as per approved selection by Architect/ Client. Equivalent make as per approved make list .Table top finish as per selection Work complete including all necessary hardware and fittings , mock up sample, loading,unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client Basic rate of table Rs. 12000/- Nos.</p>	24.00	Nos	0.00	0.00
31	<p>Centre table Type 1: Centre table two nos unit pair - 1 unit- 800 mm top & 380 mm ht /2 unit- 500 mm top & 500 mm ht (size may be vary as per slection by 100 -200 mm) Supplying and placing centre table as per approved selection by Architect/ Client. Equivalent make as per approved make list .Table top finish as per selection Work complete including all necessary hardware and fittings , mock up sample, loading,unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. basic rate of table Rs.13,500/-Pair</p>	8.00	Pair	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
32	Corner table Type 1: - 500mm top & 480 mm ht (size may be vary as per slection by 100 -200 mm): Supplying and placing corner table as per approved selection by Architect/ Client. Equivalent make as per approved make list .Table top finish as per selection Work complete including all necessary hardware and fittings , mock up sample, loading,unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. basic rate of table Rs.7,500/-Nos.	16.00	Nos.	0.00	0.00
33	Sofa (One Seater) : @ 900(L) x 870 mm (B) x 800 mm (H): comprising up of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC all external & internal exposed woodwork to be finished in PU semi gloss finish polish. .The work shall be done as per drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 1000 Rmt.	16.00	Nos	0.00	0.00
34	Sofa (two Seater): 1500mm (L) x 870 mm (B) x 800 mm (H) "-----Do-----" as per above specification for complete work. Basic Rate of Fabric : 1000 Rmt	2.00	Nos	0.00	0.00
35	Sofa (three Seater): 2100mm (L) x 870 mm (B) x 800 mm (H) "-----Do-----" as per above specification for complete work. Basic Rate of Fabric : 1000 Rmt	8.00	Nos	0.00	0.00
36	Lounger chair : The seat shall 150 mm th 40 density & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC all external & internal exposed woodwork to be finished in PU semi gloss finish polish. .The work shall be done as per the drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric :1000 Rmt	2.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
37	<p>Chair Type-5A (Other area Chair) - Model equivalent to Vento 02 : Mid Back Revolving Chair as per approved make list.</p> <p>* Frame in Moulded Nylon PP with Black Mesh & PU * Moulded Cushion on Seat. * Cushion Lumber Support. * Adjustable Arms with PP Pad .* Chrome Base.* Synchronized Mechanism with Single Lock & Gas Lift.</p> <p>Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	43.00	Nos	0.00	0.00
38	<p>Wooden seating benches : 860 x 380 x 450 mm:</p> <p>Providing, making, and placing in position with all necessary accessories. Seat, Back & Base: wooden/ply 25 mm thick with Polish finish and 40 density PU foam with fabric finish as per selection of architect. All wooden surfaces are to finished with PU polish. Work complete including all type of material, fittings, fixtures, Finish, loading, unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, etc complete as per drawings, specifications & instruction of Client/EIC. seating made from 40 density PU foam with fabric finish as per selection of architect</p>	5.00	Nos	0.00	0.00
39	<p>Outdoor Seating Chair and Table Set : 2 Single Seater Chairs + 1 Table</p> <p>Patio Seating Chair and Table Set Outdoor Balcony Coffee Table Set Furniture with 1 Table and 2 Chairs Set Braid & Rope (Grey)</p> <p>Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	4.00	Unit	0.00	0.00
40	<p>Magazine rack : 18" W x 55 " HT</p> <p>Providing and fixing rack comprising from Prime Quality CRCA Steel Display Floor Standing /Tabletop Stand (4 Shelf, 18 Inch, Grey, Mt-18), Tiered Shelf as per approved sample by Architect.</p> <p>Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	2.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
41	<p>Dining Table : 2800 x 1200 x 750 mm : Guest house Providing & Fixing of DINNING TABLE as per detail drawings/ Ref Image. Top :75 mm th table top finish with 15 mm thick Artificial stone fixed on BWP ply with edge reverse bull nose as per refernce image Structure : Solid wooden with approved polish Leg : Solid wooden as per detail/refernce image with approved polish (Basic Rate of Stone is Rs 300 Per Sq.Ft.) Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	2.00	Nos	0.00	0.00
42	<p>Dining Table : 1500 x 900 x 750 mm : Guest house Providing & Fixing of DINNING TABLE as per detail drawings/ Ref Image. "-----Do-----as per above specification for complete work.</p>	4.00	Nos	0.00	0.00
43	<p>DINNING CHAIR : Guest house Providing & Fixing of DINNING CHAIR as per detail drawings/ Ref Image. Structure : Solidwood with approved polish Finish : Fabric Finish . (Basic Rate of Fabric is Rs 1000 Per Meter) Leg : Wooden Leg . Finish : Approved Shade Polish on Wooden Leg Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	32.00	Nos	0.00	0.00
44	<p>Dining table chair : Other area Supplying and placing Fix Chair with Seat. as per approved and selection by Architect/ Client. Make: Qedo make, Model no. Casper Cafe Fully Polypropylene Chair or equivalent make as per approved make list .tapperd Legs at the base duly polished. Work complete including all necessary hardware and fittings , mock up sample, loading,unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client</p>	56.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
45	<p>SERVING UNIT WITH ARTIFICIAL STONE TOP : Size: 3500mm x 500mm Providing Fixing of SERVING UNIT WITH 15 mm th ARTIFICIAL STONE TOP with required edge finish as per detail drawings/ Ref Image. Structure : BWP Plywood inside: 0.8mm Thk off white Laminate. Outside:Veneer finish as per selection Drawers: Tendom Drawers Shutters: Openable Shutter Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	1.00	Nos	0.00	0.00
46	<p>STUDY & LIVING CHAIR Providing & Fixing of STUDY CHAIR as per detail drawings / Ref Image. Structure : Solidwood with approved polish Finish : Fabric Finish ; Basic Rate of Fabric is Rs 1000 Per Meter Leg : Wooden Leg Finish : Approved Shade Polish on Wooden Leg Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	4.00	Nos	0.00	0.00
47	<p>TV UNIT CUM STUDY UNIT : 1500 x 550 x 750 mm : Suit room Providing & Fixing as per detail drawings/ Ref Image. Top- 35 mm th top finish with 15 mm thick Artificial stone as per approved sample by Architect. As per detail edge finish complete Basic rate of stone is 150/ Sq.ft Structure- BWR Grade Plywood Inside : 0.8 mm Thk Off White Laminate Outside : Veneer finish as per selection Wall dado skirting 75 ht Veneer finish as per selection Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	8.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
48	<p>Wardrobe : Suit room Providing, making and fixing wardrobe units in position as per drawings. Front solid shutter : 25 mm thick IS 303 BWR ply with both side Veneer finish with polish Back side : 12 mm thick IS 303 BWR ply with one side Veneer finish with polish Bottom & Side , shelves/Divider : 303 BWR ply with Veneer finish with polish Dawers : 2 nos Hardware : Including hanging ss rod with fixing All necessary S.S 304 grade (hardware from Hettich like Auto Hinges, handle, Multipurpose lock, Telescopic channel, S.S. pipe oval Hettich (047 615) , tower bolts, ball catches/Magnet, hydraulic hinges etc as per approved sample. Skirting : 75 mm ht skirting with Veneer finish. Work complete including all type of material,Haffele/ Hettich fittings , fixtures,Finish, loading , unloading ,transporation, all leads ,accessories, sample mockup, all floor , all levels, all heights ,necessary grooves etc complete as per detailed drawings ,specifications & instruction of Client/EIC Basic Rate for material only veneer - 120/Sqft.</p>	8.00	Sq.mt	0.00	0.00
49	<p>LUGGAGE RACK : Size : 1500 mm x 600 Providing & Fixing of LUGGAGE RACK as per detail drawings/refrence image Material : BWR Grade Plywood with Outside : Slected veneer with approved polish. Top-25 mm th veneer finish top with SS solid bend inlay on top as per detail drawing Drawer: 1 no with veneer finish Ledge with skirting : veneer finish 75 mm ht Work complete including all necessary ,hardware(hafle/hettich) , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	4.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
50	<p>LUGGAGE RACK : Size : 900 mm x 600 Other rooms</p> <p>Providing & Fixing of LUGGAGE RACK as per drawings/Ref image.</p> <p>Material : MR Grade Plywood with VNR laminate finish</p> <p>Work complete including all necessary Alluminium strips ,hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description.</p> <p>Work complete as per the detailed drawing and instruction of Architect/Client.</p>	48.00	Nos	0.00	0.00
Total Amount					0.00
B	Part-2				
51	<p>Dressing Mirror with Profile frame : Size @600 x 1500 mm</p> <p>Providing & Fixing of DRESSING MIRROR as per detail drawings/ Ref Image.</p> <p>Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	28.00	Nos	0.00	0.00
52	<p>Double Bed with Headboard : Suit room : 6' 2 " x 7' 2 "</p> <p>Providing & Fixing of BED WITH HEADBOARD as per detail drawings/Ref Image.</p> <p>Material : MR Grade Plywood , Structure : Solid wood with approved polish.</p> <p>Head board and side finish-fabric Basic rate of fabric 1000 per Meter</p> <p>Drawers : N/A</p> <p>Storage : N/A</p> <p>Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	4.00	Nos	0.00	0.00
53	<p>BED SIDE TABLE :450 x 450 mm : Suit room</p> <p>Providing & Fixing of BED SIDE TABLE as per detail drawings/Ref image.</p> <p>Material : Solidwood (Mango and sesame) with approved polish</p> <p>Drawers : 2 Nos. Hardware : Hafele/Hettich</p> <p>Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	8.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
54	<p>ARM CHAIR : Suit Room IMPORTED RECLINER CHAIR WITH OTTOMAN (108 G ALPHA) RECLINER CHAIR SIZE (L - 32" / D - 36" / SH - 18" / BH - 40") OTTOMAN SIZE (L - 21" / D - 17" / H - 17") Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	2.00	Nos	0.00	0.00
55	<p>STUDY TABLE : 1200 x 600 mm : Providing & Fixing of TV UNIT CUM STUDY TABLE as per drawings/Ref image. MR Grade Plywood with Outside : 1 mm Thk Approved Shade Laminate. with PVC edge finish Drawers- 2 Nos Hardware : Haffele/Hettich Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	28.00	Nos	0.00	0.00
56	<p>Wardrobe : other room Providing, making and fixing wardrobe units in position as per drawings. Front solid shutter : 25 mm thick IS 303 BWR ply with both side VNR laminate finish Back side : 12 mm thick IS 303 BWR ply with laminate finish Bottom & Side , shelves/Divider : 303 BWR ply with both side VNR laminate finish Drawers : 2 nos Hardware : Including hanging ss rod with fixing All necessary S.S 304 grade (hardware from Hettich like Auto Hinges, handle, Multipurpose lock, Telescopic channel, S.S. pipe oval Hettich (047 615) , tower bolts, ball catches/Magnet, hydraulic hinges etc as per approved sample. Skirting : 75 mm ht skirting with VNR laminate. Edge finish : All exposed edges shall be finish with matching PVC edge finish Work complete including all type of material, Haffele/ Hettich fittings , fixtures, Finish, loading , unloading , transportation, all leads , accessories, sample mockup, all floor , all levels, all heights , necessary grooves etc complete as per detailed drawings , specifications & instruction of Client/EIC Basic Rate for material only VNR laminate-55/-Sq.ft</p>	51.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
57	SINGLE SIZE BED WITH HEADBOARD : Rooms Providing & Fixing of SINGLE SIZE BED WITH HEADBOARD (SOLIDWOOD FINISH) as per drawings/Ref image. Structure : Solidwood with approved polish . Drawers : N/A. Storage : N/A Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	48.00	Nos	0.00	0.00
58	BED SIDE TABLE : 450 x 450 mm : Rooms Providing & Fixing of BED SIDE TABLE as per detail drawings/Ref image. Material : Solidwood (Mango and sesame) with approved polish Drawers : 2 Nos. Hardware : Hafele/Hettich Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	48.00	Nos	0.00	0.00
59	BED CENTER TABLE : 900 x 450 mm : Rooms " -----Do-----" as per above specification for complet work.	24.00	Nos	0.00	0.00
60	STUDY TABLE/ TV unit / Pantry counter : 2700 x 600 mm : Rooms Providing & Fixing of TV UNIT CUM STUDY TABLE as per drawings/Ref image. MR Grade Plywood with Outside : 1 mm Thk Approved Shade Laminate. with PVC edge finish Drawers- 2 Nos, Hardware : Hafele/Hettich Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	24.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
61	<p>STUDY CHAIR ; Rooms Providing & Fixing of STUDY CHAIR as per detail drawings / Ref Image. Structure : Solidwood with approved polish Finish : Fabric Finish ; Basic Rate of Fabric is Rs 800 Per Meter Leg : Wooden Leg Finish : Approved Shade Polish on Wooden Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	48.00	Nos	0.00	0.00
62	<p>Wooden ledge : Providing & Fixing of Wooden ledge as per detail drawings/Ref image. Material : Solidwood (Mango and sesame) with approved polish Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	12.00	Rmt	0.00	0.00
63	<p>Metal cupboard with storage for ATPS Hostel: Supplying and installing Cupboard: size: 1850mm x 900mm x 480mm Welded Construction 0.8 mm thk (±0.08mm) CRCA* for Structure (20 guage) 1 mm thk (±1mm) High yield strength CRCA** for door (20 guage) CRCA D grade as per IS:513 CRCA D grade high yeild strength as per IS : 513 Locking : Three way locking mechanism with shooting bolt Shelving : Height wise fixed shelf mounting Uniformly Distributed Load Capacity per each full shelf is 40 Kg. maximum 3 nos. of adjustable full shelf Box file A4 size (85W x 345H x 285D) can be stored vertically on three shelves and the clear space above fourth shelf is 240mm. Leveler :M10 screw type leveler with hex plastic base Finish : Epoxy powder coated to the tickness of 50 microns (±10). Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	112.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
64	<p>Waiting lounge beam seating : Three Seater Tandem Providing and fixing of ERGO Waiting Lounge Tandem , Fully Chrome Plated Frame, with Arms. As per approved make & sample by Architect. Work complete including all necessary hardware , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	2.00	Nos	0.00	0.00
65	<p>Double Bed mattress size for Suite Room - 6' x 7' x 8" Mattress of Kurlon, Sleepwell, Springfit,Wakefit, Sleepy cat, Spring Air. or as per approved make and sample by Architect . Model equivalent to Kurlon- DOUBLE POSTURE : BONNELL P.U. FOAM BOTH SIDE (10 year) Mattress comprising from Bonded foam with softy sandwich layer of 100mm thick with 50mm thick softy foam which is from standard make, Both foam are fix with standard glue with both side kwilted cotton fabric cover, Bed all edges are stitch with piping finish with standard finishing, Cotton kwilt of Dark colour decorative shade require & mockup sample approved by the Architect/ EIC. Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transporation, , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per drawings ,specifications & instruction of Client/EIC.</p>	4.00	Nos	0.00	0.00
66	<p>Single Bed Mattress size - 3' x 6'6" x 6" "-----Do -----" as per above specification for complete work.</p>	104.00	Nos	0.00	0.00
67	<p>Pillow : 17" x 27" Providing and supplying standard make full size recron pillow . Pillow cover stitched properly with standard stitching. Pillow of standard quality with stadard make. Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per Shop drawings ,specifications & instruction of Client/EIC.</p>	112.00	Nos	0.00	0.00
68	<p>CUSHION : 16 " x 16" with cover Providing and supplying Cushion (Recron) as per approved make & Sample Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per Shop drawings ,specifications & instruction of Client/EIC.</p>	79.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
69	Pure Shield Quilted Cotton Mattress Protector : Double bed 8 " thick : Suit room Providing and supplying Mattress Protector as per approved make & Sample . Work complete including all type of material, fittings , fixtures,Finish, loading , unloading transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per Shop drawings ,specifications & instruction of Client/EIC.	4.00	Nos	0.00	0.00
70	Pure Shield Quilted Cotton Mattress Protector : Single bed 6 " thick : Other room " ---Do----" as per above specification for complete work.	160.00	Nos	0.00	0.00
71	BEDSHEETS WITH PILLOW COVER : (White 250 TC) : For Double bed Providing and supplying bedsheet with pillow cover as per approved make & Sample . Work complete including all type of material, fittings , fixtures,Finish, loading , unloading transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per Shop drawings ,specifications & instruction of Client/EIC.	8.00	Pair	0.00	0.00
72	BEDSHEETS WITH PILLOW COVER : (White 250 TC) : For Single bed Providing and supplying bedsheet with pillow cover as per approved make & Sample . Work complete including all type of material, fittings , fixtures,Finish, loading , unloading transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per Shop drawings ,specifications & instruction of Client/EIC.	264.00	Pair	0.00	0.00
73	Carpet : 1200 x 1800 mm Providing and supplying polyster carpet of D Decor as per approved make & Sample Work complete including all type of material, fittings , fixtures,Finish, loading , unloading ,transporation, all taxes , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per Shop drawings ,specifications & instruction of Client/EIC.	8.00	Nos	0.00	0.00
74	Signages : Providing and fixing signages comprising form ACP/ Solid wood with Acrylic leter as per instruction of Archiect/EIC. Contractor shall submit mock up sample.	27.00	Sq.mt	0.00	0.00
75	Emergency Signages : Providing and fixing emergency signages of size 300mm x 100mm comprising form 1.5mm thick photoluminescent tap on 3mm thick acrylic sheet as per instruction of Archiect/EIC. Contractor shall submit mock up sample.	10.00	Nos	0.00	0.00
76	Logo Work : Providing and fixing standard Logo using virgin acrylic or other material like Colored HDF/cementsheet /SS plate with CNC work complete as per architect selection , letters as per detailed drawings and fixed with approved adhesive with necessary fittings and provision shall be made for conceal LED light as per detail drawing. (logo size will be aprox. Size - 600 mm dia)	2.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
77	<p>Signages: 3D letters with LED : Wall Mounted</p> <p>Material : 3 mm thick exterior grade premium quality ACP sheet (0.25 mm foil thickness) & and 3D Embossed virgin acrylic/aluminum letters as per approved make and sample by Architect/ Client.</p> <p>Led Light : Rishang(Korea) and SMPS as per approved make and sample by Architect/ Client.</p> <p>The rate shall be for complete item of Designing , providing , fixing & erection , inclusive of all material, labor, wastages, necessary tools & tackles, adhesives, required hardware/accessories , any type of framing work , engraving , required civil work with finishing , LED light .</p> <p>Work complete including all type of material, fittings , fixtures,Finish, loading , unloading , transportation, , all leads ,accessories, sample mockup, all floor , all levels, all heights , etc complete as per drawings ,specifications & instruction of Client/EIC.</p>	12.00	Sq.mt	0.00	0.00
78	<p>Mirror Type 1: Providing and fixing Mirror with aluminium frame in which Aluminium frame with special deep colour anodise 40mm width and 1.3mm thickness and 5mm mirror fitted using high grade silicon. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.</p>	53.00	Sq.mt	0.00	0.00
79	<p>Mirror Type 2: Providing and fixing Mirror with aluminium frame in which Aluminium frame with special deep colour anodise 40mm width and 1.3mm thickness and 5mm mirror fitted using high grade silicon. with LED light. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.</p>	4.00	Sq.mt	0.00	0.00
80	<p>Mirror Type 3 : Providing and fixing 6 mm thick mirror of Saint Gobain/ Modiguard / Asahi as per approved make shall be fixed with SS studs. Provision shall be made for conceal led light work as per detailed drawing / instruction of architect complete. Rate shall be inclusive of frosting work as per detail drawing. Work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.</p>	51.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
81	Pot with Trolly 35 : Supply & installation of High quality rotomoulded plastic which is UV resistant, light weight yet strong and durable, frost resistance, unbreakable and easy to move , Matte finish is perfect for resisting scratches, dirt, and fingerprints. Unique bottom channel design with optional drainage holes and hidden groves/handles for easy lifting are available in this pot as per approved sample by Architect. Work complete including all type of material, fittings, fixtures, Finish, loading , unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, etc complete as per detailed drawings, specifications & instruction of Client/EIC.	16.00	Nos	0.00	0.00
82	Pots Chatura 9' : Supply & Installation of Snack Plant Pots Chatura 9' Durable plastic planter made of high-grade plastic that can be reused for years and then recycled to avoid plastic pollution. as per approved sample plant by Architect. Work complete including all type of material, fittings, fixtures, Finish, loading , unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, etc complete as per detailed drawings, specifications & instruction of Client/EIC.	30.00	Nos	0.00	0.00
83	Monstera plant : Supply & Installation of approved sample plant by Architect. Work complete including Poting mix , Expended Eca - 8 mm to 15 mm , all type of material, fittings, fixtures, Finish, loading , unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, maintenance with 30 days or more till the shrubs forms a thick etc etc complete as per detailed drawings, specifications & instruction of Client/EIC.	10.00	Nos	0.00	0.00
84	Bird of paradise Plant : Supply & Installation of approved sample plant by Architect. Work complete including Poting mix , Expended Eca - 8 mm to 15 mm , all type of material, fittings, fixtures, Finish, loading , unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, maintenance with 30 days or more till the shrubs forms a thick etc etc complete as per detailed drawings, specifications & instruction of Client/EIC.	6.00	Nos	0.00	0.00
85	Snack plant : Supply & Installation of approved sample plant by Architect. Work complete including Poting mix , Expended Eca - 8 mm to 15 mm , all type of material, fittings, fixtures, Finish, loading , unloading, transporation, all leads, accessories, sample mockup, all floor, all levels, all heights, maintenance with 30 days or more till the shrubs forms a thick etc etc complete as per detailed drawings, specifications & instruction of Client/EIC.	30.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
86	<p>Canvas painting with frame work: Providing and fixing of Panko Canvas Artwork custome printed with durable and wrinkle resistant fabric of 180 GSM , printed on HP latex 700 with 600 dpi to produe saturated colours as approved by Architect. Work complete including all necessary frame work , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	100.00	Sq.mt	0.00	0.00
87	<p>PVC Canvas painting with frame work : Providing and Fixing of PANKO PVC Canvas Artwork Custom Printed on 160GSM Media, Printed on HP Latex 700 with 600 dpi to produce saturated colours as approved by Architect/EIC. Work complete including all necessary frame work , fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	50.00	Sq.mt	0.00	0.00
88	<p>Wallpaper: Providing and supplying wall papers as approved by Architect. Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. Basic rate of wallpaper is 80 / Sq.ft</p>	10.00	Sq.mt	0.00	0.00
89	<p>Artifacts : Providing and supplying Artifacts as per selection . Glass/Metal/Fiber/Ceramic Basic rate of Artifacts is - Rs. 2500/ Nos. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	5.00	Nos.	0.00	0.00
90	<p>Artificial Planter/ indoor plant with SS finish pot as per approved sample. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	5.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
91	Metal clock : Decorative Big Size Hanging Wall Clock Battery Operated Clock : 40 x 40 cm Providing and fixing Decorative metal clock as per approved sample by Architect. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	29.00	Nos	0.00	0.00
92	Metal clock : Craftique Metal Wall Clock 75 Cm Large Size Analog Wall Clock (30 Inches), Black : Providing and fixing Decorative metal clock as per approved sample by Architect. Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	2.00	Nos	0.00	0.00
93	Dustbin (5 liter) : Providing and fixing Dustbin as per approved sample by Architect. Capacity 5 litres. Opening Mechanism Step-On Material Stainless Steel . Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	91.00	Nos	0.00	0.00
94	Dustbin (12 liter) : Providing and fixing Dustbin as per approved sample by Architect. Capacity 5 litres. Opening Mechanism Step-On Material Stainless Steel . Work complete including all necessary fittings, mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	7.00	Nos	0.00	0.00
95	Door mat : 400mm X 600mm Providing and supplying Antiskid Door mat (BATHMAT - OBSESION (DIANA) as per selection . Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	88.00	Nos	0.00	0.00
96	Door mat : 450 mm X750 mm Providing and supplying DOORMAT- SUPERLIVING (MATH WITH RUBBER BACKIN) POLYSTER/JUTE as per selection . Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	84.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
97	<p>Texture Paint : Exposed RCC look (6mm Groov Light tone & Top coat Dark tone):</p> <p>a. Preparation of surface: Make sure the surface should be free from oil, grease and all type of foreign items. Minor repairs should be make up with cement;sand mixture. Other than concrete plasters, other suitable surfaces are ply board, asbestos sheets and gyp board partitions, and all type of absorbent surfaces.</p> <p>b. Base coat*: - Apply 2 coats of LCF- Base Coat with fiber glass mesh an average thickness of 1.5-1.7mm. LCF Base Coat is a polymer modified ceramic based material bonded primarily with in-organic binders. LCF Base Coat is a dry material and water should be added in to this to make it workable.</p> <p>c. Grooving and Taping: - The dried base coat should be properly grooved or tapped as per the designs suggested by the engineers.</p> <p>d. Top Coat: - Apply the LCF- Top Coat of desired color with an average thickness of 1.7-2mm. LCF- Top Coat is a polymer modified ceramic based material with special high performance additives, in-organic binders are the primery binding medium. LCF- Top Coat is a dry material and water should be added in to it to make it workable. LCF- Top Coat can be applied in desired pattern like honey combed (to be done with special tools), trowel marked, rough cast or in smooth.</p> <p>e. Protective Sealer: - LCF- Top Coat when gets dry, apply two coats of TC-5000 (exterior grade protective sealer). TC-5000 protects the surface from dust, dirt, fungus and stains.</p> <p>Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all level, all heights as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	418.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
98	Shower Cubicles : Supply & Installation of Shower Cubicles with Fittings (Dorma make) or as per as per Architect selection & approved make. Glass to Wall Hinges (90 Deg or 135 Deg) - 2 Nos. Glass to Wall Small Brackets (90 Deg) without Back Plate - 4 Nos. Towel Rod cum Handle Bar (458mm x 205mm x 18mm) - 1 No. Water Disper Seal - 1 No. Magnetic Seal (180 Deg) - 1No. Soft Nose Seal - 1No Support Bar 40mm x 40mm Glass: 8 mm thick Door: 1no Work complete including all type of fittings, fixtures, tools, etc complete as per manufacturer specification and drawing.	113.00	Sq.mt	0.00	0.00
99	Glass Corner Shelf : Providing and fixing in position Glass Corner shelf as per approved make list and work complete including all type of accessories. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC. Bathroom Accessories for Home Decor - Pack of 2 (9x9 Inch, Glossy)	56.00	Nos	0.00	0.00
100	S.S Corner Shelf : Providing and fixing in position S.S Corner shelf as per approved make list and work complete including all type of accessories. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC. Plantex Bathroom Corner Shelf for Wall Mount/304 Grade Stainless Steel Corner Shelf for Bathroom with Railings/Bathroom Accessories Holder (9x9 inches, Chrome)	24.00	Nos	0.00	0.00
Total Amount					0.00
C	Part-3				
101	Shaving Mirror : Providing and fixing in position Round Mirror as per approved make list and work complete including all type of accessories. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC. Wall Mount Stainless Steel 5X Magnifying Shaving Makeup Round Mirror (Silver, 8 Inch) Framed	4.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
102	<p>Bathroom S.S Shelf : Providing and fixing in position Stainless Steel 304 Grade Shelf as per approved make list and work complete including all type of accessories. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC.</p> <p>Plantex Stainless Steel 304 Grade Shelf for Bathroom/Storage Organizer for Bathroom/ Kitchen Rack - Bathroom Accessories - Pack of 1 (12x5 Inch, Chrome)</p>	4.00	Nos	0.00	0.00
103	<p>Ceramic Bathroom Accessories Set of 4 : Providing and fixing in position Ceramic Bathroom Accessories Set of 4 as per approved make list and work complete including all type of accessories. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC.</p> <p>Kookee Ceramic Bathroom Accessories Set of 4, Modern Bath Set with Liquid handwash Soap Dispenser and Toothbrush Holder, Luxury Gift Accessory for Home, Grey/Gold (8684)</p>	4.00	Nos	0.00	0.00
104	<p>Ceramic Bathroom Accessories Set of 3 : Providing and fixing in position Ceramic Bathroom Accessories Set of 3 as per approved make list and work complete including all type of accessories. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC.</p> <p>Ceramic Bathroom Accessories Set of 3, Modern Bath Set with Liquid handwash, Soap Dispenser and Toothbrush Holder, Luxury Gift Accessory for Home Rust-Proof (White Strip Bathroom Set)</p>	24.00	Nos	0.00	0.00
105	<p>Towel Rack: Providing and fixing in position Towel Rack as per approved make list and work complete including all type of accessories. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC. Model Equivalent to Jaquar code ACNCHR-1181S, TOWEL RACK 600MM LONG WITH LOWER HANGERS STAINLESS STEEL</p>	28.00	Nos	0.00	0.00
106	<p>DOUBLE HOOK: Providing and fixing in position DOUBLE HOOK as per approved make list and work complete including all type of accessories. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC. Model Equivalent to Jaquar code ACNCHR-1161N</p>	93.00	Nos	0.00	0.00
107	<p>Rugs: Providing and fixing in position Rugs as approve by architect/EIC. and work complete including all type of accessories. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads,etc complete as per detailed drawing & Instruction of Architect/EIC.</p> <p>Luxe Home Runner Super Soft Non Slip Vegas Rugs for Bedroom (2x5 Ft, Fuscia) Pack of 1</p>	4.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
108	<p>Railing Finishing work: Sand Stone work for diff. elements: Providing and fixing of Railing top patta from Pink sand / Red sand stone of approved quality, selected and sorted for uniform color & texture, engraving , carving , laser cutting etc., of specified sizes as per drawing .Stone is to be laid over polymer modified mortar(stone adhesive) of saint gobain or as per approved make , average 20 mm thickness bedding , with joints, pointing and finishing and filling the grooves with polymer modified mortar , including curing and cleaning with wire brush to remove excess cement on the sides of stone up to the satisfaction of the Architect & Engineer-in-charges etc. complete. Loose and laid sample shall be approved by Architect and EIC before execution.Contractr shall submitt Shop drawing for all type of design elements for approval of Architect/ EIC before execution.</p> <p>a). Railing Top finishing patta</p>	4.00	Cu.mt	0.00	0.00
109	<p>Providing and applying PPG paint on existing MS railing as per approved make & sample by Architect/EIC.</p> <p>Application method:</p> <p>First Coat - primer : Amerlock 400 THINNER Thinner 91-92</p> <p>Second Coat - Epoxy High build Sigmashield 880 THINNER : Thinner 91-92</p> <p>Third Coat - Epoxy High build : Sigmashield 880 THINNER Thinner 91-92</p> <p>Work complete including remove of existing paint , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all level, all heights as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	379.00	Sq.mt	0.00	0.00
110	<p>Dismantling all type of tiles flooring, or stone flooring laid in mortar, any type of flooring with mortar, waterproofing, including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.</p>	246.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
111	Dismantling all type of wall tiles, dado and any type of (stone/ tiles) cladding laid in mortar, any type of flooring with mortar, waterproofing, including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	87.00	Sq.mt	0.00	0.00
112	Vitrified Tile Flooring : Providing and laying Vitrified tiles flooring using minimum 10 mm thick tiles of as per approved make list by architect/client, including preparing base for leveling with 20mm thick cement mortar 1:6 (1 cement : 6 coarse sand) OR Cement based high polymer modified quick-set tile adhesive (Water based) and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction and approval by architect. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning, protection sheet, at all floor, all level, all depth, all Height, all lead and lift , work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. (A) Tile size: 1200 x 600 mm Basic rate of tile is Rs. 40/Sqft	491.00	Sq.mt	0.00	0.00
113	Vitrified Tile Skirting : Providing and laying Vitrified tiles in skirting using minimum 10 mm thick tiles as per approved make list by architect /client fixed in dado on 10 mm th. Cement plaster 1:3 (1 cement: 3 coarse sand) OR Cement based high polymer modified quick-set tile adhesive (Water based) All surfaces must be dimensionally stable according to level, cured, undamaged, compact,rigid,resistant, dry and free from any debonding agents tiles fixed by approved tile adhesive and all application shall be done under instruction of manufacturer guideline and specification , and jointed with 3mm thick epoxy grouting as per approved make of approved shade and colour in proper line and level as per detailed drawing / instruction all complete as per approved sample by Architect, drawings and instruction of EIC. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning , at all floor, all level, all depth, all Height, all lead and lift, work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. (A) Tile size: 1200 x 600 mm Basic rate of tile is Rs. 50/Sqft	174.00	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
114	Fabricated work: Providing Fabrication & erection of steel structure as per drawings including materials, consisting of plates, rolled steel joists, channels, angles, chequered plates etc and also rectangular / square hollow steel sections, insert plates in RCC/Brickwork, anchor bolts for steel structure, sleeve pipes, anchor nuts, washers etc, straightening of raw steel if required, fabrication of steel structures with primer and minimum two coats of anti corrosive matt finish paint including preparation of supplementary sketches and detailed bill of materials supply of bolts, nuts, washers, shims, packs, putty. gas, welding electrodes and all other consumables, as required and carrying out surface preparation all complete. The scope includes loading, transportation ,unloading and delivery and erection site of all fabricated structures,, alignment and welding of all structures true to line, level, plumb and dimension, including rectification if any, splicing, site assembly all as per technical specifications and drawings, ,all complete.Contactror shall provide stability certificate for the fabrication structure. Rate inclusive of shop drawing.	2547.00	KG	0.00	0.00
115	SS WORK TABLE WITH 2 U/S (304), Size (mm) : 525 x 600 x 850 + 150, Make: JANSHAKTI , Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	3.00	Nos	0.00	0.00
116	SS TWO BR. GAS RANGE WITH 1 U/S (304) CI JALI : 350 x 350mm, Size (mm) : 1125 x 600 x 850 + 150 mm, Make: JANSHAKTI, Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
117	SS THREE BR. GAS RANGE WITH 1 U/S (304), CI JALI : 350 x 350mm Size (mm) : 1550 x 600 x 850 + 150 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
118	SS WORK TABLE WITH SINK & 1 U/S (304) SINK SIZE : 400 x 400mm WITH FAUCET, Size (mm) : 600 x 1000 x 850 + 150 mm Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
119	SS WORK TABLE WITH SINK & 1 U/S (304), SINK SIZE : 400 x 400mm WITH FAUCET, Size (mm) : 1300 x 600 x 850 + 150, Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
120	SS DOSA PLATE WITH 1 U/S (304) Size (mm) : 900 x 600 x 850 mm Make: JANSHAKTI, Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
121	SS WORK TABLE WITH 2 U/S (304) Size (mm) : 900 x 600 x 850 + 150 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
122	IDLI STEAMER - GAS OPERATED CAP- 72 IDLIS Size (mm) : 450 x 525 x 410 + 250 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
123	SS TWO BR. STOCK POT STOVE (304) Size (mm) : 1500 x 600 x 450 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
124	SS STOCK POT STOVE (304) Size (mm) : 585 x 600 x 450 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
125	SS SINGLE SINK UNIT WITH CROSS BRACING (304) SINK : 450 x 450mm WITH FAUCET, Size (mm) : 585 x 600 x 850 + 150 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	3.00	Nos	0.00	0.00
126	SS 8 GN PAN CONT. MASALA TROLLEY (304) Size (mm) : 515 x 720 x 850 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
127	SS WORK TABLE WITH 2 U/S (304) Size (mm) : 1350 x 600 x 850 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
128	SS WORK TABLE WITH 2 U/S (304) Size (mm) : 1350 x 600 x 850 Make: JANSKAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
129	SS WORK TABLE WITH 2 U/S (304) Size (mm) : 750 x 600 x 850 + 150 Make: JANSKAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
130	SS CHAPATI HOT PLATE WITH BULLET PUFFER & 1 U/S (304) Size (mm) : 1200 x 600 x 850 Make: JANSKAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
131	SS CHAPATI HOT PLATE WITH BULLET PUFFER & 1 U/S (304), Size (mm) : 900 x 600 x 850, Make: JANSKAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
132	SS STONE TOP TABLE WITH 2 U/S (304) Size (mm) : 1125 x 600 x 850 Make: JANSKAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
133	SS STONE TOP TABLE WITH 2 U/S (304), Size (mm) : 1125 x 700 x 850, Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
134	SS WORK TABLE WITH 2 U/S (304) Size (mm) : 1125 x 600 x 850 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
135	DOUGH KNEADER - 10 KG HEAVY DUTY Size (mm) : 950 x 475 x 875 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
136	FOUR DOOR VERTICAL CHILLER Size (mm) : 1200 x 818 x 1990 Make : HOSHIZAKI Model : HRWH-127MS4 Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
137	SS WORK TABLE WITH 2 U/S (304) Size (mm) : 1500 x 600 x 850 + 150 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
138	MICROWAVE OVEN - 25 LTRS Size (mm) : 511 x 311 x 432 Make : BUTLER Model : MWO-25 Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
139	SS WORK TABLE WITH 2 U/S (304) Size (mm) : 1800 x 600 x 850 + 150 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
140	INDUCTION TABLE TOP - 3.5 KW Size (mm) : 410 x 380 x 95 Make : STELLA Model : TS-3501 Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
141	SANDWICH GRILLER - JUMBO Size (mm) : 360 x 480 x 235 Make : HOTPRO Model : SG-202 Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
142	SS WORK TABLE WITH SINK & 1 U/S (304) SINK SIZE : 400 x 400mm WITH FAUCET Size (mm) : 1800 x 600 x 850 + 150 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
143	POP UP TOASTER - 6 SLICES Make : BUTLER Model : POP-06 Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
144	GLASS TOP DEEP FRIDGE - 310 LTRS Size (mm) : 1122 x 708 x 883 Make : BLUESTAR Model : CF5-330NEYW Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
145	SS STORAGE RACK WITH 4 SHELVES (304) Size (mm) : 1350 x 400 x 1550 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	9.00	Nos	0.00	0.00
146	SS STORAGE RACK WITH 4 SHELVES (304) Size (mm) : 1125 x 400 x 1550 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	5.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
147	SS DUNNAGE RACK (304) Size (mm) : 1125 x 600 x 200 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
148	SS DUNNAGE RACK (304), Size (mm): 1500 x 600 x 200, Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
149	WEIGING SCALE - 500KG Size (mm) : 600 x 600 Make : SWISSER Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
150	SS ONION / POTATO BIN (304) Size (mm) : 600 x 600 x 900 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	4.00	Nos	0.00	0.00
	Total Amount				0.00
D	Part-4				
151	SS WORK TABLE WITH SINK & 1 U/S (304) SINK SIZE : 400 x 400mm WITH FAUCET, Size (mm) :2100 x 700 x 850 + 150 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
152	SS WORK TABLE WITH SINK & 1 U/S (304), SINK SIZE : 450 x 450mm WITH FAUCET, Size (mm) :2100 x 700 x 850 + 150, Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
153	SS WORK TABLE WITH SINK & 1 U/S (304) SINK SIZE : 450 x 450mm WITH FAUCET, Size (mm) : 1550 x 600 x 850 + 150, Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
154	SS WORK TABLE WITH 2 U/S (304), Size (mm) : 2100 x 700 x 850 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
155	PLASTIC ROUND BIN WITH LID - 80 LTR Size (mm) : 555 x 505 x 615 Make : NILKAMAL Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
156	SS VEGETABLE CRATE HOLDING TROLLEY (304) WITH CRATE - 5 NOS., Size (mm): 445 x 565 x 1720 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
157	SS PLATFORM TROLLEY (304) Size (mm) : 900 x 600 x 850 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
158	PULVERISER - 5.0 HP Size (mm) : 460 x 360 x 680 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
159	TILTING TYPE WET GRINDER - 10 LTR - STD. Size (mm) : 675 x 475 x 1150 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
160	POTATO PEELER MACHINE - 10 KG HEAVY DUTY Size (mm) : 825 x 550 x 750 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
161	SS POT RACK WITH 4 SHELVES (304) Size (mm) : 1445 x 585 x 1550 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	3.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
162	SS SOILED DISH LANDING TABLE WITH CROSS BRACING & GARBAGE CHUTE (304) Size (mm) : 1800 x 675 x 850 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
163	SS SOILED DISH LANDING TABLE WITH CROSS BRACING & GARBAGE CHUTE (304), Size (mm) : 1500 x 675 x 850, Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
164	SS THREE SINK UNIT WITH CROSS BRACING (304) SINK SIZE : 450 x 450mm WITH FAUCET, Size (mm) : 1550 x 600 x 850 + 150, Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
165	SS WORK TABLE WITH 2 U/S (304) Size (mm) : 600 x 600 x 850 + 150 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
166	SS PLATE RACK WITH 4 SHELVES (304) Size (mm) : 1125 x 400 x 1550 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
167	SS PLATE RACK WITH 4 SHELVES (304), Size (mm) : 1350 x 400 x 1550, Make: JANSKAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
168	SS PLATE COLLECTION TROLLEY (304) Size (mm) : 1300 x 600 x 850 Make: JANSKAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
169	SS PLATE COLLECTION TROLLEY (304), Size (mm) : 1125 x 600 x 850, Make: JANSKAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
170	VISI COOLER - 500 LTRS Size (mm) : 583 x 695 x 2060 Make : WESTERN Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
171	SS 6 CONT CANTEEN BAIN MARIE WITH SNEEZE GUARD & 3 SIDE COVERING WITH SERVICE RAIL & 1 U/S (304) GN PAN - 1 /1 x 150 mm- 6 NOS Size (mm) : 2250 x 625 + 225 x 850 Make: JANSKAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
172	CASE ROLL Size (mm) : 15 LTR Make: JANSKAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
173	SS SERVICE TABLE WITH 3 SIDE COVERING & 1 U/S & SERVICE RAIL WITH SNEEZE GUARD & AMBIENT (304) GN PAN 1/2 x 150 mm -2 NOS Size (mm) : 1500 x 625 + 225 x 850 Make: JANSKAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00
174	WATER COOLER - 80 Ltrs MODEL- SWCSDLX6080UVE SDLX6080 AQUAGARD RO ECO Size (mm) : 665 x 480 x 1210 Make : BLUESTAR Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
175	SS PLATE COLLECTION TROLLEY WITH CRATES (304) Size (mm) : 900 x 600 x 850 Make: JANSKAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
176	SS SOUP CATTLE - 10 Ltrs Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
177	GAS LINE WITH TESTING & INSTALLATION Size (mm) : 100 SQ. FT. Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Job	0.00	0.00
178	SS EXHAUST HOOD WITH FILTER (304) FOR STOCK POT STOVE, Size (mm) : 3000 x 750 x 525 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Job	0.00	0.00
179	SS EXHAUST HOOD WITH FILTER (304) FOR STOCK POT STOVE, Size (mm) : 2400 x 750 x 525 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Job	0.00	0.00
180	SS EXHAUST HOOD WITH FILTER (304) FOR IDLI STEAMER & THREE BURNER, Size (mm) : 2400 x 750 x 525 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Job	0.00	0.00
181	SS EXHAUST HOOD WITH FILTER (304) FOR TWO BURNER & CHAPATI PUFFER, Size (mm) : 1200 x 750 x 525, Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Job	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
182	SS EXHAUST HOOD WITH FILTER (304) FOR DOSA PLATE, Size (mm) : 900 x 750 x 525 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Job	0.00	0.00
183	SS EXHAUST HOOD WITH FILTER (304) FOR CHAPATTI PUFFER, Size (mm) : 900 x 750 x 525 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	1.00	Job	0.00	0.00
184	G.I DAMPER Size (mm) : 300 x 300 Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	20.00	Nos	0.00	0.00
185	G.I DUCTING Size (mm) : 500 SQ. FT. APX. Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Job	0.00	0.00
186	EXHAUST BLOWER Size (mm) : 5.0 HP Make: JANSHAKTI Work complete including supplying & fixing, fittings, fixtures, Finish, loading , unloading, transporation, all leads,accessories, sample mockup, all floor, all levels, all heights etc complete as per drawings, specifications & instruction of Architect/EIC.	2.00	Nos	0.00	0.00
	Total Amount				0.00
E	Part-5 (Rate only item)				

Sr. No.	Item Description	Qty	Unit	Rate	Amount
187	<p>Veneer panelling: Providing & fixing 12mm thick fire retardant marine plywood as per IS 710:2010 and IS 5509:2000 fixed on frame work finish with 4mm thick Veneer & matt finish monocoat polish. The frame work shall be made from square hollow aluminium anodised section size of 50x50x1.5 mm & 25x50x1.5 mm of approved make conforming to IS code. The framework shall be fixed as per drawing vertically @ 600 mm c/c & horizontal 600 mm c/c horizontally. All ply/wooden shall be treated with anti- termite treatment .</p> <p>Measurements for paneling work to be recorded upto finished false ceiling level only irrespective of aluminium frame work, which shall be provided from gr. level to RCC slab / beams soffit level. Rates shall also be inclusive of cost of making CNC/engraving /cut outs/ openings for electrical fixtures, tube lights /air-conditioners ,grills, diffusers etc & providing additional sections for strengthening around the openings/cutouts additional support for fixing of patch fittings for doors, making grooves between wall & board, in filled with termite treated wooden members if required or as per drawing /instruction of EIC. and no extra payment shall be considered for additional sections provided. All curved surfaces, recesses, waffles shall be part of the paneling including openable shutter wherever required area and finished with the same material.Work complete including all type of material, fittings , fixtures, Finish, loading , unloading , transportation, all leads ,accessories, groove, adhesive ,tape, headless nails, sample mockup, all floor , all levels, all heights etc complete as per detailed drawings ,specifications & instruction of Client/EIC. only the clear elevation area of finished plywood wall paneling with Veneer shall be measured and paid. sample mock shall be approved from Architect/Client. Basic rate of veneer is 120/ Sq.ft</p>	Rate Only	Sq.mt	0.00	0.00
188	<p>Lacquered glass / Coloured glass Panelling : " -----Do-----" as per above item specification for complete work . using 4mm thick coloured magnetic glass / Coloured glass for panelling work, as per approved by Architect/Client. The rate shall be for all floors, at all heights, all shapes including all costs.</p>	Rate Only	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
189	<p>Accoustic Panelling : 12 mm thick Board - Providing and fixing wall acoustical panelling with using CS55 and IC91 framing directly to the wall and then fixing 12.5mm perforated board with the help of screw and using rockwool of 50kg density and 50MM thick between framing and perforated sheet then Fixing Ecotone make Marco polyester fiber acoustic wallpaneling with the specification of 9MM thick having density of1.90kg/m2 with NRC value of 0.80 surface matt finish which is fixed with solution SR505 asrequired. The panel should have euro class BASTME84-13 fire rating. The color shade of Panel as approved by Architect. Including all accessories, material & labor complete as directed by Engineer. Including surface preparation, Including cost of all type of tools, tackles, all labour, scaffolding, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. etc. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. Only the clear elevation area shall be measured and paid."</p>	Rate Only	Sq.mt	0.00	0.00
190	<p>Centre table Type 1: Centre table two nos unit pair - 1 unit- 800 mm top & 380 mm ht /2 unit- 500 mm top & 500 mm ht (size may be vary as per slection by 100 -200 mm) Supplying and placing centre table as per approved selection by Architect/ Client. Equivalent make as per approved make list .Table top finish as per selection Work complete including all necessary hardware and fittings , mock up sample, loading,unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. basic rate of table Rs. 25,000/-Pair</p>	Rate Only	Pair	0.00	0.00
191	<p>Corner table Type 1: - 500mm top & 480 mm ht (size may be vary as per slection by 100 -200 mm): Supplying and placing corner table as per approved selection by Architect/ Client. Equivalent make as per approved make list .Table top finish as per selection Work complete including all necessary hardware and fittings , mock up sample, loading,unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client. basic rate of table Rs. 12,000/-Nos</p>	Rate Only	Nos.	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
192	Sofa (One Seater) : @ 900(L) x 870 mm (B) x 800 mm (H) comprising up of Solid teak wood with PU semi gloss finished polish. The seat shall 150 mm th 40 density & back shall be 32 density foam & finished in Approved fabric upholstery as per the drawing/image and instruction from Architect/EIC all external & internal exposed woodwork to be finished in PU semi gloss finish polish. .The work shall be done as per drawing , specifications, sample approved and as directed by the Architect and Engineer-in-charge. The rate shall be for complete item inclusive of all material, labour, wastages, necessary tools & tackles,approved make for all floors, all heights, all levels and all places within campus. Contractor shall do all the needful and shall fulfill Architect's design intent. No additional claims will be entertained for this.Rate shall inclusive of providing mockup sample for approval of architect. Basic Rate of Fabric : 800 Rmt	Rate Only	Nos	0.00	0.00
193	Sofa (two Seater): 1500mm (L) x 870 mm (B) x 800 mm (H) "-----Do-----" as per above specification for complete work. Basic Rate of Fabric : 800 Rmt	Rate Only	Nos	0.00	0.00
194	Sofa (three Seater): 2100mm (L) x 870 mm (B) x 800 mm (H) "-----Do-----" as per above specification for complete work. Basic Rate of Fabric : 800 Rmt	Rate Only	Nos	0.00	0.00
195	Planter box: Providing making, fixing as per detail drawing and required length and depth shall be made from 19mm IS 710 BWP ply with both side laminate finish and providing lighting arrangement cutout and fixing as per detail drawing and instruction. Rate shall inclusive all necessary hardware and fitting, ms framing, paint. The work shall be done as per the specifications, sample approved and as directed by the Architect/ Client. Rate shall inclusive of providing mockup sample for approval of Architect/ Client. Rate shall be inclusive of all materials, loading, unloading, transportation, placing at all floors and for all leads, polishing and all accessorie, sample mockup etc as described in item description.work complete as per the instruction of Client/EIC.	Rate Only	Sq.mt	0.00	0.00
196	Chair Type-4A -Model equivalent make - Amardeep Lotus 02 Mid Back * Chair with Frame in MS. * PU Foam in Back & Moulded PU Seat.* PU Arms with PU Cladding. * Synchronized Multi Lock Mechanism.* Chrome Base & Gas Lift. Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.	Rate Only	Nos	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
197	<p>Puffy : Providing & Fixing of Puffy as per approved sample by Architect. Make : Solidwood , Structure : Solidwood , Finish : Fabric Finish (Basic Rate of Fabric is Rs 800 Per Meter) Leg : Wooden Leg Finish : Approved Shade Polish on Wooden Leg Work complete including all necessary fittings , mock up sample, loading, unloading, transportation, placing at all floors and for all leads, all accessories as described in item description. Work complete as per the detailed drawing and instruction of Architect/Client.</p>	Rate Only	Nos	0.00	0.00
198	<p>Signages : Providing and fixing signages comprising form 45mm aluminum profile with back side UV printed PC as per instruction of Architect/EIC. Contractor shall submit mock up sample.</p>	Rate Only	Sq.mt	0.00	0.00
199	<p>Aluminium Fins/Louvers (Elevation): Supplying and Installing of METALIUMTM make U- Shaped Baffle 50*50*50mm (50mm gap) Galvanized Steel 0.50mm TCT plain wooden powder coating on visible surface of Panel and supporting structure in black color Exterior Louver System.</p> <p>Panel (Galvanized Steel): Metalium make square edge P-50 series panels, 50 * 50 * 50 mm& 0.50 mm TCT Galvanized Steel. Panel length is up to approx. 3 mtr. Panels shall be wooden powder coated on visible surface with special Exterior Grade powder to enhance property of Fadedness Resistivity.</p> <p>P-50 Carrier (U Shaped): Black enameled Galvanized Steel Carrier of 20mm wide at bottom x 39mm deep x 0.6 mm thick in a standard length of 8' with cutouts to hold the panel in a module of 100 mm centre to centre at a distance of 1 mtr. Carrier and suitable structure shall be powder / coil coated on exterior face to enhance properties of Fadedness and corrosion resistivity.</p> <p>Installation Details: GS Clit shall be fixed on vertical columns with dash fasteners at distance not more than 1 mtr. Centre to centre on which Tubular Stud sections will be laid with corrosion proof screws and on this rigid structure carrier shall be fixed vertically / horizontally at distance of 1 mtr. Centre to centre. Panel shall be clipped to carriers. Rate shall inclusive of mock up sample, all materials, loading, unloading, transportation, placing at all floors and for all leads, all accessories , Scaffolding etc as described in item description. Work complete as per the detailed drawing , mockup sample and instruction of Architect/Client.</p>	Rate Only	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
200	Single Leaf Flush Door finish with veneer polish: Providing and fixing in position 35 mm thick BWP grade single leaf flush doors of approved make and finished with both side 4 mm thick veneer as approved sample. including Hardware system of SS 304 Grade like Hinges, Mortise lock with knob, door closer, door stopper etc. as per approved make & Sample. work complete including all type of hardware, fittings, fixtures as per instruction of Client/ Architect etc. work completed including mock up sample, all materials, loading, unloading, transportation, placing at all floors and for all leads, at all floors, all levels, all heights and all shapes, all accessorie, protection sheet etc. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. (Note: Door opening area shall be measured for payment. No extra payment shall be paid) Basic rate of veneer is 120/ Sq.ft	Rate Only	Sq.mt	0.00	0.00
201	Demolition of brick work & stone masonry with any type of plaster, paint, skirting, dedo etc. including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools, tackles,scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (III) In cement mortar.	Rate Only	Cu.mt	0.00	0.00
202	Demolition of any type of R.C.C work with TMT bars, any type of plaster, paint, skirting, dedo etc. including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. work complete including all type of tools,tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (I) R.C.C work.	Rate Only	Cu.mt	0.00	0.00
203	Earthwork in excavation by mechanical means (All type of soil) for foundation, footings, walls, retaining walls, rafts, trenches, drains, lift pits, underground sumps, tank, septic tanks, soak well, Box cutting etc. including dewatering the sub-soil water from any source and rain water to keep the excavation dry, removal of slush, dressing of sides and ramming of bottoms, planking, shoring & strutting, removal & disposal of surplus excavated material with all lead & lift. including compaction by using mechanical plate compactor / vibro roller, finished to desire levels all as per excavation plan and foundation drawings to get Modified Proctor Density test (MPD) of 95%., work including mechanical transport inclusive of royalty, statutory fees all permissions & any other incidental expenses etc. complete. i) Up to 1.5 Mtr Depth	Rate Only	Cu.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
204	Filling available excavated earth in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering. Rate to include cost of compaction to achieve at least 95% Proctor Density of refilled excavated earth. Work shall complete as per the instruction of EIC. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	Rate Only	Cu.mt	0.00	0.00
205	Filling in plinth with sand under floors including watering ramming, consolidating and dressing complete. work complete including all type of tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC.	Rate Only	Cu.mt	0.00	0.00
206	Providing and laying cement concrete 1:3:6 (1- Cement : 3- coarse sand : 6- hand broken stone aggregates 40 mm nominal size) and curing complete including mixing laying, vibrating, consolidating, leveling and curing etc. complete with all labours and materials with formwork. The item includes finishing the top surface with trowel. Work complete including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels etc complete as per instruction of Architect/EIC. (A) Foundation and Plinth	Rate Only	Cu.mt	0.00	0.00
207	Providing and laying controlled cement concrete M.250 and curing complete. including mixing laying, vibrating, consolidating, leveling and curing etc. complete with all labours and materials with formwork. The item includes finishing the top surface with trowel, necessary admixtures etc. Work complete including all type of tools, tackles, labours, formwork, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC. (excluding the cost of reinforcement) (A) Foundations, footings, columns, Slabs, landing, shelves, Balconies, Lintels, Beams, Girders and Cantilever upto floor two level.	Rate Only	Cu.mt	0.00	0.00
208	TMT Bars: Providing, straightening, cutting, bending, binding and laying in position of TMT FE 500/500D grade steel reinforcement confirming to IS 1786 : 1990 or latest code, to correct all shape and size as per detailed drawings, specifications for all RCC work etc, at all levels and all heights with necessary chairs and laps; with correct size PVC cover blocks or approved quality concrete cover blocks of same grade of concrete and binding wire of 18 gauge etc. complete with test certificate of the steel bars from manufactures as well as approved laboratory test certificates directed by Engineer in charge, etc. complete. Rate shall be inclusive of binding wire, cover, lap, chair etc. Work shall complete up to any levels, all floor & as per the instruction of EIC.	Rate Only	kg	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
209	Providing and laying Half brick masonry in common burnt clay building bricks having crushing strength not less than 35 Kg./Sq. Cm. in cement mortar 1:4 (1 cement : 4 coarse sand) in superstructure - at all floor levels including proper filling of all masonry joints, curing etc. complete. Work complete including all type of tools, tackles, scaffolding etc complete as per instruction of Architect/ EIC. The rate includes providing and placing in position 2 Nos 6 mm dia bars at every third course of masonry work.	Rate Only	Sq.mt	0.00	0.00
210	15 mm thick cement plaster : Providing and laying average 15 mm. thick single coat smooth finishing using steel float (mala finish) plaster in CM 1:4 (1 cement : 4 coarse river sand), on brickwork, RCC work, blocks, sills, soffits, jambs etc. at all floors, all levels, all heights, all shapes and for all sizes with necessary scaffolding, curing, chicken mesh at the junction of masonry & RCC work using screw / dhoba nails, making moulded, grooves, drip moulds, tapak, chemical bonding agent etc., for all lead, lift, height and levels etc., complete as per specification and as directed by the EIC. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC.	Rate Only	Sq.mt	0.00	0.00
211	20 mm thick Sand Faced Plaster: Providing and applying 20mm thick sand faced plaster (Using Wooden Gutka/Float) to all external surfaces at all levels and in any shape, in two coats, 12 mm thick average base coat in cement mortar 1:5 and 8mm thick finish coat in cement mortar 1:2 using fine sand for finish coat, including preparation of surface to uniform texture, staging, double scaffolding, curing, chicken mesh at the junction of masonry & RCC work using screw / dhoba nails, making moulded, grooves, drip moulds, tapak etc., complete as per specification and as directed by the EIC. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC.	Rate Only	Sq.mt	0.00	0.00
212	Applying two coats of Birla (white cement based) or Asian (acrylic lapy- putty) or equivalent & two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth. including all type of material, labour, tools, tackles, scaffolding, safety measures, loading, unloading, transportation, at all floors, all heights, all levels, all leads and lifts etc complete as per instruction of Architect/EIC.	Rate Only	Sq.mt	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
213	Interior paint for wall & Ceiling: wall painting (two coats) with plastic emulsion paint of approved brand and manufacture on undecorated wall surface to give an even shade including throughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth. Including cost of all type of tools, tackles, all labour, materials, transportation, cleaning , at all floor, all level, all depth, all Height, all lead and lift , performance waranty certificate etc. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	Rate Only	Sq.mt	0.00	0.00
214	Finishing wall with weather proof exterior emulsion paint on wall surface (two coats) to give an required shape even shade after thoroughly brushing the surface to remove all dirt, and remains of loose powdered materials. etc complete	Rate Only	Sq.mt	0.00	0.00
215	<p>Carring out plinth treatment to post construction / existing structure by spraying chemical solution for termite control treatment including labour and material consistment with I.S.I specification. Using Chlordene and Chiorpurfiles 20 EC. As Per 6131_paret-II Consentracion Weight one percent is recommended i.e one litre 20 EC chemical emulsion with 19 liter give 1 % concnentracion inclusive of one litre chemical emulsion appication at the rate of 5 Litre chemical / Sqm of surface is recommended as per I.S.</p> <p>The whole work is to be executed through specialized agency with a guarantee of 5 (Five) years given on a prescribed proforma duly stamped. The termite control treatment work 10% will be retained from the billing amount for 5 years (without interest). The amount shall be refunded after Five years without interest. work complete including all type of tools , tackles, scaffolding, safety measures etc complete at any level and height. work complete as per the instnuction of EIC/Architect. Including cost of all type of tools, tackles, all labour, materials, scaffolding, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample, specifications and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.</p>	Rate Only	Sq.mt	0.00	0.00
216	Providing and laying polished Kota stone slab flooring over 20mm (Average) thick base of cement mortar 1:6 (1-cement : 6- coarse sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of slab including rubbing and polishing etc. complete. Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC. (A) 25mm thick	Rate Only	Sqm	0.00	0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
217	Providing and laying polished kota stone slab 25mm thick in risers of steps,skirting Dedo and pillars laid on 10mm thick cement mortar 1:3 (1-Cement : 3 coarse sand) and jointed with gray cement slury mixed with pigment to match the shade of slab including rubbing and polishing etc. complete. Including cost of all labour, materials, safety measures, loading, unloading, transportation, cleaning, at all floor, all level, all depth, all Height, all lead and lift etc. complete as per instruction of Architect/EIC. work complete as per the detailed drawing, approved sample and instruction of Architect/EIC. Sample mock shall be approved from Architect/EIC.	Rate Only	Sqm	0.00	0.00
218	Three track sliding window : Domal section : 27x65 mm series Supply & Fixing of Aluminium sliding window with powder coated as per by approved make & sample by architect/EIC. Track section: 45 x 80x 1.5 mm, Shutter section : 27x 65 x 1.4 mm, Glass : 5 mm thick reflective toughened glass of saint gobain or approved make list Work including Trolley Wheel (Bearing), EPDM Gasket, Woolen In Shutter, Concealed Lock, Anti Rattling Guide, Lock Guide, handle Antilifting, Shutter Corner Clit, Shutter wing Connector, Interlock EPDM Gasket, Interlock Guide, Anti Capillary Pad, Bush Bottom silicon all side & All Necessary Hardware etc. complete as per detailed drawings, mock sample and specifications.	Rate Only	Sqm	0.00	0.00
219	Fixed Glass Aluminium Window: Domal section : R40 mm series Supply & Fixing Fixed glass window Comprising from Domal section series R40 mm series with powder coated as per approved make & sample by Architect/EIC. Frame section: 40 x 39.4 x 1.25 mm Glass : 5 mm thick clear reflective toughened glass of saint gobain or approved make list including EPDM Gasket and All Necessary Hardware etc. complete as per detailed drawings, mock sample and specifications.	Rate Only	Sqm	0.00	0.00
	Total Amount				0.00

Sr. No.	Item Description	Qty	Unit	Rate	Amount
---------	------------------	-----	------	------	--------

Sr. no.	Summary Sheet				Amount
A	Sub Total : Part - 1				0.00
B	Sub Total : Part - 2				0.00
C	Sub Total : Part - 3				0.00
D	Sub Total : Part - 4				0.00
E	Sub Total : Part - 5 (Rate only item)				0.00
	Grand Total Amount (Rs.)				0.00

GST Extra as per Govt. Norms